1. GENERAL

1.1 Summary

- .1 Section Includes:
 - .1 Thermal insulation for piping and piping accessories in commercial type applications.

1.2 References

- .1 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
 - .1 ASHRAE Standard 90.1-10(R2011), Energy Standard for Buildings Except Low-Rise Residential Buildings (IESNA co-sponsored; ANSI approved; Continuous Maintenance Standard).
- .2 ASTM International (ASTM)
 - .1 ASTM B 209M-10, Standard Specification for Aluminium and Aluminium Alloy Sheet and Plate (Metric).
 - .2 ASTM C 335-10(E2011), Standard Test Method for Steady State Heat Transfer Properties of Horizontal Pipe Insulation.
 - .3 ASTM C 411-11, Standard Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation.
 - .4 ASTM C 533-11, Calcium Silicate Block and Pipe Thermal Insulation.
 - .5 ASTM C 547-11, Mineral Fiber Pipe Insulation.
 - .6 ASTM C 921-10, Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation.
- .3 Canadian General Standards Board (CGSB)
 - .1 CGSB 51-GP-52Ma-89, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.
 - .2 CAN/CGSB-51.53-95, Poly (Vinyl Chloride) Jacketting Sheet, for Insulated Pipes, Vessels and Round Ducts
- .4 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .5 Thermal Insulation Association of Canada (TIAC)
 - .1 Best Practices Guide.
- .6 Underwriters' Laboratories of Canada (ULC)

- .1 CAN/ULC-S102-10, Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
- .2 CAN/ULC-S702-09, Standard for Mineral Fibre Thermal Insulation, for Buildings

1.3 Definitions

- .1 For purposes of this section:
 - .1 "CONCEALED" insulated mechanical services in suspended ceilings and non-accessible chases and furred-in spaces.
 - .2 "EXPOSED" will mean "not concealed" as specified.
- .2 TIAC Codes:
 - .1 CRF: Code Rectangular Finish.
 - .2 CPF: Code Piping Finish.

1.4 Submittals

- .1 Submittals: in accordance with Section 01 33 00 Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit one copy of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 Submittal Procedures.
- .3 Shop Drawings:
 - .1 Submit shop drawings in accordance with Section 01 33 00 Submittal Procedures.
- .4 Quality assurance submittals: submit following in accordance with Section 01 33 00 -Submittal Procedures.
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.

1.5 Quality Assurance

- .1 Qualifications:
- .2 Installer: specialist in performing work of this Section, and have at least 5 years successful experience in this size and type of project, and being a member of TIAC.

1.6 Delivery, Storage and Handling

- 1 Packing, shipping, handling and unloading:
- .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .3 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .2 Storage and Protection:
 - .1 Protect from weather, construction traffic.
 - .2 Protect against damage.
 - .3 Store at temperatures and conditions required by manufacturer.
- .3 Waste Management and Disposal:
 - .1 Place excess or unused insulation and insulation accessory materials in designated containers.
 - .2 Dispose of unused adhesive material at official hazardous material collections site .

2. PRODUCTS

2.1 Fire and Smoke Rating

- .1 In accordance with CAN/ULC-S102.
 - .1 Maximum flame spread rating: 25.
 - .2 Maximum smoke developed rating: 50.

2.2 Insulation

- .1 Mineral fibre specified includes glass fibre.
- .2 Thermal conductivity ("k" factor) not to exceed specified values at 24 degrees C mean temperature when tested in accordance with ASTM C 335.
- .3 TIAC Code A-1: rigid moulded mineral fibre without factory applied vapour retarder jacket.
 - .1 Mineral fibre: to CAN/ULC-S702.
 - .2 Maximum "k" factor: to CAN/ULC-S702.
- .4 TIAC Code A-3: rigid moulded mineral fibre with factory applied vapour retarder jacket.
 - .1 Mineral fibre: to CAN/ULC-S702.

- .2 Jacket: to CGSB 51-GP-52Ma.
- .3 Maximum "k" factor: to CAN/ULC-S702.

2.3 Insulation Securement

.1 Tape: self-adhesive, aluminium, plain, 50 mm wide minimum.

2.4 Jackets

- .1 Polyvinyl Chloride (PVC):
 - .1 One-piece moulded type to CAN/CGSB-51.53 with pre-formed shapes as required.
 - .2 Colours: White, gloss finish.
 - .3 Minimum service temperatures: -20 degrees C.
 - .4 Maximum service temperature: 65 degrees C.
 - .5 Moisture vapour transmission: 0.02 perm.
 - .6 Thickness: 0.8 mm.
 - .7 Fastenings:
 - .1 Use solvent weld adhesive compatible with insulation to seal laps and joints.

2 Aluminium:

- .1 To ASTM B 209.
- .2 Thickness: 0.9 mm sheet.
- .3 Finish: stucco embossed.
- .4 Joining: longitudinal and circumferential slip joints with 50 mm laps.
- .5 Fittings: 0.9 mm thick die-shaped fitting covers with factory-attached protective liner.
- .6 Metal jacket banding and mechanical seals: stainless steel, 19 mm wide, 0.5 mm thick at 300 mm spacing.

3. EXECUTION

3.1 Manufacturer's Instructions

.1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 Pre-Installation Requirement

- .1 Pressure testing of piping systems and adjacent equipment to be complete, witnessed and certified.
- .2 Surfaces clean, dry, free from foreign material.

3.3 Installation

- .1 Install in accordance with TIAC Best Practices Guide.
- .2 Apply materials in accordance with manufacturer's instructions and this specification.
- .3 Use two layers with staggered joints when required nominal wall thickness exceeds 75 mm.
- .4 Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.
 - .1 Install hangers, supports outside vapour retarder jacket.
- .5 Supports, Hangers:
 - .1 Apply high compressive strength insulation, suitable for service, at oversized saddles and shoes where insulation saddles have not been provided.

3.4 Removable, Pre-Fabricated, Insulation and Enclosures

- 1 Application: at expansion joints, valves, primary flow measuring elements flanges and unions at equipment.
- .2 Design: to permit movement of expansion joint and to permit periodic removal and replacement without damage to adjacent insulation.
- .3 Insulation:
 - .1 Insulation, fastenings and finishes: same as system.
 - .2 Jacket: aluminium and PVC.

3.5 Installation of Elastomeric Insulation

- .1 Insulation to remain dry. Overlaps to manufacturer's instructions. Ensure tight joints.
- .2 Provide vapour retarder as recommended by manufacturer.

3.6 Piping Insulation Schedules

- .1 TIAC Code: A-3.
 - .1 Securements: Tape at 300 mm on centre.
 - .2 Seals: VR lap seal adhesive, VR lagging adhesive.

- .3 Installation: TIAC Code: 1501-C.
- .2 Thickness of insulation as listed in following table.
 - .1 Run-outs to individual units and equipment not exceeding 4000 mm long.
 - .2 Do not insulate exposed runouts to plumbing fixtures, chrome plated piping, valves, fittings.

Application	Temp °C	TIAC code	Pipe sizes (mm) and insulation thickness (mm)					
			Run	to 25	30 to	65 to	125 to	200 &
			out		50	100	150	over
Chilled Water	4 – 13	A-3	25	25	25	25	25	25
Chilled Water	4 – 13	A-3	25	25	25	25	25	25
Pump Casing								
Condenser	40 -						ļ	
Water	60	A-1	25	25	40	40	40	50
(Indoors)	00							

.3 Finishes:

- .1 Exposed in mechanical rooms: aluminium jacket.
- .2 Use vapour retarder jacket on TIAC code A-3 insulation compatible with insulation.
- .3 Finish attachments: SS bands, at 150 mm on centre. Seals: closed.
- .4 Installation: to appropriate TIAC code CRF/1 through CPF/5.

3.7 Cleaning

.1 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION