



BID OPPORTUNITY No. 769-2011 ADDENDUM No. 1

**RE-ROOFING OF THE WASTEWATER SERVICES GARAGE BUILDING AT
552 PLINGUET STREET – CONTRACT NO. 26**

ISSUED: September 9, 2011
BY: D. Berg, C.E.T.
TELEPHONE NO. (204) 986-4452

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

- | | | |
|------|-----------|---|
| Add: | E4.3.3(h) | If required, the Contractor shall remove the existing eaves, rain gutters and downspouts to allow for proper installation of SPF and shall replace these components to the same locations after SPF installation. |
| Add: | E4.3.3(i) | The Contactor shall ensure the SPF is properly installed around all roof obstructions such as, but not limited to, vents, conduits, cables, compressors, flashings, etc. |
| Add: | E4.3.3(j) | The Contractor shall ensure the perimeter of the roof deck is properly insulated from either the interior or exterior (or combination of both) sides of the building to provide a continuous insulation and vapour barrier seal around the building roof. |
| Add: | E4.3.4(h) | If required, the Contractor shall remove the existing eaves, rain gutters and downspouts to allow for proper installation of roofing membrane and shall replace these components to the same locations after roofing membrain installation. |
| Add: | E4.3.4(i) | The Contactor shall ensure the roofing membrane is properly installed around all roof obstructions such as, but not limited to, vents, conduits, cables, compressors, flashings, etc. |