



938-2011 ADDENDUM 1

MINNETONKA STREET AND RIVER ROAD OUTFALL GATE CHAMBERS CONSTRUCTION AND UPGRADES

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: November 29, 2011
BY: Damir Muhurdarevic, P.Eng.
TELEPHONE NO. (204) 943-3178 ext. 3880

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 938-2011 Bid Submission with 938-2011 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Item A.2 (a) description revised

Page numbering on some forms may be changed as a result.

PART D – SUPPLEMENTAL CONDITIONS

Add: D13.3 The City anticipates awarding the Contract to the successful bidder by Friday, December 16, 2011.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D2.2(a) to read: Construction of a cast-in-place concrete extension/addition to the existing Minnetonka Chamber including the construction of a new manhole cast-in-place concrete base, pick-up and installation of steel thimbles and cast-iron sluice and flap gates and associated hardware.

Revise: D2.2(e) to read: Supply and installation of a new manhole on the new manhole cast-in-place concrete base

Add: D12.3(c)(xi) construct new manhole cast-in-place concrete base

Replace: Form I with the attached Form(s). The following is a summary of changes incorporated in the replacement forms:

Form I(R1): New Item No. 8 is added and should read: Construction of new manhole cast-in-place concrete base

Item No. 8 is now Item No. 9 and should read: Supply and Installation of manhole on the new manhole cast-in-place concrete base.

All subsequent Item Nos. should have an Item No. higher by 1 than originally.

Page numbering on some forms may be changed as a result.

PART E – SPECIFICATIONS

- Revise: E10.1(a) to read: This specification shall cover construction of cast-in-place concrete gate chambers, including the construction of the cast-in-place manhole base, and removal and disposal of the existing manhole. This specification shall also supplement, revise and amend CW 2160.
- Revise: E10.3(e) to read: Cast-in-place Concrete Chambers and Manhole Base Construction
- (i) Construct cast-in-place concrete chambers including the cast-in-place concrete base in accordance with CW 2160, except as supplemented, revised or amended in this specification and as indicated in the construction notes on the Drawings.
 - (ii) Adjust the location of reinforcing steel adjacent to openings to frame those openings in accordance with good practice, and maintain the bar spacing intent.
 - (iii) Do not use welded splices for reinforcing steel.
 - (iv) Order all wall reinforcing steel in lengths to best suit the spacing of walers so that reinforcing bars will not be bent or misformed in order to remove the walers.
 - (v) Install foundation waterproofing in accordance with E12 of this Specification.
 - (vi) The Contractor shall note that the existing gate chamber may not be vertical or plumb or square and may vary by +/- 150mm. It is the Contractor's responsibility to ensure smooth transition for the new chamber addition.
 - (vii) The Contractor shall note that existing formwork may be present around the existing gate chamber and will have to be removed prior to placement of the gate chamber addition at the Contractor's expense.
- Revise: E11.1(a) to read: This specification shall cover construction, supply and installation of a pre-cast concrete manhole as shown on the Drawings.
- Revise: E11.4 to read: Measurement and Payment
- Supply and installation of pre-cast concrete manhole will not be measured and will be paid for at the Contract lump sum price for "Supply and install 1200 Diameter Manhole, and Associated Manhole Cover", which price shall be payment in full for supplying all materials and for performing all operations herein described, and all other items incidental to the work.
- Revise: E12.1(c) to read: The Contractor shall be solely responsible for all transportation to collect the two cast iron sluices gate, two wall thimble, two mechanical lift operators, two stems, wall brackets and accessories after being notified by the Contract Administrator of their availability. The Contractor is advised that the wall thimbles will be available for pick-up the week of December 12, 2012, and all other mechanical hardware, such as cast iron sluice gate, mechanical lift operator, stem, wall brackets and accessories will be available for pick-up from February 1, 2012.
- Revise: E13.1(c) to read: The Contractor shall be solely responsible for all transportation to collect the two cast iron flap gates, two wall thimbles, and accessories after being notified by the Contract Administrator of their availability. The Contractor is advised that the wall thimbles will be available for pick-up the week of December 12, 2012, and all other mechanical hardware, such as two cast iron flap gates, and accessories will be available for pick-up from February 1, 2012.
- Add: E24: **SOILS INVESTIGATION REPORT**
- E24.1 Further to C3.1, of the General Conditions, several geotechnical soils investigations have been completed in the vicinity of the proposed works to determine the subsurface soils to facilitate the design of the Work. The information is considered accurate at the locations

indicated and at the time of the investigation. However, considerable variations in the soil conditions may exist between test holes (upper bank versus mid bank versus lower bank areas) and fluctuations in ground water levels can be expected seasonally, as the soils investigations were carried out a significant number of years ago. Test hole logs without reports are solely included.

- E24.2 Bidders are responsible for any interpretation they place on the supplied information in the test hole logs and are expected to make such additional investigation of the soil conditions as they feel necessary to satisfy themselves.
- E24.3 Any test borings made by the bidder shall be done in accordance with the requirements of the appropriate authority of the City of Winnipeg. Bidders shall notify the Contract Administrator prior to starting any soil boring operations.

DRAWINGS

Replace: 938-2011_Drawing_LD-5707_R0 with 938-2011_Addendum_1-Drawing_LD-5707_R1
938-2011_Drawing_LD-5708_R0 with 938-2011_Addendum_1-Drawing_LD-5708_R1
938-2011_Drawing_LD-5709_R0 with 938-2011_Addendum_1-Drawing_LD-5709_R1
938-2011_Drawing_LD-5710_R0 with 938-2011_Addendum_1-Drawing_LD-5710_R1
938-2011_Drawing_LD-5712_R0 with 938-2011_Addendum_1-Drawing_LD-5712_R1
938-2011_Drawing_LD-5713_R0 with 938-2011_Addendum_1-Drawing_LD-5713_R1