



PRAIRIE PRESERVE MAY NOT BE DISTURBED IN ANY WAY THROUGHOUT ENTIRE DURATION OF CONTRACT. PROTECT AS NECESSARY. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE INCURRED AND MUST RETURN TO ORIGINAL CONDITION AS DIRECTED BY CONTRACT ADMINISTRATOR

REMOVE EXISTING LAWN AND ALL ORGANICS TO MINIMUM 8" BELOW PROPOSED FINISHED GRADE. COMPACT SUB-BASE PER SPECIFICATIONS

RE-GRADE AS NECESSARY TO MEET EXISTING GRADES PER GRADING PLAN

PROVIDE TEMPORARY CONSTRUCTION FENCING AROUND ENTIRE PERIMETER OF SITE FOR DURATION OF CONTRACT. PLASTIC SNOW FENCE SHALL NOT BE ACCEPTABLE.

EXISTING CONCRETE CURB

EXISTING BOLLARDS (14 TOTAL) AND CHAIN TO BE REMOVED BY OTHERS PRIOR TO START OF CONSTRUCTION

REMOVE EXISTING LAWN AND AMEND SOIL FOR PLANTING BED

REMOVE EXISTING CIP CONCRETE CURB AND AGGREGATE BASE AT PERIMETER OF PARKING LOT

REMOVE EXISTING ASPHALT SURFACE AND AGGREGATE BASE FOR PLANTING BED. EXCAVATE TO A MINIMUM OF 18" BELOW FINISHED GRADE AND SCARIFY MIN. 6"

SAWCUT EXISTING ASPHALT. PROTECT ASPHALT TO REMAIN TO MINIMIZE CHIPPING OR CRUMBLING.

REMOVE EXISTING ASPHALT SURFACE AND RETAIN AGGREGATE BASE IF POSSIBLE FOR CRUSHED STONE SURFACE

EXISTING PLANTING BED TO REMAIN

REMOVE PORTION OF EXISTING CONCRETE WALL

SAWCUT EXISTING CONCRETE WALL AT ANGLE PER LAYOUT PLAN

INTERPRETIVE CENTRE

REMOVE EXISTING LAWN AND AMEND SOIL FOR PLANTING BED

REMOVE EXISTING CONCRETE AND REPLACE WITH NEW CONCRETE SURFACE

2500mm

PROTECT EXISTING BRICK PAVING SO NO CHIPPING OR BREAKING OF BRICKS OCCURS

PROVIDE TEMPORARY CONSTRUCTION FENCING AROUND ENTIRE PERIMETER OF SITE WHILE MAINTAINING ACCESS TO INTERPRETIVE CENTRE, WHEN POSSIBLE. PLASTIC SNOW FENCING SHALL NOT BE ACCEPTABLE.

REMOVE EXISTING LAWN AND ALL ORGANICS TO MINIMUM 8" BELOW PROPOSED FINISHED GRADE. COMPACT SUB-BASE PER SPECIFICATIONS

WOLFROM ENGINEERING LTD.
 CONSULTING ENGINEERS 345 HARGREAVES AVENUE, WINNIPEG, CANADA R6L 0L5 PHONE (204) 833-0211 FAX (204) 244-8888

PLAIN PROJECTS
 LANDSCAPE ARCHITECTURE & ENVIRONMENTAL DESIGN
 200 Cordova Street, Winnipeg, MB R2N 1A1
 (204) 930 0272 / www.plainprojects.ca

the manitoba association of architects
 Elizabeth Wreford Taylor
 Member No. 141
 June 1/12

Winnipeg
 The City of Winnipeg
 Planning, Property and Development Department
 4185 King Street, Winnipeg, MB R3B 1J1

Project:
LIVING PRAIRIE MUSEUM SHADE STRUCTURE AND WORKSHOP - 2795 NESS AVENUE
 Project Number: **2011-182**
 Drawing Title:
DEMOLITION PLAN

#	Issue/Revision	Date
1	30% DESIGN REVIEW	JAN. 14, 2012
2	60% DESIGN REVIEW	MAR. 19, 2012
3	90% DESIGN REVIEW	MAY 31, 2012
4	ISSUED FOR TENDER	JUNE 5, 2012

Sheet No:
L003

This drawing is property of the Council Administrator and cannot be reproduced or used without the written permission of the Council Administrator. The contractor is responsible for checking and verifying all levels and dimensions and shall report all discrepancies to the Council Administrator and obtain verification prior to commencing work.