



- U/G SERVICE NOTES:**
1. LOCATIONS OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION. ANY VARIANCES SHALL BE REPORTED TO THE CONTRACT ADMINISTRATOR IMMEDIATELY.
 2. DUCTS CONTAIN FIBRE OPTIC CABLES AND MUST BE EXCAVATED IN ACCORDANCE WITH UTILITY'S EXPRESS REQUIREMENTS. THE CONTRACTOR SHALL CONTACT THE UTILITY AT LEAST SEVEN DAYS PRIOR TO EXCAVATION.
 3. THE LOCATION OF WATER SERVICE SHUT-OFF VALVES CAN VARY SIGNIFICANTLY. A MINIMUM OF 1.0 METER CLEARANCE FROM ALL SHUT-OFF VALVES IS REQUIRED.
 4. A MINIMUM CLEARANCE OF 1.0 METER MUST BE PROVIDED BETWEEN THE UNDERSIDE OF ANY EXISTING WATERMAIN OR SEWERMAIN AND THE TOP OF PROPOSED WORKS.
 5. A MINIMUM CLEARANCE OF 0.5 METER MUST BE PROVIDED BETWEEN THE UNDERSIDE OF THE PROPOSED WORKS AND THE TOP OF ANY EXISTING WATERMAIN OR SEWERMAIN.
 6. A MINIMUM CLEARANCE OF 2.0 METERS MUST BE PROVIDED BETWEEN ANY EXISTING WATERMAIN OR SEWERMAIN PIPE AND THE PROPOSED WORKS.
 7. CONTACT THE CUSTOMER TECHNICAL SERVICES BRANCH AT 986-3322 48 HOURS PRIOR TO CONSTRUCTION FOR CLEARANCE OF EXISTING WATER AND WASTEWATER UTILITIES.
 8. EXISTING FIBER OPTIC CABLE TO BE RELOCATED BY TERASPAN AS PART OF A SEPARATE CONTRACT. CONTRACTOR TO COORDINATE WITH TERASPAN (604-630-1491).

- LEGEND**
- PROPERTY LINE
 - LIMIT OF WORK
 - EXISTING SEWER
 - EXISTING WATER MAIN
 - EXISTING GAS LINE
 - EXISTING TERASPAN FIBER OPTIC CABLE
 - EXISTING LIGHT AND HYDRO LINE
 - EXISTING MANHOLE
 - ⊗ EXISTING WATER VALVE
 - ○ EXISTING BOLLARD & CHAIN
 - EXISTING TREES TO BE PROTECTED
 - ⊗ ⊗ TREES TO BE REMOVED AS PER CW 3010
 - ⊗ ⊗ BOLLARD & CHAIN TO BE REMOVED
 - 1 REMOVE EXISTING PAVEMENT AND CONC. CURB. BASE TO REMAIN
 - 2 REMOVE EXISTING PAVEMENT, CONC. CURB AND BASE
 - 3 REMOVE EXISTING SIDEWALK PAVEMENT BASE TO REMAIN
 - 4 REMOVE EXISTING UNIT PAVERS BASE TO REMAIN
 - 5 CLEAR AND GRUB AS PER CW 3010
 - 6 FIBER OPTIC CABLE TO BE RELOCATED BY TERASPAN (SEPARATE CONTRACT)

| <p>Friday, May 18, 2012</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>No.</th> <th>Date</th> <th>Issue/Revision</th> <th>By</th> </tr> <tr> <td>1</td> <td>16/05/12</td> <td>ISSUED FOR TENDER</td> <td>AJH</td> </tr> </table> | No. | Date | Issue/Revision | By | 1 | 16/05/12 | ISSUED FOR TENDER | AJH | | <p>3rd Floor - 65 Gary Street, Winnipeg, MB R2C 4K4</p> | <p>Contact Colin McLachlan: 775-0291</p> | <p>Contact Matt Fischer: 489-0474</p> | <p>Contact James Hudson: 944-9907</p> | <p>ST JAMES CENTENNIAL PARKING LOT EXPANSION WINNIPEG, MANITOBA</p> <p>Sheet Title: DEMOLITION PLAN</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>Design: MAG</td> <td>Drawn: AJH</td> <td>Checked: MAG</td> <td>Scale:</td> <td>Date: 16/05/12</td> <td>File: 12-016</td> </tr> </table> <p style="text-align: right; font-size: 1.2em;">L-1.1</p> | Design: MAG | Drawn: AJH | Checked: MAG | Scale: | Date: 16/05/12 | File: 12-016 |
|---|------------|-------------------|----------------|----------------|--------------|----------|-------------------|-----|--|---|--|---------------------------------------|---------------------------------------|--|-------------|------------|--------------|--------|----------------|--------------|
| No. | Date | Issue/Revision | By | | | | | | | | | | | | | | | | | |
| 1 | 16/05/12 | ISSUED FOR TENDER | AJH | | | | | | | | | | | | | | | | | |
| Design: MAG | Drawn: AJH | Checked: MAG | Scale: | Date: 16/05/12 | File: 12-016 | | | | | | | | | | | | | | | |