


SIXTH FLOOR PARTIAL ROOF PLAN - NEW CONSTRUCTION


REMOVAL OF EXISTING COOLING TOWER UNIT AND FRAMING BY OTHERS.

DO NOT DAMAGE EXISTING CONCRETE FRAMING AROUND OPENING.



SIXTH FLOOR MACHINE ROOM PLAN - NEW CONSTRUCTION REMOVAL OF EXISTING COOLING TOWER UNIT AND FRAMING BY OTHERS.

DO NOT DAMAGE EXISTING WELD PLATES ON CONCRETE WALL.




 GENERAL CONTRACTOR TO CONFIRM AND COORDINATE EXACT UNIT SIZE AND ANCHOR BOLT LOCATIONS FROM SUPPLIER WITH SUPPORT DIMENSIONS PRIOR TO FABRICATION. COOLING TOWER UNIT NOT SHOWN FOR CLARITY (BY OTHERS). MAX UNIT OPERATING WEIGHT = 16810# MAX VERTICAL REACTION LOAD AT ANCHOR = 4375# (UNFACTORED) MAX HORIZONTAL REACTION LOAD AT ANCHOR = 125# (UNFACTORED) PROVIDE 3/8"Ø DRAIN HOLE AT BASE OF HSS SECTIONS TYP
 SITE CONFIRM EXIST STRUCTURE & DIMENSIONS PROVIDE WEB STIFFENERS IN ALL BEAMS WHICH CROSS OVER ALL COLUMNS OR BEAMS CONFIRM FINAL STEEL FINISH WITH OWNER

REMOVE SLIDING HATCH ACCESS AND INFILL EXISTING OPENING AS FOLLOWS: PROVIDE 1 1/2 X 0.03 STEEL DECK ON C8x11.5 AT 4'-0" O.C. AND AT EACH SIDE OF COLUMN c/w 8x10x5/8 WELD PLATE BOLTED TO EXISTING CONCRETE BEAM WITH 2-5/8" HILTI KB x 4" EMBEDMENT. ELEVATION OF TOP OF CHANNEL 3" BELOW TOP OF EXISTING CONCRETE CURB. PROVIDE 44x4x3/8 ANGLE DECK SUPPORT AROUND PERIMETER CONNECTED TO CHANNELS AND BOLTED TO CONCRETE BEAMS ON EACH SIDE OF OPENING WITH

1/2"ø HILTI KB11 x 4" EMBEDMENT AT 8" o/c AND CONNECTED AROUND NEW TOWER COLUMN LOCATIONS.

PROVIDE 1 1/2" RIGID INSULATION OVER STEEL DECK AND PROVIDE ROOFING ABOVE MATERIALS TO MATCH EXISTING SYSTEM WITH FLASHING OVER EXISTING PERIMETER CONCRETE CURB. SEAL ALL OPENINGS REQUIRED FOR MECHANICAL LINE PENETRATIONS AND AT COOLING TOWER SUPPORT COLUMN PENETRATIONS.



GENERAL NOTES

- 1. STRUCTURAL DESIGN BASED ON THE NATIONAL BUILDING CODE OF CANADA 2005 EDITION. A) IMPORTANCE CATEGORY: NORMAL
- 5. DO NOT SCALE DRAWINGS. 4. ALL DIMENSIONS ARE TO BE VERIFIED WITH THE MECHANICAL DRAWINGS PROJECT DRAWINGS AND EXISTING SITE CONDITIONS PRIOR TO CONSTRUCTION. 5. THESE STRUCTURAL DRAWINGS SHOW THE COMPLETED STRUCTURE AND DO NOT INDICATE ALL

STRUCTURAL STEEL

- DESIGNING PROVISIONS FOR ALL TEMPORARY FALL PROTECTION SYSTEMS REQUIRED DURING CSA-G40.20 "GENERAL REQUIREMENTS FOR ROLLED OR WELDED STRUCTURAL QUALITY STEEL".
- 5. ALL WELDING SHALL CONFORM TO THE LATEST EDITION OF CSA W59, "WELDED STEEL
- PRIMER. STEEL TO BE CLEANED IN CONFORMANCE WITH SSPC-SP2. STEEL RECEIVING FINISH PAINTING TO HAVE ONE COAT OF CISC/CPMA 2-75 QUICK DRYING SHOP PRIMER. STEEL TO BE CLEANED IN CONFORMANCE WITH SSPC-SP7.
- 9. ALL BEAMS CONTINUOUS OVER COLUMNS ARE TO HAVE WEB STIFFENERS THE SAME SIZE AND ORIENTATION AS THE COLUMN BELOW, UNLESS OTHERWISE NOTED. 10. ANCHOR BOLTS TO BE GRADE ASTM A307 PROVIDED BY STEEL SUPPLIER AND SET BY THE
- STRUCTURE AS A WHOLE. THESE SHALL REMAIN IN PLACE UNTIL ALL STEEL BRACING IS ERECTED, WELDED IN PLACE.

 14. STRUCTURAL STEEL SUPPLIER IS TO SUBMIT ENGINEERING DRAWINGS BEARING THE SEAL OF A PROFESSIONAL ENGINEER REGISTERED IN THE PROVINCE OF MANITOBA COVERING THE DESIGN

FABRICATION AND ERECTION PROCEDURES AND TOLERANCES.

B) WIND LOAD: Q50 = 9.4 P.S.F.

C) GROUND SNOW LOAD: SS = 39.6 P.S.F. D) ASSOCIATED RAIN LOAD: SR = 4.2 P.S.F. SEISMIC SITE CLASSIFICATION: NOT APPLICABLE

COMPONENTS NECESSARY FOR SAFETY DURING CONSTRUCTION. THE GENERAL CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR SAFETY ON AND AROUND THE JOBSITE DURING CONSTRUCTION.

1. THE STRUCTURAL STEEL FABRICATOR'S ENGINEER SHALL BE RESPONSIBLE FOR LOCATING AND CONSTRUCTION TO MEET MANITOBA WORKPLACE HEALTH AND SAFETY REGULATIONS. 2. STRUCTURAL STEEL TO CONFORM TO CSA-G40.21, "STRUCTURAL QUALITY STEELS" AND 3. ALL ROLLED OR STEEL STRUCTURAL SECTIONS SHALL BE G40.21-50W. ALL HOLLOW STRUCTURAL SECTIONS TO BE G40.21-50W CLASS C. ALL ANGLES, CHANNELS AND PLATES

SHALL BE G40.21-44W. 4. FABRICATION AND ERECTION OF STRUCTURAL STEEL SHALL BE PERFORMED IN ACCORDANCE WITH CAN/CSA S16.1-01, "STEEL STRUCTURES FOR BUILDINGS".

CONSTRUCTION". FABRICATORS SHALL BE PROPERLY CERTIFIED IN ACCORDANCE WITH CSA W47.1, "CERTIFICATION OF COMPANIES FOR FUSION WELDING OF STEEL STRUCTURES". 6. ALL BOLTED CONNECTIONS TO USE A325 HIGH STRENGTH BOLTS, MINIMUM CONNECTION SHALL CONSIST OF 2 BOLTS. 7. ALL STRUCTURAL STEEL IS TO RECEIVE ONE COAT OF CISC/CPMA 1-73A QUICK DRYING SHOP


8. NO HOLES PERMITTED IN TOP FLANGE OF BEAMS AT COLUMNS WHERE BEAMS ARE CONTINUOUS OVER COLUMNS.

GENERAL CONTRACTOR. 11. FABRICATOR TO NOTIFY ENGINEER OF ANY PROPOSED MEMBER SUBSTITUTIONS AND CHANGED CONNECTION DETAILS. 12. THE STRUCTURAL STEEL SUPPLIER SHALL PROVIDE AND BE RESPONSIBLE FOR ALL HOLES IN STEEL SECTIONS REQUIRED BY OTHER TRADES. SECTION SHALL BE STRENGTHENED WHERE REQUIRED TO GUARANTEE THE ORIGINAL STRENGTH OF THE BEAM. ANY CUTTING OF STEEL AT


THE JOB SITE SHALL BE DONE ONLY AS DIRECTED AND APPROVED BY THE ENGINEER.


OF CONNECTIONS. TO THE PROJECT DESIGN ENGINEER FOR REVIEW PRIOR TO FABRICATION. CONNECTION DESIGN TO INCLUDE FOR ALL ADJUSTABLE CONNECTIONS REQUIRED TO SUIT

13. THE STRUCTURAL STEEL ERECTOR SHALL BE RESPONSIBLE FOR SUPPLYING AND ERECTING ALL TEMPORARY GUYING AND BRACING OF THE STEEL FRAMING TO PROVIDE STABILITY FOR THE









SMS ENGINEERING

770 Bradford Street Winnipeg MB Canada R3H 0N3 Telephone 204.775.0291 Fax 204.772.2153

CITY OF WINNIPEG COOLING PLANT REPLACEMENT 151 PRINCESS STREET BID OPPORTUNITY 887-2012

MACHINE ROOM COOLING PLANT PLANS AND SECTIONS

Revision Number Drawing Number