


NOTES:

1. PROVIDE AND INSTALL FIRE ALARM STROBES IN THE STORAGE ROOM (QTY. 2), FIRST AID ROOM (QTY. 1), MAINTENANCE ROOM / STORAGE ROOM (QTY. 2), BACKUP GENERATOR ROOM (QTY.1), CRAWLSPACE (QTY. 3) AND HORN STROBES AROUND THE POOL DECK (QTY. 6), CRAWLSPACE (QTY. 1) TO MEET CURRENT CODE REQUIREMENTS. ADD ONE (1) SMOKE DETECTOR TO THE TOP OF STAIRS TO POOL CRAWLSPACE ACCESS.
2. EQUIPMENT LOCATED ON ROOF.
3. PROVIDE AND INSTALL WIRE GUARDS AROUND LOCKER ROOM HEAT DETECTORS.
4. PROVIDE AN ADDRESSABLE PULL STATION NEXT TO CRAWLSPACE EXIT DOOR INSIDE THE CRAWLSPACE. THE NEW PULL STATION SHALL BE TIED INTO THE LOCAL FIRE ALARM LOOP AND VERIFIED.
5. REFER TO ARCHITECTURAL DRAWINGS FOR EXACT MOUNTING LOCATIONS.
6. PROVIDE A NEW FULLY ADDRESSABLE FIRE ALARM CONTROL PANEL (FACP) AND REMOTE ANNUNCIATOR. THE NEW FACP SHALL BE FED FROM THE EXISTING CIRCUIT.
7. COORDINATE LOCATIONS OF PU-1, PU-2 AND PU-3 WITH MECHANICAL CONTRACTOR. CONTRACTOR TO PROVIDE A NEW BREAKER AND PROVIDE FEEDER FOR PUMPS FROM PANEL C. CONTRACTOR TO ALSO CARRY AN ALLOWANCE TO FEED THE PUMPS FROM PANEL D OR PANEL B, IF PANEL C IS STILL FULL AFTER DEMOLITION WORK.
8. PROVIDE A NEW DISTRESS ALARM HORN (FEDERAL SIGNAL - LP5-09-030).
9. PROVIDE A NEW BLUE DISTRESS ALARM STROBE (STI-SAS5000-B) TOP OF INSTALLED STROBE TO ALIGN WITH THE TOP OF THE DOOR FRAME.
10. PROVIDE A NEW BLUE DISTRESS ALARM PUSH BUTTON C/W KEYED RESET AND STOPPER SHIELD WITH SOUND (STI SS-24 2A O "DISTRESS ALARM").
11. RE-FEED ALL EXISTING DATA DROPS TO CAMERAS IN ALL POOL AREAS.
12. MOUNT HORN/STROBE TO BE VISIBLE THROUGH CHLORINE ROOM WINDOW.
13. ALTERNATE MOUNTING LOCATION FOR FACP. CONTRACTOR TO DETERMINE FINAL LOCATION BASED ON DIMENSIONS OF NEW PANEL AND ACCESS. COORDINATE WITH CONTRACT ADMINISTRATOR.

Ownership of Documents:
 Drawings and specifications as instruments of service are and shall remain the property of the Architect whether the project for which they are made is executed or not. They are not to be used by the owner on other projects or extensions to this project except by agreement in writing and with appropriate compensation to the Architect.

This drawing shall not be scaled. Follow given dimensions only.



ISSUED FOR

ISSUED FOR TENDER

SEAL

PEGM
 Certificate of Authorization
 KGS Group
 No. 245

ARCHITECT / PRIME CONSULTANT
SYNYSHYN
 ARCHITECTURE + INTERIOR DESIGN INC.
 MANITOBA • ALBERTA
 T: 204.947-1100
 F: 204.956-5742
 603-63 Albert Street Winnipeg, Manitoba R3B 1G4 Canada info@synyshyn.com www.synyshyn.com

ENGINEERING CONSULTANT
KGS GROUP
 CONSULTING ENGINEERS

ENGINEERING CONSULTANT

PROJECT TITLE
MARGARET GRANT POOL INTERIOR RENOVATIONS BID OPPORTUNITY NO. 12-2013

685 DALHOUSIE DRIVE, Winnipeg, MB

DRAWING TITLE
ELECTRICAL MAIN FLOOR PLAN POWER AND SYSTEMS

DESIGNED BY AP DRAWN BY BGO

ISSUE DATE 13/02/06 REVISION No. 0

PROJECT No. 87611 DRAWING No. **E02**

LEGEND:

- DUPLEX RECEPTACLE
- DENOTES: 15/20 - 5-20R CONVENIENCE OUTLET
- DENOTES: alpha - MOUNTED ABOVE COUNTER/TABLE
- DENOTES: DW - DISH WASHER
- DENOTES: F - FRIDGE
- DENOTES: GFI - GROUND FAULT INTERRUPTER
- DENOTES: M - MICROWAVE (NOTE 5)
- DENOTES: MW - MOUNTED IN MILL WORK (NOTE 5)
- DENOTES: V - VENDING MACHINE
- DENOTES: WF - WATER FOUNTAIN
- DENOTES: WP - WEATHER PROOF
- SPLIT WIRED DUPLEX RECEPTACLE
- DENOTES 2 CAT5 DROPS
- DUPLEX DATA OUTLET
- DENOTES: MW - MOUNTED IN MILL WORK
- DENOTES 1 CAT5 DROP
- DATA OUTLET
- HAND DRYER
- FIRE ALARM HORN/STROBE
- FIRE ALARM STROBE LIGHT
- FIRE ALARM PULL STATION
- HEAT DETECTOR
- FIRE ALARM ANNUNCIATOR
- FIRE ALARM CONTROL PANEL
- FORCE FLOW HEATER
- BASEBOARD HEATER
- 3/8 MOTOR
- 1/8 MOTOR
- LOCAL DISCONNECT SWITCH
- DENOTES: WP - WEATHER PROOF
- AUTOMATIC TRANSFER SWITCH
- DOOR OPENER
- PUSH BUTTON (NOTE 5)
- DENOTES: D - DISTRESS ALARM (NOTE 10)
- DISTRESS ALARM STROBE (NOTES 5,9)
- DISTRESS ALARM HORN (NOTES 5,8)
- PA SPEAKER