



230-2013 ADDENDUM 3

WAVERLEY WEST ARTERIAL ROADS PROJECT (WWARP) PART 3 – CONTRACT 1 – KENASTON BOULEVARD EXTENSION NORTHBOUND AND SOUTHBOUND LANES NEW ROAD CONSTRUCTION AND ASSOCIATED WORKS

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: April 25, 2013
BY: Brad Cook
TELEPHONE NO. (204) 478-8939

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20130301

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph B10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 230-2013 Addendum 1 - Bid Submission with 230-2013 Addendum 3 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

- Form B(R2): Revise Item No. A.7.
- Form B(R2): Revise Item No. B.6.
- Form B(R2): Revise Item No. B.7.
- Form B(R2): Revise Item No. C.2i).
- Form B(R2): Revise Item No. C.3i).
- Form B(R2): Revise Item No. C.4.
- Form B(R2): Revise Item No. C.5a).
- Form B(R2): Add Item No. C.5b).
- Form B(R2): Revise Item No. C.6a).
- Form B(R2): Add Item No. C.6b).
- Form B(R2): Add Items No. C.8 to C.11 inclusive.
- Form B(R2): Revise Item No. D.4.
- Form B(R2): Revise Item No. D.5.
- Form B(R2): Revise Item No. E.4.
- Form B(R2): Revise Item No. E.5.

Page numbering on some forms may be changed as a result.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, April 30, 2013.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D23.1(a) to read Substantial Performance – Four-thousand five-hundred dollars (\$4,500.00);

Page numbering on some forms may be changed as a result.

PART E – SPECIFICATIONS

Add:	E41	DEWATERING
	E41.1	DESCRIPTION
	E41.1.1	This specification shall cover the dewatering of surcharged land drainage sewers (LDS) and ponds as necessary for manhole connections, catch basin lead connections, culvert outfall installation, and televised sewer inspections.
	E41.2	GENERAL
	E41.2.1	Provision of adequate site drainage during the entire construction phase shall be the Contractor's responsibility. The Contractor shall maintain site grading as necessary to provide for proper drainage away from the excavated area. This water is to be re-directed into ditches or sewers outside of the site. Silt fences shall be properly erected and keyed into the primary ditches to protect fish habitat and prevent clogging of LDS. No extra payment or time extension will be granted as a result of difficulties associate with site access resulting from poor site drainage during any part of the construction phase.
	E41.3	CONSTRUCTION METHODS
	E41.3.1	The Contractor shall prepare and submit a plan to dewater the existing pond for culvert outfall installations at the Pre-Construction Meeting. The plan shall adhere to guidelines specified in E21, "Environmental Protection Plan". The plan will be reviewed and approved by the Contract Administrator prior to commencement of construction. If at any time the Contract Administrator deems the dewater efforts to be insufficient, the Contract Administrator may order the Contractor to modify and / or increase efforts at the sole discretion of the Contract Administrator with no additional time or compensation. The Contractor shall maintain dewatering until final completion of the contract.
	E41.3.2	The Contractor shall plug the LDS as necessary to perform manhole connections. The Contractor will verify with the Contractor Administrator that the method of plugging the LDS is adequate and approved prior to any installations.
	E41.3.3	The Contractor shall plug each LDS segment as necessary to perform catch basin lead connections. An LDS segment length will be considered to be the LDS leg from manhole to manhole to which all required and necessary catch basin lead connections are to be made. The Contractor will verify with the Contractor Administrator that the method of plugging the LDS is adequate and approved prior to any installations.
	E41.3.4	The Contractor shall plug the LDS as necessary to perform televised sewer inspections. The Contractor will verify with the Contractor Administrator that the method of plugging the LDS is adequate and approved prior to any installations.
	E41.3.5	The Contractor shall coordinate dewatering procedures with the other contractors on site to prevent conflicts with potential runoff from other work areas. No claim for extra payment shall be made because of conflicts with other work area's drainage issues.
	E41.4	MEASUREMENT AND PAYMENT

- E41.4.1 Payment for dewatering of the existing pond for culvert outfall installations will be measured on a unit basis and paid for at the Contract Unit Price for "Dewatering for Outfall Installation" and considered compensation in full for supplying all of the labour, materials, equipment, and tools, and completing all operations herein described and all other work included in the work of this specification.
- E41.4.2 Payment for dewatering of LDS for manhole connections will be measured on a unit basis and paid for at the Contract Unit Price for "Dewatering of LDS for Manhole Connection" and considered compensation in full for supplying all of the labour, materials, equipment, and tools, and completing all operations herein described and all other work included in the work of this specification.
- E41.4.3 Payment for dewatering of an LDS segment for catch basin lead connections will be measured on a unit basis per LDS leg and paid for at the Contract Unit Price for "Dewatering of LDS Segment" and considered compensation in full for supplying all of the labour, materials, equipment, and tools, and completing all operations herein described and all other work included in the work of this specification.
- E41.4.4 No measurement and payment will be made for dewatering of LDS for televised sewer inspections. The cost incurred for dewatering the LDS for televised sewer inspection will be incidental to televised sewer inspection and paid for as per CW 2145-R3.