



NOTES:

1. 15M TIE BARS SHALL BE PLACED PRIOR TO THE PLACING OF ANY CONCRETE. TIE BARS SHALL BE BENT AS REQUIRED AND PLACED SO AS TO ENSURE A MINIMUM CONCRETE COVER OF 50.
2. EXISTING PAVEMENT MAY BE CUT FULL DEPTH. REF. SD-229C



THE CITY OF WINNIPEG
 PUBLIC WORKS DEPARTMENT

Reference Spec. No.
 CW 3235, CW 3310, CW 3325

DIMENSIONS ARE IN MILLIMETRES

**CURB RAMP
 FOR ASPHALT OVERLAY**

Designed By:
 B.P.

Drawn By:
 A. R.

Scale :
 N.T.S.

Checked By:
 D.R.K.

Date:
 05-12-31

Drawing No.

Approved:
 SURFACE WORKS COMMITTEE

SD-229D