

## 371-2013 ADDENDUM 2

### 2013 WATERMAIN RENEWALS CONTRACT NO. 8

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

ISSUED: May 23, 2013  
BY: Gord Steiss  
TELEPHONE NO. (204) 954-6800

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20130301

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.**

---

#### **PART D – SUPPLEMENTAL CONDITIONS**

- Add: D16.2 Watermain works on Elgin Avenue near the MRHA building currently under construction will conflict with the Ellis-Don Construction's laydown and materials delivery area. The watermain replacement work cannot be deferred due to high break frequency, and must be completed this year. In addition, the watermain renewal shall be constructed during the months of July and August in accordance with Section D16.1 to minimize the impact on Ellen Douglas Elementary School. Conflict between the Watermain renewal and building construction projects shall be minimized as follows:
- a) The Contract Administrator will liaison with Ellis-Don immediately after award of the project, to coordinate the schedules for the Elgin Avenue works.
  - b) Shoring for the building site is located at the Elgin Avenue property line. The contractor must provide a list of equipment including weights and loadings and consult with Ellis-Don, who will determine if the equipment may be used on the boulevard in close proximity to the shoring. Smaller excavation equipment may be required subject to these weight restrictions.
  - c) Temporary water services to homes shall not cross Elgin Avenue between Sherbrook Street and the lane west of Sherbrook, to decrease the likelihood of damage by heavy vehicles accessing the building construction site.
  - d) Existing Ellis-Don trailers and materials located in the south boulevard that conflict with watermain installation (i.e. shaft locations, a hydrant location and several building service reconnections) will be identified and relocated by Ellis-Don. Ellis-Don will require two weeks' notice to coordinate this relocation. The trailers and material will remain on the boulevard, but will be relocated to accommodate the immediate work area for watermain works.
  - e) All watermain works between Sherbrook Street and the first lane west of Sherbrook shall be done at night beginning no earlier than 6:00pm and completing by 5:00am (Ellis-Don normally begins work at 7:00am and ends work at 5:00pm, or sometimes later during concrete pours).
  - f) Existing water services (2) serving the Ellis-Don site offices (owned by MHRA) will not require replacement, and shall be abandoned.
  - g) Watermain flushing shall be done in such a manner to route flow away from the building construction site, using hoses and sandbags as necessary.
  - h) No additional costs of time extensions will be considered for dealing with the above constraints.