

## 2013 RE-ROOFING OF THE BIOREACTOR BUILDING AT THE WEWPCC

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY**

ISSUED: May 13, 2013  
BY: Matthew Klowak  
TELEPHONE NO. (204) 986-3982

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: A20130301

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.**

---

### **PART D – SUPPLEMENTAL CONDITIONS**

- Revise: D2.2(a) to read      The removal of approximately 1,935 square meters of existing built-up roofing from Area 1 and 600 square metres from Area 2,
- Delete: D2.2(b)              The supply and installation of 13 millimetre gypsum sheathing board,
- Revise: D2.2(f) to read      The supply and installation of approximately 1,935 square meters of modified bitumen roofing in Area 1 and 600 square metres from Area 2,

### **PART E – SPECIFICATIONS**

- Revise: E3.2 to read:      The Contractor shall be responsible for the removal and reinstallation of any obstructions such as, but not limited to, handrails, drains, ducts, conduits, cable trays, gas lines, vents, access hatches, support brackets, stairs, air-conditioning components and communication components at his own expense.
- Revise: E3.3 to read:      The Contractor shall remove and stockpile whatever quantity identified by the Contract Administrator of the existing granular ballast material to a location on-site that is to be determined by the Treatment Plant Supervisor(s) and acceptable to the Contract Administrator.
- Add: E3.3.1                  Removed ballast material not selected to be stockpiled shall be hauled off site and disposed of by the Contract at his own expense.
- Add: E3.4                      The Contractor shall supply and install a metal pitch box at all penetrations through the roof using FillGard Pourable sealer as manufactured by Firestone, or an approved equal in accordance with B6.
- Add: E3.5                      All cable trays to be adequately supported by new C-ports and shall be C-port CX series rubber or an approved equal in accordance with B6.
- Revise: E4.1.1(a) to read:      The Contractor shall remove and stockpile whatever quantity identified by the Contract Administrator of the existing precast paver stone material to a location on-site that is to be determined by the Treatment Plant Supervisor(s) and acceptable to the Contract Administrator.

- Add: E4.1.1(b) Removed precast paver stone material not selected to be stockpiled shall be hauled off site and disposed of by the Contract at his own expense.
- Add: E3.5 ACCESS AND RESTORATION
- Add: E3.5.1 Existing grassed areas disturbed or damaged by accessing the Site shall be restored with seeding using imported topsoil in accordance with CW 3520.
- Add: E3.5.2 Costs associated with restoring disturbed or damaged existing grassed areas will not be measured for payment and shall be included with the roofing work being done.

### **NATIONAL MASTERS SPECIFICATIONS – DIVISION 7**

Delete: 2.1 DECK COVERING

.1 Gypsum Sheathing Board: to ASTM C1396/C1396M-04, 12.7 mm thick.

### **DRAWINGS**

Replace: 376-2013 \_Drawing\_1-0103S-B0014-002 with 376-2013 \_Addendum\_2 Drawing 1-0103S-B0014-002\_R1