


plotscale - 1:1 (metric)

sheet size - ANSIC 17" x 22"

CAD File Name: 2014.05.30 woodhaven_base_play_area_phase 2_for_tender.dwg



CENTRE POINT OF PLAY AREA TO BE STAKED OUT ON SITE PRIOR TO CONSTRUCTION FOR CONTRACT ADMINISTRATOR REVIEW

TIMBER LOG EDGE, LANDSCAPE TIMBER EDGING AND VERTICAL LOGS FEATURE TO BE STAKED OUT / LOCATED ON SITE AFTER PLAY STRUCTURE IS INSTALLED FOR CONTRACT ADMINISTRATOR APPROVAL PRIOR TO INSTALLING

BENCH TO BE CENTERED BETWEEN PHASE 1 TREES NEXT TO 2-5 YEAR OLD PLAY AREA

ALSO REFER TO SCD-136A - ACCESSIBLE BENCH NODE FOR BENCH LAYOUT

EXISTING BUILDING

PERPENDICULAR TO BLDG

PHASE 1 TREES FOR REFERENCE ONLY

EXISTING TREE

± 8.34
DUE NORTH

± 21.69
DUE NORTH

CENTRE POINT OF PLAY AREA TO BE STAKED OUT ON SITE PRIOR TO CONSTRUCTION FOR CONTRACT ADMINISTRATOR REVIEW

TIMBER LOG EDGE AND LANDSCAPE TIMBER EDGING TO BE STAKED OUT / LOCATED ON SITE AFTER PLAY STRUCTURE IS INSTALLED FOR CONTRACT ADMINISTRATOR APPROVAL PRIOR TO INSTALLING

CONTRACTOR TO ENSURE SMOOTH CURVES ALONG PATHWAY

APPROX. LENGTH ALONG CENTRE LINE OF PATHWAY = ±14.1m

PATHWAY AND BRIDGE LOCATION TO BE STAKED OUT FOR APPROVAL BY C.A. PRIOR TO CONSTRUCTION

APPROX. LENGTH ALONG CENTRE LINE OF PATHWAY = ±9.3m

BOULDER LOCATION TO BE MARKED ON SITE FOR APPROVAL BY C.A. PRIOR TO INSTALLATION. STEPPING BOULDERS TO BE NO FURTHER THAN 300mm APART

PATHWAY TO ALIGN WITH LANDSCAPE TIMBER EDGING

CONTRACTOR TO MARK EDGE OF WOOD FIBRE FOR APPROVAL BY C.A. PRIOR TO INSTALLING WOOD FIBRE. CONTRACTOR TO ENSURE CRISP SPADE EDGE.

LOCATION FOR CONSTRUCTION ACCESS, LOCATION TO BE CONFIRMED ON SITE WITH CONTRACT ADMINISTRATOR PRIOR TO STARTING CONSTRUCTION

TOP OF BANK

LEGEND

- PROPERTY LINE
- LIMITS OF WORK - PHASE 2
- CONSTRUCTION ACCESS LOCATION
- EXISTING TREE / SHRUB TO REMAIN
- FEATURE BOULDER
- STEPPING BOULDER
- PROPOSED BENCH
- FLAGSTONE PAVING (PHASE 1, N.I.C.)
- PLAY AREA BOULDER EDGING (PHASE 1, N.I.C.)

LAYOUT NOTES

1. ALL EXISTING TREES, SHRUBS, SIDEWALKS, CURBS, SOD, UTILITIES AND PAVING TO BE PROTECTED DURING CONSTRUCTION TO CITY OF WINNIPEG STANDARDS. CONTRACTOR TO MAKE GOOD ALL DAMAGED AREA DURING CONSTRUCTION BOTH ON AND OFF SITE TO CITY OF WINNIPEG STANDARDS AT THE CONTRACTORS COST.
2. ALL NOTES IN GREY INDICATE FUTURE WORK OR WORK TO BE COMPLETED BY OTHERS UNDER SEPARATE CONTRACT.
3. LAYOUT TO BE APPROVED BY CONTRACT ADMINISTRATOR PRIOR TO ANY CONSTRUCTION OR REMOVAL.
4. LOCATIONS OF PLAY AREA AND PATH SHALL BE LAID OUT ON SITE WITH CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION
5. TIMBER LOG EDGING SHALL BE INSTALLED AFTER PLAY STRUCTURE INSTALLATION TO ENSURE THAT EDGING IS NOT INSTALLED WITHIN PLAY STRUCTURE FALL ZONE
6. ALL BOULDERS AND SITE FURNITURE SHALL BE FIELD LOCATED BY CONTRACT ADMINISTRATOR PRIOR TO INSTALLATION.
7. REFER ALSO TO WRITTEN SPECIFICATIONS.

REV	YY / MM / DD	DESCRIPTION	BY
0	14 / 06 / 02	ISSUED FOR TENDER	JW

A. SECTION LETTER OR DETAIL NUMBER.	SEAL
B. DRAWING WHERE SECTION OR DETAIL IS DRAWN.	
OR	
DRAWING WHERE SECTION OR DETAIL IS INDICATED.	
SECTION OR DETAIL SHOWN ON SAME DRAWING.	

SCATLIFF + MILLER + MURRAY Inc.
 TEL 204 927-3444 FAX 204 927-3443
 1120 - 201 PORTAGE AVE. WINNIPEG, MB, CANADA

CLIENT
CITY OF WINNIPEG

PROJECT
WOODHAVEN COMMUNITY CENTRE PLAY AREA - PHASE 2

TITLE
LAYOUT PLAN

DESIGN	DRAWN	DATE - Y / M / D	SCALE
CO/JW	JW/WF	2014/06/02	1:150
CHECKED	APPROVED	JOB NO.	DRAWING NO.
JW	CO	263-2014	L2