

## GENERAL NOTES

- 1) ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE NOTED.
- 2) ALL UTILITIES ARE SHOWN AS INFORMATION ONLY. CONTRACTOR TO CONFIRM LOCATION OF ALL UTILITIES ON SITE PRIOR TO CONSTRUCTION.
- 3) CONTRACTOR TO STAKE OUT LOCATION OF ALL WORKS FOR APPROVAL OF THE CONTRACT ADMINISTRATOR PRIOR TO ANY CONSTRUCTION OR REMOVALS.
- 4) CONTRACTOR TO CONFIRM ALL DIMENSIONS ON SITE AND REPORT ANY DISCREPANCIES TO THE CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION.
- 5) DURING CONSTRUCTION, CONTRACTOR TO PROTECT TO CITY OF WINNIPEG STANDARDS. ALL EXISTING TREES, SOD, UTILITIES, AND PAVING TO REMAIN. AREAS DAMAGED DURING CONSTRUCTION TO BE REPAIRED TO CITY OF WINNIPEG STANDARDS AT CONTRACTOR'S COST. REPAIRS ALL DAMAGE TO PRIOR EXISTING CONDITIONS.
- 6) CONSTRUCTION ACCESS TO BE LIMITED TO THE ROUTES SPECIFIED ON SITE BY CONTRACT ADMINISTRATOR.
- 7) CONTRACTOR IS RESPONSIBLE FOR ALL REMOVALS AS REQUIRED TO CONSTRUCT ALL WORKS AS SHOWN ON PLANS AND DETAILS. ALL ITEMS TO BE REMOVED MUST BE DISPOSED OF OFF SITE IN A LEGAL MANNER.
- ALL WORK TO BE DONE IN ACCORDANCE WITH CITY OF WINNIPEG STANDARDS UNLESS OTHERWISE NOTED.
- SERVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE LATEST CITY OF WINNIPEG STANDARD SPECIFICATIONS.

LEGEND			
·0000	CHAIN LINK FENCE PROPERTY LINE		
	EXISTING LIGHT STAND		
	EXISTING TREE		
	PARK PATH CRUSHED LIMESTONE PER SCD-645		
	ENGINEERED WOOD FIBER BASE AS PER SPECIFICATIONS AND DETAILS 8/L2.7 AND 9/L2.7. NEW TREE (ELM)		
	NEW TREE (MAPLE)		
	NEW TREE (ASH)		
+ NEW TREE (BASSWOOD)			
CALE BAR (METRES)			
2 Inte			cow
			COW By
Date March 20, 2014	Scale 1:500		
	rawn By	Checked By	
Seals	Seals		
LOMBARD NORTH G 287 Taché Ave. Winnipeg, Manitoba R <i>Tel:</i> (204) 943-3896 <i>F</i>	2H 2A1	)	
Winnipeg THE CITY OF WINN Planning, Property and D Planning and Land Use D Unit 15 - 30 Fort Street, V	evelopment Departm Division		
Project Title		-	
PAT PHILLIPS PAT PHILLIPS PAT PHILLIPS PAT PHILLIPS PAT PAILS		HNESSY	PARK
Sheet Title	SY PARK - S	ITE PLA	N
Project No.		Drawing No.	