



**MAIN FLOOR PLAN - POWER & SYSTEMS DEMOLITION**  
 SCALE: 1/8"=1'-0"

**ELECTRICAL NOTES:**

- DISCONNECT AND REMOVE THE EXISTING FIRE ALARM SYSTEM INCLUDING CONDUIT AND DEVICES.
- DISCONNECT AND REMOVE ABANDONED ELECTRICAL CABINETS AND CONDUIT.

**NOTES:**

THESE DRAWINGS SHALL NOT BE SCALED.

THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.

THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.

ALL OPENINGS THROUGH FIRE ASSEMBLIES ARE TO BE FIRE STOPPED AND SEALED WITH ULC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE A SMOKE-TIGHT BARRIER.

ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.

THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.

WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN EXISTING AREAS (REFER TO FLOOR PLAN AND ROOM SCHEDULE) THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE PREPARED IN ACCORDANCE TO MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF NEW FLOOR.

WHERE PAINTING OF EXISTING WALLS IS INDICATED ON THE ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY EXISTING WALL COVERING, PATCHED & PREPARED TO ACCEPT NEW MATERIAL, UNLESS OTHERWISE NOTED.

**RENOVATION LEGEND:**

- X EXISTING ELECTRICAL EQUIPMENT TO BE REMOVED AND TURNED OVER TO THE OWNER OR AS DIRECTED BY THE ENGINEER. REMOVE, BLANK OFF, EXTEND OR RELOCATE ALL ASSOCIATED WIRING AND MAKE SAFE.
- \* EXISTING ELECTRICAL EQUIPMENT TO BE REMOVED AND REINSTALLED OR RELOCATED AS SHOWN UPON COMPLETION OF NEW CEILING OR WALL CONSTRUCTION. RE-WIRE OR EXTEND WIRING AS REQUIRED.
- ✓ EXISTING ELECTRICAL EQUIPMENT TO REMAIN IN ITS PRESENT LOCATION. RE-WIRE OR EXTEND WIRING AS REQUIRED.

**GENERAL DEMOLITION NOTES:**

- REMOVE ALL ABANDONED ELECTRICAL EQUIPMENT INCLUDING BUT NOT LIMITED TO SWITCHES, CONDUITS AND JUNCTION BOXES.
- ALL EXISTING EQUIPMENT NOT SHOWN ON THE PLAN SHALL REMAIN. IF FURTHER CLARIFICATION IS REQUIRED, THE CONTRACTOR SHALL OBTAIN WRITTEN DIRECTION FROM THE CONTRACT ADMINISTRATION.

**LEGEND:**

- PANELBOARD
- MOTOR LOAD
- HAND DRYER
- FIRE ALARM CONTROL PANEL (FACP)
- FIRE ALARM PULL STATION
- FIRE ALARM BELL
- SMOKE DETECTOR
- HEAT DETECTOR
- HAND DRYER
- SECURITY KEYPAD
- KEYPED SWITCH
- WALL MOUNT PA SPEAKER
- MOTION DETECTOR
- DOOR OPENER
- PUSHBUTTON DOOR OPERATOR SWITCH
- SECURITY CAMERA
- DUPLEX RECEPTACLE
- JUNCTION BOX
- SWITCH
- FAN SPEED CONTROL

0	ISSUED FOR CONSTRUCTION	CL	15.02.17
No.	REVISION/DESCRIPTION	BY	DATE

SEAL

DRAWN	GCN	CHECKED	DESIGNED	CLS	APPROVED
DATE	2014.10.27	USER	APPROVAL		

THE CITY OF WINNIPEG  
 PLANNING, PROPERTY AND  
 DEVELOPMENT DEPARTMENT  
 MUNICIPAL ACCOMMODATIONS DIVISION  
 3-65 GARRY STREET, R3C 4K4

PROJECT  
**SHERBROOK POOL  
 REFURBISHMENT OF SHERBROOK POOL**

381 SHERBROOK STREET  
 SHEET TITLE

ELECTRICAL  
 MAIN FLOOR PLAN  
 POWER & SYSTEMS - DEMOLITION

SCALE	PROJECT No:	SHEET No:
AS SHOWN	2013-173	E02

