



- NOTES:
1. HEADERS TO BE 3-38x235 WITH 2 JACK STUDS EACH END UNLESS NOTED OTHERWISE.
 2. JACK STUDS REFER TO STUDS ON WHICH HEADERS BEARS DIRECTLY.
 3. UNLESS NOTED OTHERWISE EACH END OF SHEAR WALL SEGMENT SHALL HAVE A 2-38x140 COLUMN FASTENED TO FOUNDATION WITH A HOLD DOWN ANCHOR AS PER DETAIL THIS SHEET. FASTEN 2-38x140 COLUMN TO TOP PLATE WITH 2 SPH6 SIMPSON TIES.
 4. ALL PLYWOOD SHEATHING TO BE FASTENED TO STUDS WITH 3" COMMON NAILS @ 150 O.C. TYPICAL.

PLAN - ELEVATION 232.75
1:50



B.M. ELEV.	DESIGNED BY	WH
	DRAWN BY	PDR
	CHECKED BY	NR
	APPROVED BY	ARR
	HOR. SCALE	AS NOTED
	VERTICAL	
2	ISSUED FOR ADDENDUM # 1	16/03/14 ARR
1	ISSUED FOR TENDER	16/03/04 ARR
NO.	REVISIONS	DATE BY DATE

DESIGNED BY WH
DRAWN BY PDR
CHECKED BY NR
APPROVED BY ARR
HOR. SCALE AS NOTED
VERTICAL

RELEASED FOR CONSTRUCTION
DATE

ENGINEER'S SEAL
PROVINCE OF MANITOBA
REGISTERED PROFESSIONAL ENGINEER
RATTANWANANCHAROEN
MARCH 4/16
Member
23609

CONSULTANT PROJECT NUMBER
13-8224

THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT

4R WINNIPEG DEPOT
PACIFIC AVENUE

HHW EWASTE BUILDING @ EL.
232.75, DETAILS

CITY DRAWING NUMBER
1-0851A-S0008-001

SHEET 16 OF 43

CONSULTANT DRAWING NUMBER
S-8

C:\projects\win\working_directory\active\4046\138224-09-STRUCT-CON-PACIFIC.dwg