



601-2015 ADDENDUM 4

CONTRACT 2 – HIGH RATE CLARIFIER AND GRIT REMOVAL STRUCTURAL CONCRETE & MISCELLANEOUS WORKS – SOUTH END WATER POLLUTION CONTROL CENTRE (SEWPCC) UPGRADING/EXPANSION PROJECT

ISSUED: September 21, 2015
BY: John Wiebe, P.Eng.
TELEPHONE NO. (204) 488-2214 x 73075

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20150806

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, September 24, 2015.

PART E – SPECIFICATIONS

Revise: NMS Division 01
Section 01 11 00
Clause 1.2.C Revise Description of Work in the table for the drawings noted:

Drawing Reference	Description of Work
1-0102-PGAD-K012	Supply and Install embedded pipe spools for 300-HRS-CS01 as shown on the drawings. All other electrical and mechanical equipment is by OTHERS.

Revise: NMS Division 10
Section 10 80 00
Clause 2.2.B.8.b.2 Nominal Size: 762 mm x 762 mm. Quantity: 8 units at Roof of Grit tanks, **2 units at High Rate Clarification Building.**

Revise: NMS Division 10
Section 10 80 00
Clause 2.2.B.8.b.3 Nominal Size: 750 mm x 900 mm. Quantity: **2 units at Roof of Grit tanks, 4 units at High Rate Clarification Building Influent Channel.**

QUESTIONS AND ANSWERS

Q1: Please reference Add#2 – page 7, Q&A #32. Are the davit bases to be powder coated/zinc plated mild steel or stainless steel. Cast in place davit bases are recommended to be of 316 stainless construction.

A1: Cast in place davit bases shall be of 316 stainless construction.

Q2: Please reference BGAD-P002, Room Finish Schedule. Is the floor and base finish for Stair P-101 included in Bid Op 601-2015? If so, please provide a specification section for Seamless Flooring (Quartz)

A2: Room Finish Schedule BGAD-P002 was revised by Addendum 2.