



| Tag | Finish | Specification |
|-----|--------|---|
| M1 | THRSM | Thermobond Grade 3; Thermobond Brushed Steel |
| M2 | THRSM | LPL White Side B |
| M3 | MEL | LPL White Drawer Parts |
| M4 | MEL | Finished Back Panel - Double Sided LPL Substrate (Pre-Finished); LPL White |
| M5 | THRSM | Thermobond Grade 1; Thermobond Snow White |
| M6 | THRSM | Thermobond Grade 1; Thermobond Ash White |
| M7 | PNT | Grade 1 - Standard Chrome Coat - Powder White DCC2 |
| M8 | HPL | HPL - Grade 1-HPL, Frosty White |
| M9 | PWD | Powder Coated Metallic; Powder Coat - Shimmer DP465 |
| M10 | ANO | Grade 1 Anodized; Anodized Finish - Clear |
| M11 | GLS | Center Mounted Tempered Glass; 6mm Tempered Glass - Clear; No Edge Polish 5.0mm |
| M12 | GLS | Side Bull Tempered Glass; 10mm Tempered Glass - Clear; Flat Polish all edges 10.0mm |
| M13 | PNT | Grade 1 - Standard Chrome Coat - Fog DCC2 |
| M14 | PWD | Powder Coated; Powder Coat - Shimmer DP465 |
| M15 | GLS | Grade 1 (Non-metallic) Backcoat; Sapphire Glass; Starwhite; Flat Polish all edges 5.0mm |
| M16 | WTO | No Tile |
| M17 | PWD | Powder Coat - Black DP13 |

NOTES:

THESE DRAWINGS SHALL NOT BE SCALED.

THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.

THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.

ALL OPENINGS THROUGH FIRE ASSEMBLIES ARE TO BE FIRE STOPPED AND SEALED WITH ULC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE A SMOKE-TIGHT BARRIER.

ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.

THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.

WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN EXISTING AREAS (REFER TO FLOOR PLAN AND ROOM SCHEDULE) THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED, UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE PREPARED IN ACCORDANCE TO MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF NEW FLOOR.

WHERE PAINTING OF EXISTING WALLS IS INDICATED ON THE ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY EXISTING WALL COVERING, PATCHED & PREPARED TO ACCEPT NEW MATERIAL, UNLESS OTHERWISE NOTED.

- FURNITURE NOTES:**
- CONTRACTOR TO OBTAIN THREE QUOTES FOR DEMOUNTABLE FURNITURE WALL SYSTEM - DIRTY WALL AND/OR EQUAL. EQUAL/ALTERNATES TO BE SUBMITTED TO CONTRACT ADMINISTRATOR FOR REVIEW AND APPROVAL PRIOR TO CLOSE OF BID.
 - CONTRACT ADMINISTRATOR TO SELECT FROM MANUFACTURERS FULL RANGE OF STANDARD COLOURS AND FINISHES FOR DEMOUNTABLE WALL SYSTEM.

FILM DOORS, LETTERING, AND NUMBERING
 MACMARK GLASS DECOR 700, DUSTED GLASS TRANSLUCENT VINYL FILM. SEE ELEVATIONS FOR FURTHER DETAILING.

DOORS TO BE FROSTED FULL HEIGHT AND WIDTH OF GLAZING.

NUMBERING TO BE HELVETICA FONT, 8" IN HEIGHT, CENTRED HORIZONTALLY ON GLAZING UNIT. BOTTOM OF NUMBER TO BE 7-2" AFF.

LETTERING TO BE HELVETICA FONT, 4 1/2" IN HEIGHT, TOP ROW OF TEXT TO BE 6'-6" AFF. ALL TEXT POSITIONED HORIZONTALLY AS INDICATED.

ISSUED FOR CONSTRUCTION - CEA - 08.24.15

| No. | REVISION/DESCRIPTION | BY | DATE |
|-----|----------------------|----|------|
| | | | |



| DRAWN | CAM | CHECKED | CAD | DESIGNED | CAD | APPROVED | CAD |
|-------|------------|---------|-----|----------|-----|----------|-----|
| DATE | 2015.08.24 | USER | TC | | | | |

Winnipeg
 THE CITY OF WINNIPEG
 PLANNING, PROPERTY AND
 DEVELOPMENT DEPARTMENT
 MUNICIPAL ACCOMMODATIONS DIVISION
 3-65 GARRY STREET, R3C 4K4

PROJECT
 RICE BUILDING
 CITY OF WINNIPEG
 PARKING AUTHORITY
 481 PORTAGE AVE.

SHEET TITLE
 FURNITURE SYSTEM
 ELEVATIONS 1

| SCALE | PROJECT No: | SHEET No: |
|--------------|-------------|-----------|
| 1/4" = 1'-0" | 2013-127 | A4 |

DRAWING SHEET SIZE: A1 (841mm x 594mm) PLOT 1:1