

1.0 GENERAL CONDITIONS

1.1 SCOPE OF WORK

- .1 The Work to be done under this Contract shall consist of the removal and disposal of existing flooring material surfaces and rubber base, existing concrete slab substrate preparation, and the supply and installation of new 2' x 2' carpet tile and sheet vinyl flooring complete with rubber wall base.

2.0 MATERIALS

2.1 PRODUCT DESCRIPTIONS

CARPET TILE

- .1 **ACCEPTABLE PRODUCT:** SHAW CONTRACT GROUP 2" x 24" Carpet Tiles or an approved equal in accordance with B7.

Style Name	Tempt Tile
Style Number	5T019
Color Name	Tease
Color Number	18504
Construction	Multi-level pattern loop
Fiber	ECO solution Q nylon
Protective Treatment	SSP Shaw soil protection
Gauge	½
Stiches per inch	9.0
Tufted weight	16.0 oz./yd(2)
Finished Pile Thickness	0.117
Average Density	4,923 oz/yd(2)
Dye Method	100% solution dyed
Secondary Backing	Ecoworx tile
Coordinating Products	Tangle Tile

- .2 Rubber Wall Base (to be supplied and installed by Contractor): JOHNSONITE INC. BASEWORKS traditional rubber wall base, 4" height. Colour: Charcoal 20.

- .3 Finishing Accessories (to be supplied and installed by Contractor): JOHNSONITE INC. rubber transition strips:
- | | |
|-----------------------------------|--|
| RT1 – Adaptor TBD, Colour Grey 48 | New Carpet to existing Ceramic Tile |
| RT2 – SLT-48-C, Colour Grey 48 | New Carpet to new Sheet Vinyl Flooring |
| RT3 - Adaptor TBD, Colour Grey 48 | New Carpet to existing Sheet Vinyl Floor |

SHEET VINYL FLOORING

- .1 **ACCEPTABLE PRODUCT:** TARKETT IQ Optima sheet vinyl flooring complete with 4" height coved base or an approved equal in accordance with B7.

Light Fastness (EN ISO 105-B02)	> 6
Thermal Resistance (EN 12667)	0.01
Thermal Conductivity	0.01
Total Thickness (EN 428)	2 mm
Wear Layer thickness (EN 429)	2 mm
Total Weight (EN 430)	2.8
Unit	KG/M ²
Residual Indentation (EN 433)	0.03
Description (EN 649)	Homogeneous single layered vinyl
Classification – Commercial (EN 685)	Class 34

.2 **DELIVERY, STORAGE AND HANDLING**

Store products and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by Flooring Manufacturer's.

Protect flooring surfaces with no traffic for 24 hours after installation. No heavy traffic, rolling loads, or furniture placement for 72 hours after installation.

Provide final clean, vacuuming, washing of flooring surfaces affected by the flooring installation work. Patch, prime and paint existing walls, doors and door frames to match existing conditions.