



876-2015 ADDENDUM 1

2015 STORMWATER RETENTION BASIN REVETMENT REPLACEMENT FOR LAKES 3-14 AND 4-5

ISSUED: October 16, 2015
BY: Newton Conti
TELEPHONE NO. 204 986-3179

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20150806

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 876-2015 Bid Submission with 876-2015 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

- Form B(R1): Revise: Item No. A.2 – New revetment surface course approximate quantity to read 75 m².
- Revise: Item No. D.1 – Geotextile Fabric approximate quantity to read 4100 m².
- Add: Item No. A.4 – Pumping to lower water level
- Add: Item No. D.2 – New revetment surface course

Page numbering on some forms may be changed as a result.

PART B – BIDDING PROCEDURES

Revise: B17.4 (b) to read: If the lowest evaluated responsive Bid submitted by a responsible qualified Bidder exceeds the budgetary provisions for the Work, the Total Bid Prices of all responsive Bids submitted by responsible and qualified Bidders will be adjusted by progressively deducting:

- (i) Item A.4, Lake 3-14 Pumping to lower lake level, in its entirety;
- (ii) Item C, Lake 4-5 North Side, in its entirety;
- (iii) Item B, Lake 4-5 South Side, in its entirety;

in the order listed, until a Total Bid Price within the budgetary provision is achieved.

PART E – SPECIFICATIONS

Revise: E3.2 to read: The City will not be responsible for the amount of, or duration of fluctuations in ice or water levels in the event surface run-off, water main breaks or other circumstances contributing water to the lakes. During the construction period, the Contractor shall be responsible for providing pumping to maintain the lake water elevation at the required level to complete the Work.

- Add: E3.4 The water level at Lake 4-5 will be lowered by the City to facilitate the required construction.
- Add: E3.5 It will be the Contractor's responsibility to lower the water level at Lake 3-14 to facilitate the required construction. The Contractor must submit plans to lower the water level for approval to the Contract Administrator prior to the start of the work. The Contract Administrator reserves the right to cancel work associated with lowering the water level if the costs exceed budget as specified in B17.4 (b) or weather prohibits the safe lowering of water levels. If the water level is not lowered, the revetment renewal will be limited to the area above the normal water level as specified in the drawings or as directed by the Contract Administrator.

DRAWINGS

Replace: 876-2015 Drawing LD-7501 R0 with 876-2015 Addendum 1 Drawing LD-7501 R1