

The City of Winnipeg  
Water and Waste Department  
Engineering Division



# Wilkes Reservoir North Cell Rehabilitation

Bid Opportunity 930-2015

## Mandatory Bidder's Conference

Held at: Dillon Consulting Limited  
1558 Willson Place  
Winnipeg, MB R3T 0Y4

December 2 & 3, 2015 – 10:00am

City Project Manager  
Rob Carroll, P.Eng.

Dillon Consulting Limited  
Sital Rihal, M.Eng., P.Eng.  
David Amorim, EIT  
Fred Kemp, P.Eng.

# Introductions




# Outline

- Project Background
- Project Site
- Laydown Area (Completed by Others)
- Security Requirements
- Environmental Requirements
- Project Scope and Details
- Equipment Restrictions Within the Site
- Material Requirements Within the Cells
- Conclusions
- Q&A


# Project Background






## Project Background

- Wilkes Reservoir constructed as an open cell reservoir in 1960 and reconstructed as an enclosed cell in 1980.
- 1980 reconstruction divided the North Cell into East and West cells.
- Reconstruction of the North Cell consisted of:
  - Cast-in-place perimeter wall and footing on hexagonal precast concrete piles.
  - Interior precast columns founded on cast-in-place footings with hexagonal precast concrete piles. Columns on a 10 m x 11 m grid.
  - Precast inverted-tee beams supporting 1220 mm x 305 mm hollowcore roof slabs.
  - Replacement of approximately 30% of the existing unreinforced concrete floor slab.
  - Roof envelope: minimal waterproofing. Reservoir left uninsulated.




## Project Background Cont.

- Within 3 years of reconstruction, major issues were noted with the reservoir during routine inspections including:
  - Roof envelope did not perform to prevent leakage into cells.
  - Foundation settlements and roof depressions.
  - Uncontrolled roof movements with jamming of expansion joints.
  - Concrete spalling at ends of precast concrete beams.
  - Side splitting and bulging of the precast beam neoprene bearing pads.
  - Popouts and cracking in hollowcore slabs.
- Freeze/thaw cycles without adequate waterproofing and insulation contributed to rapid deterioration.



## Project Background Cont.

- In 1988, detailed review of North Cell performance issues completed.
- Majority of problems attributed to performance of roof envelope.
- In 1991-1992, the North Cell was rehabilitated to address the noted problems.
  - 1991 – Structural Rehabilitation.
  - 1992 – Building envelope installation.
- Rehabilitation consisted of:
  - Replacement of deteriorated hollowcore slabs.
  - Installation of new building envelope: protected membrane roof (PMR) consisting of EPDM membrane on protection board, rigid insulation and a geotechnical fabric held down by concrete paving slabs.
  - Miscellaneous concrete repairs: beam end spalls and hollowcore popouts/cracking.
  - Underpinning of pile caps to control foundation settlement.




## Project Background Cont.

- In 2013, Dillon was retained by WWD to perform a Condition Assessment of the North Cell.
- Condition Assessment included:
  - Exterior Inspection:
    - Roof elevation survey
    - Inspection of building envelope
  - Interior Inspection:
    - Underside of roof (hollowcore slabs/beams) by boat
    - Floor slabs/walls/suction pits of empty cells








## Project Background Cont.

- 2013/2014 Assessment findings:
  - Failure of building envelope.
  - Continued structural deterioration since 1991-1992 rehabilitation including:
    - Continuing foundation settlement and roof depression at column F-16.
    - Deterioration of some concrete pile caps – spalling.
    - Increased deterioration of neoprene bearing pads supporting precast beams ... pads at end of service life.
    - Increased deterioration of roof elements - hollowcore slab cracking, precast beam spalling.
- Assessment recommendations:
  - Rehabilitation of North Cell to address building envelope problems and most severe structural issues to extend its service life by another 50 years.
- In 2014, Dillon retained to complete the detailed design for the rehabilitation of the North Cell.

# Project Site







North Gate off Hurst Way  
(City of Winnipeg use only)

Hurst Way

NORTH

Secured Area Boundary

North Cell

East Cell  
(Stage 2  
2017)

West Cell  
(Stage 1  
2016)


South Cell

Willson Place

Fennell St

Edderton Ave

Google





Laydown Area South Gate  
(Main Access to Site)

Hurst Way



Secured Area  
Boundary

East Cell  
(Stage 2  
2017)

Stage 1  
West Cell  
16

South Cell

Laydown Area

Willson Place

Edderton Ave

Waverley St

Victor Lewis Dr

Fennell St

Google

# Laydown Area (Completed by Others)

# Laydown Area

- Constructed by others (City of Winnipeg Bid Opportunity 711-2015).
- Approximately 35 m x 150 m granular pad enclosed with 3.0 m high barbed wire fencing.
- Will be main storage area for materials, deliveries, site offices, parking, etc.
- Security clearances not required within laydown area (see Security Requirements).
- South gate of laydown area to be locked when Contractor not on site.






# Security Requirements

# Security Clearance Requirements

## D10 - Criminal Record Search Certificate and Public Safety Verification Check Part F – Security Clearance

- ALL personnel working on Site required to obtain these clearances.
- Clearances to be submitted at least three (3) Business Days prior to commencement of the Works.
- Only exceptions are as follows:
  - Personnel working solely within the laydown area do not require clearances provided they do not cross the north gate into the secured Reservoir area.
  - Contractor’s supervisor to provide an escort for delivery drivers w/o clearance while within the secured area. Delivery drivers must stay within 5 m of their vehicle at all times.






# Security and Access to Site

## E8 – Security and Access to Site

### Security Guard

- Security guard from a bonded security company required at north end of the laydown area (vehicle/pedestrian gate).
- Guard responsible for validating the security clearances of all personnel accessing the secured area.



### Keys to Site

- Contractor will be issued three keys to the secured construction area.
- Keys require a \$10,000 holdback which will be released upon return of keys at Substantial Performance (end of Stage 2 – 2017)

# Environmental Requirements



# Environmental Requirements

- E3 Environmental Plan
- Need to submit Environmental Protection Plan.
  - Includes a Fuel Handling and Storage Plan
  - Contractor to propose refueling procedures/location for approval
  - Requires some form of fuel containment
  - Requires membranes under large stationary equipment e.g. cranes



Example of vehicle berm for fuel containment during refueling (Basic Concepts Inc.)

# Project Scope and Details

# Critical Dates

- STAGE 1 – West Cell Works
  - April – October 2016
- STAGE 2 – East Cell Works
  - April – October 2017
- Stage 1 Completion – October 31, 2016
- Stage 2 Completion – October 31, 2017
- Substantial Performance – October 31, 2017
- Total Performance – November 15, 2017



## NOTE:

- D16 – Detailed Work Schedule
- Schedule is critical and will be monitored closely
- Schedule is firm and no extensions to critical dates will be permitted



# Scope of Work

## STAGE 1 – West Cell Works (April – October 2016)

- Remove/replace building envelope
- Supply/install temperature monitoring system
- Hollowcore slab rehabilitation
- Bearing replacement
- Wall expansion joint repairs
- Concrete spall repairs
- Gel injection at suction pits
- Supply/install steel stairways into cell
- Cell cleaning

## STAGE 2 – East Cell Works (April – October 2017)

- Remove/replace building envelope
- Supply/install temperature monitoring system
- Hollowcore slab rehabilitation
- Bearing replacement
- Wall expansion joint repairs
- Concrete spall repairs
- Gel injection at suction pits
- Supply/install steel stairways into cell
- Underpinning pile cap F-16
- Cell cleaning

Cleaning must be completed and Cells turned over to the City by October 31 of each year



# Project Scope and Details

## Exterior Cell Works

# Removal and Replacement of Building Envelope

## REMOVAL

- Remove existing building envelope
- Salvage steel grid line marker plates

## REPLACEMENT

- Install new building envelope

View of existing roof




Typical steel grid line marker plate




## Existing roof envelope exposed during 2013-2014 Condition Assessment



## New Building Envelope for Reservoir Roof



# New Building Envelope for Entrance Building



## Replacement/Repair of Hollowcore Slabs

Replace designated hollowcore slabs with new slabs

Repair designated hollowcore slabs

- Cut slots into each void from above
- Place rebar
- Fill voids solid with SCC






## Hollowcore Slab Replacement




### For information

- Note: See drawings for load restrictions for equipment operating on the roof.
- Picture shows a system used to install hollowcore slabs during the 1991 rehabilitation.
- Contractor to submit proposed hollowcore replacement method for review and approval.

# Typical Hollowcore Slab Repair



2 DETAIL  
TYPICAL HOLLOWCORE REPAIR  
1:25




3 SECTION  
1:10




# Project Scope and Details

## Interior Cell Works



Note: Access into Cells will be via scaffolding stairway at designated hollowcore removal locations (shown on Drawings). Access building not to be used for access unless approved



Existing equipment access hatches  
(2.6 m x 4.1 m)

Approximate locations  
of temporary access  
(scaffolding/stairway)

## Project Scope and Details

# Video 1 – Cell Access and General Construction

## Project Scope and Details


# Video 2 – Access Building and Roof Structure

## Project Scope and Details



# Video 3 – Access Panels and Suction Pit




## Gel Injection at Suction Pits



# Wall Expansion Joint Replacement





# Steel Stairway




## Type 1 – Interior Column Shoes

- At beam ends with concrete spalling




## Type 2 – Interior Column Plates




- At good beam ends






# Type 3 – Wall Seat Plates



## Type 4 – Double Column Plates




## Type 5 – Quadruple Column Plates






# Concrete Spall Repairs Beam Ends



## Concrete Spall Repairs Pile Caps



Water Supply  
For Cell Clean-up



# Equipment Restrictions Within the Site

# Equipment Restrictions Include:

## Within the Cells

- NO gas, diesel, or any other fossil fuels permitted.
- Equipment shall be electric, battery powered, or pneumatic.
- NO vibratory/heavy equipment within 3 m of existing 1200 mm dia. Suction Line No. 4 below floor slab (between Grid line 7-8)

## On Reservoir Roof


- Only one piece of equipment permitted on hollowcore slab at any time meeting the following load restrictions:
- During removal of existing concrete pavers
  - 5300 kg max GVW
  - 3500 kg max single axle load
- After removal of existing concrete pavers
  - 7200 kg max GVW
  - 4400 kg max single axle load

## Within 5 m of Reservoir Walls

- NO heavy equipment (> 25 tonnes GVW) within 5 m of Reservoir walls

## Within 5 m of By-pass Line

- NO equipment within 5 m of by-pass line



# Material Requirements Within the Cells

# NSF/ANSI 61 Compliance Requirement

- All repair materials in contact with potable water shall meet NSF/ANSI 61 certifications.
- Includes:
  - Expansion joint systems
  - Gel for injection around suction pits
  - Epoxy for bearing assembly installation
  - Spall repair grouts
  - Others as required by the Specifications
- Contractor shall provide compliance reports and access to materials so they can be inspected for the NSF compliance label.
- **Note: Compliance is non-negotiable (Provincial requirement of operating licence)**



# Summary of Major Submissions






# Summary of Major Submissions

## Prior to Commencement of any Work – D18

- Criminal Record Search Certificates & Public Safety Verification Checks – D10
- Safe Work Plan – D12
- Detailed Work Schedule – D16
  - Includes a schedule review meeting with the Contract Administrator to approve proposed schedule
- Construction Method Statement – D17
- Preconstruction Site Record – D20
- Environmental Protection Plan – E3

- Shop Drawings – E4/E5
  - Note: To meet tight construction schedule, Shop Drawing submission to be expedited



# Conclusion

## Closing Notes...

- Optional Site Investigation – December 7, 2015 at 11:00 a.m. at the laydown area south gate.
- Public Safety Verification Check required 24 hrs in advance.
- Bid Opportunity submission deadline – December 11 at 12:00 p.m.
- City will obtain and pay for all necessary building permits for the Works.

# Thank You

## Questions and Answers

