SUPPLY: 208V 3Ø 4W
MAINS AMPACITY: 600
INCOMING: ☐ BREAKER ■ LUGS
MAIN BREAKER REQUIRED: ■ YES ☐ NO
MAIN BREAKER AMPS:
BUS MATERIAL: ■ COPPER ☐ ALUMINUM
BUS AND BREAKER RATING: 18kA

NAME PLATE:

PANEL ' SP-1 '

LOCATION: CRAWLSPACE ELECTRICAL ROOM
MOUNTING: ■ SURFACE ☐ FLUSH
MANUFACTURER:
MODEL NO:
BREAKER: ☐ PLUG-IN ■ BOLT-ON
SPD: ☐ YES ■ NO
SERVICE ENTRANCE RATED: ☐ YES ■ NO

REV	CCT		VA	P	BKR	A	B	C	BKR	P	VA		CCT	REV	REV	CCT		VA	P	BKR	A	B	C	BKR	P	VA		CCT	REV
	1	RETURN FAN: RF-1	1000	2	15	●			15	2	2250	UNIT HEATER: UH-1	2			67	C-3 CHEMICAL FEED PUMP	1200	1	15	●			15	1	1050	LIGHTING: SPLASH PAD	68	
	3						●						4			69	C-4 CHEMICAL FEED PUMP	1200	1	15		●		15	1	1050	LIGHTING: SPLASH PAD	70	
	5	HEAT RECOVERY VENTILATOR: HRV-1	4000	3	25			●	15	2	2250	UNIT HEATER: UH-2	6			71	L-1: WATER LEVELLER SPLASH PAD	1200	1	15			●	15	1	191	LIGHTING: ROOM 120	72	
	7					●							8			73	L-2: WATER LEVELLER POOL	1200	1	15	●			15	1	207	LIGHTING: ROOMS 100, 101, 103	74	
	9						●						10			75	T-SLOT RECEPTACLES – SWIMSUIT DRYER	1200	1	20		●		15	1	93	LIGHTING: 104	76	
	11	HEAT RECOVERY VENTILATOR: HRV-2	600	1	15			●	15	2	2250	UNIT HEATER: UH-3	12			77	T-SLOT RECEPTACLES – SWIMSUIT DRYER	1200	1	20			●	15	1	1021	LIGHTING: 102	78	
	13	BOILER: B-1	1200	1	15	●			15	2	2250	UNIT HEATER: UH-4	14			79	T-SLOT RECEPTACLES – SWIMSUIT DRYER	1200	1	20	●			15	1	750	LIGHTING: 107, 108, 105, 110, 112, 113	80	
	15	BOILER: B-2	1200	1	15		●						16			81	SPARE	–	2	15		●		15	1	1000	LIGHTING: 113, 114, 115, 116, 117, 118	82	
	17	BOILER: B-3	1200	1	15			●	15	2	2250	UNIT HEATER: UH-5	18			83							●	15	1	650	LIGHTING: 000	84	
	19	BOILER: B-4	1200	1	15	●							20			85	SPARE	–	2	15	●			15	1	750	LIGHTING: 001, 004, 200	86	
	21						●						22			87						●		15	1	1200	UV-1: ULTRAVIOLET SYSTEM	88	
	23	POOL HEATING CIRCULATION PUMP: PU-3	1000	2	15			●	60	3	8750	PP-1: SPRAY PAD CIRC PUMP	24			89	SPARE	–	2	15			●	40	1	3200	UV-2: ULTRAVIOLET SYSTEM	90	
	25					●							26			91					●			15	1	600	TELECOMMUNICATION RACK	92	
	27	POOL HEATING CIRCULATION PUMP: PU-4	1000	2	15		●						28			93	SPARE	–	2	20		●		15	1	–	SPARE	94	
	29							●	60	3	8750	PP-2: FEATURE SPARY PUMP	30			95							●	15	1	–	SPARE	96	
	31	POOL HEATING CIRCULATION PUMP: PU-7	1000	2	15	●							32			97	SPARE	–	2	20	●			15	1	–	SPARE	98	
	33						●						34			99						●		15	1	–	SPARE	100	
	35	POOL HEATING CIRCULATION PUMP: PU-8	1000	2	15			●	40	3	6000	PP-3: GROUND SPRAY PUMP	36			101	EXHAUST FAN: EF-1	10	1	15			●	15	1	–	SPARE	102	
	37	GLYCOL MAKEUP UNIT: GMU-1	110	1	15	●							38			103	HEAT RECOVERY VENTILATOR: HRV-3	–	1	–	●			15	1	–	SPARE	104	
	39	WATER MAKUP UNIT: WMU-1	110	1	15		●						40			105	PLUMBING FIXTURE: P-3	600	1	15		●		15	1	–	SPARE	106	
	41	WOMENS – AUTO FLUSH UNITS	400	1	15			●	40	3	6000	PP-4: TWISTER SLIDE SPRAY PUMP	42			107	PLUMBING FIXTURE: P-4	600	1	15			●	15	1	–	SPARE	108	
	43	MENS – AUTO FLUSH UNITS	400	1	15	●							44			109	PLUMBING FIXTURE: P-5	600	1	15	●			15	1	–	SPARE	110	
	45	SPARE	–	1	15		●						46			111	PLUMBING FIXTURE: P-6a	600	1	15		●		15	1	–	SPARE	112	
	47	SPARE	–	1	15			●	25	3	6000	PP-5: KMR SPRAY PUMP	48			113	WATER FOUNTAIN: P-10a	600	1	15			●	20	1	–	SPARE	114	
	49	SPARE	–	1	15	●							50			115	LIGHTING	600	1	15	●			20	1	–	SPARE	116	
	51	SPARE	–	1	15		●						52			117	LIGHTING	600	1	15		●		20	1	–	SPARE	118	
	53	RECEPTACLE: ROOF TOP	1200	1	20			●	25	3	6000	PP-6: POOL CIRC PUMP	54			119	LIGHTING	600	1	15			●	20	1	–	SPARE	120	
	55	RECEPTACLE: ROOF TOP	1200	1	20	●							56			121	LIGHTING	600	1	15	●			20	1	–	SPARE	122	
	57	TEMPERED WATER RETURN PUMP: PU-9	600	1	15		●		15	1	1200	CAT-1: CHEMICAL CONTROLLER SPLASH PAD	58			123	LIGHTING	600	1	15		●		20	1	–	SPARE	124	
	59	DOMESTIC HOT WATER RETURN PUMP: PU-10	600	1	15			●	15	1	1200	CAT-2: CHEMICAL CONTROLLER POOL	60			125	LIGHTING	600	1	15			●	20	1	–	SPARE	126	
	61	CABINET UNIT HEATER: CUH-1	400	1	15	●			15	1	600	RECEPTACLES: MEZZANINE	62			127	LIGHTING	600	1	15	●			20	1	–	SPARE	128	
	63	C-1 CHEMICAL FEED PUMP	1200	1	15		●		15	1	1050	LIGHTING: SPLASH PAD	64			129	LIGHTING	600	1	15		●		20	1	–	SPARE	130	
	65	C-2 CHEMICAL FEED PUMP	1200	1	15			●	15	1	1050	LIGHTING: SPLASH PAD	66			131	LIGHTING	600	1	15			●	20	1	–	SPARE	132	

LOAD 'A'	LOAD 'B'	LOAD 'C'
35,634	34,645	34,645

SUPPLY: 208V 3Ø 4W
MAINS AMPACITY: 225
INCOMING: ☐ BREAKER ■ LUGS
MAIN BREAKER REQUIRED: ■ YES ☐ NO
MAIN BREAKER AMPS:
BUS MATERIAL: ■ COPPER ☐ ALUMINUM
BUS AND BREAKER RATING: 18kA

NAME PLATE:

PANEL ' SP-2 '

LOCATION: CRAWLSPACE
MOUNTING: ■ SURFACE ☐ FLUSH
MANUFACTURER:
MODEL NO:
BREAKER: ☐ PLUG-IN ■ BOLT-ON
SPD: ☐ YES ■ NO
SERVICE ENTRANCE RATED: ☐ YES ■ NO

REV	CCT		VA	P	BKR	A	B	C	BKR	P	VA		CCT	REV
	1	RECEPTACLES: OUTDOOR	600	1	15	●			20	2	2300	HAND DRYER: ROOM 112	2	
	3	RECEPTACLES: OUTDOOR	600	1	15		●						4	
	5	RECEPTACLES: OUTDOOR	600	1	15			●	20	2	2300	HAND DRYER: ROOM 113	6	
	7	T-SLOT RECEPTACLES: SPLASH PAD, ROOM 119	1200	1	20	●							8	
	9	T-SLOT RECEPTACLES: ROOMS 124, 125	1200	1	20		●		20	2	2300	HAND DRYER: ROOM 110	10	
	11	T-SLOT RECEPTACLE: SUIT DRYER ROOM 115	1200	1	20			●					12	
	13	T-SLOT RECEPTACLE: SUIT DRYER ROOM 118	1200	1	20	●			20	2	2300	HAND DRYER: ROOM 110	14	
	15	T-SLOT RECEPTACLE: SUIT DRYER ROOM 110	1200	1	20		●						16	
	17	RECEPTACLES: ROOMS 113, 114, 122	600	1	15			●	20	2	2300	HAND DRYER: ROOM 114	18	
	19	RECEPTACLES: ROOMS 116, 117	600	1	15	●							20	
	21	T-SLOT RECEPTACLES: ROOMS 109, 102	1200	1	20		●		20	2	2300	HAND DRYER: ROOM 114	22	
	23	RECEPTACLES: ROOMS 112, 113	600	1	15			●					24	
	25	RECEPTACLES: ROOM 120	1200	1	20	●			20	2	2300	HAND DRYER: ROOM 116	26	
	27	RECEPTACLE: DISHWASHER	600	1	15		●						28	
	29	RECEPTACLE: FRIDGE	600	1	15			●	20	2	2300	HAND DRYER: ROOM 116	30	
	31	RECEPTACLES: ROOM 120	600	1	15	●							32	
	33	RECEPTACLES: ROOM 120	600	1	15		●		20	2	2300	HAND DRYER: ROOM 122	34	
	35	RECEPTACLES: ROOM 104	600	1	15			●					36	
	37	RECEPTACLES: ROOMS 103, 104	600	1	15	●			15	1	1200	DOOR OPERATORS (F & M SHOWER)	38	
	39	RECEPTACLES: ROOM 103	600	1	15		●		15	1	1200	DOOR OPERATORS 113, 116, 122	40	
	41	RECEPTACLES: ROOMS 105, 106	600	1	15			●	15	1	1200	DOOR OPERATORS 112A, 112B	42	
	43	VENDING MACHINE RECEPTACLE	1200	1	15	●			15	1	1200	DOOR OPERATORS VEST 100	44	
	45	VENDING MACHINE RECEPTACLE	1200	1	15		●		15	1	600	FIRE ALARM CONTROL PANEL	46	
	47	VENDING MACHINE RECEPTACLE	1200	1	15			●	15	1	600	FIRE ALARM CONTROL PANEL	48	
	49	CHANGE ROOMS DISTRESS ALARM	600	1	15	●			15	1	–	SPARE	50	
	51	RECEPTACLES: ROOMS 001, 004	600	1	15		●		15	1	–	SPARE	52	
	53	RECEPTACLES: ROOM 002	600	1	15			●	15	1	–	SPARE	54	
	55	TURNSTILES	–	1	15	●			15	1	–	SPARE	56	
	57	TURNSTILES	–	1	15		●		15	1	–	SPARE	58	
	59	SPARE	–	1	20			●	15	1	–	SPARE	60	
	61	SPARE	–	1	20	●			15	1	–	SPARE	62	
	63	SPARE	–	1	20		●		15	1	–	SPARE	64	
	65	SPARE	–	1	20			●	15	1	–	SPARE	66	
	67	SPARE	–	1	20	●			15	1	–	SPARE	68	
	69	RECEPTACLES: ROOM 103	600	1	15		●		–	–	–		70	
	71	HEAT TRACE CONTROLLER	–	1	20			●	–	–	–		72	
	73	HEAT TRACE CONTROLLER	–	1	20	●			–	–	–		74	
	75	DOORS: D-100A, D-111, D-112, D-113	600	1	15		●		–	–	–		76	
	77	DOORS: D-115A, D-115B	600	1	15			●	20	1	1200	SP-1	78	
	79	DOORS: D-117A, D-117B, D-119, D-122	600	1	15	●			20	1	1200	SP-2	80	
	81	DOORS: D-109, D-110, D-111, D-120B	600	1	15		●		15	1	600	POOL DECK DROWNING ALARMS & BEAM DETECTORS	82	
	83		–	–	–			●	15	1	600	POOL DECK DROWNING ALARMS & BEAM DETECTORS	84	

LOAD 'A'	LOAD 'B'	LOAD 'C'
18,900	18,900	18,900

SUPPLY: 600V 3Ø 4W
MAINS AMPACITY: 600
INCOMING: ☐ BREAKER ■ LUGS
MAIN BREAKER REQUIRED: ■ YES ☐ NO
MAIN BREAKER AMPS:
BUS MATERIAL: ■ COPPER ☐ ALUMINUM
BUS AND BREAKER RATING: 25kA

NAME PLATE:

PANEL ' 6SP-1 '

LOCATION: CRAWLSPACE ELECTRICAL ROOM
MOUNTING: ■ SURFACE ☐ FLUSH
MANUFACTURER:
MODEL NO:
BREAKER: ☐ PLUG-IN ■ BOLT-ON
SPD: ☐ YES ■ NO
SERVICE ENTRANCE RATED: ☐ YES ■ NO

REV	CCT		VA	P	BKR	A	B	C	BKR	P	VA		CCT	REV
	1												2	
	3	TRANSFORMER: TR-SP1	112500	3	150		●		300	3	240000	AIR HANDLING UNIT: AHU-1	4	
	5							●					6	
	7					●							8	
	9	POOL HEATING BOILER CIRCULATION PUMP: PU-1	2500	3	15		●		25	3	18000	AIR HANDLING UNIT: AHU-2	10	
	11							●					12	
	13					●							14	
	15	POOL HEATING BOILER CIRCULATION PUMP: PU-2	2500	3	15		●		15	3	12000	AIR HANDLING UNIT: AHU-3	16	
	17							●					18	
	19					●							20	
	21	POOL HEATING BOILER CIRCULATION PUMP: PU-5	2500	3	15		●		15	3	–	SPARE	22	
	23							●					24	
	25					●							26	
	27	POOL HEATING BOILER CIRCULATION PUMP: PU-6	2500	3	15		●		15	3	–	SPARE	28	
	29							●					30	
	31					●							32	
	33	SPARE	–	3	15		●		60	3	45000	TRANSFORMER: TR-SP2	34	
	35							●					36	
	37					●			–	–	–		38	
	39	SPARE	–	3	15		●		–	–	–		40	
	41							●	–	–	–		42	
	43					●			–	–	–		44	
	45	SPARE	–	3	20		●		–	–	–		46	
	47							●	–	–	–		48	
	49					●			–	–	–		50	
	51	SPARE	–	3	20		●		–	–	–		52	
	53							●	–	–	–		54	
	55		–	–	–	●			–	–	–		56	
	57		–	–	–		●		–	–	–		58	
	59		–	–	–			●	–	–	–		60	
	61		–	–	–	●			–	–	–		62	
	63		–	–	–		●		–	–	–		64	
	65		–	–	–			●	–	–	–		66	
	67		–	–	–	●			–	–	–		68	
	69		–	–	–		●		–	–	–		70	
	71		–	–	–			●	–	–	–		72	

LOAD 'A'	LOAD 'B'	LOAD 'C'
145,833	145,833	145,833

PRAIRIE ARCHITECTS INC.
Creating Sustainable Futures
300 - 141 Bannatyne Ave., Winnipeg, MB, R3B 0R3
telephone 204.956.0938 fax 204.943.5597
web www.prairiearchitects.ca

KGS GROUP CONSULTING ENGINEERS

APEGM Certificate of Authorization KGS Group No. 245

issue / rev.

#	date	issue notes
0	2016/12/08	ISSUED FOR CONSTRUCTION

professional seals

PROVINCE OF MANITOBA R. LALONDE Member 32345 PROFESSIONAL ENGINEER
DEC-7, 2016

project information

SEVEN OAKS POOL

444 Adsum Drive
Winnipeg, MB
Canada

client

City of Winnipeg
4th Floor - 86 King Street
Winnipeg, MB

drawing information

ELECTRICAL PANEL SCHEDULES AND DETAILS

drawn by: GCN
approved by:
scale: AS NOTED
date issued: 2016.11.23
proj. #: 14-1736-008
rev. #: R-0

SEVEN OAKS POOL RENOVATION & ADDITION
BID OPPORTUNITY NO. 1044-2016

E5
02

This drawing must not be scaled. The contractor shall verify all dimensions and other data on site prior to commencement of work. All discrepancies, errors, and omissions are to be reported to the architect. Drawing and specifications, as instruments of service, are the property of the architect, the copyright in the same being reserved to him. No reproduction may be made without the permission of the architect, and when made, must bear his name. All prints to be returned to the architect on request.

FileName: P:\Projects\2014\14-1736-008\Dwg\Elec\14-1736-008_E5-02.dwg – Tab: E5-02 Plotted By: dderoche 16/12/07 [Wed 2:19pm]

Printed on post-consumer recycled content paper.