



- GENERAL NOTES:**
- GREY LINE WEIGHT DENOTES EXISTING EQUIPMENT.
 - THE EXISTING MECHANICAL ROOM LIGHTING CIRCUITS ARE BACKED-UP BY A STAND-BY NATURAL GAS GENERATOR.
 - THE BUILDING IS CURRENTLY EQUIPPED WITH RED EXIT SIGNS.

- CONSTRUCTION KEYNOTES:**
- PROVIDE NEW EMERGENCY EXIT LIGHTS AS SHOWN AND CONNECT THEM TO THE EXISTING LOCAL EMERGENCY EXIT LIGHTING CIRCUIT.
 - PROVIDE FIRE RATED BACK BOXES FOR THE NEW TYPE 'A' AND 'E1' LUMINAIRES.
 - RECONFIGURE THE EXISTING SURFACE MOUNTED CONDUIT AND WIRING TO SUIT THE NEW SOUTH VESTIBULE WALL.
 - PROVIDE POWER FOR THE NEW TYPE 'A' FIXTURES FROM THE EXISTING LOCAL UNSWITCHED EMERGENCY POWER LIGHTING CIRCUIT.
 - RELOCATE THE HORIZONTAL RANING CONDUITS AND EXTEND WIRING AS REQUIRED TO MAKE ROOM FOR THE NEW DROPPED CEILING.
 - RELOCATE THE EXISTING FIRE ALARM PULL STATIONS AS SHOWN AND PROVIDE A PARTIAL VERIFICATION PER CANULC 5537.
 - RELOCATE THE EXISTING HONEYWELL POWER SUPPLY INCLUDING CONDUIT AND WIRING OUTSIDE THE VESTIBULE ON THE EXISTING STRUCTURAL COLUMN.

- DEMOLITION KEYNOTES:**
- DISCONNECT AND REMOVE THE EXISTING TWO EXIT LIGHTS AND TWO 4' FLUORESCENT STRIPS WHERE THE NEW VESTIBULES ARE BEING BUILT.

- LEGEND:**
- FIRE ALARM PULL STATION
 - HONEYWELL POWER SUPPLY
 - EMERGENCY BOILER SHUTOFF SWITCH
 - EMERGENCY BOILER SHUTOFF PUSH BUTTON
 - EXIT LIGHT
 - 1X' LIGHT FIXTURE

NOTES:

THESE DRAWINGS SHALL NOT BE SCALED.

THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.

THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.

ALL OPENINGS THROUGH THE FIRE SEPARATIONS AS A RESULT OF THE WORK OF THIS CONTRACT ARE TO BE FIRE STOPPED AND SEALED WITH ULC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE AND SMOKE-TIGHT BARRIER.

ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.

THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.

WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN EXISTING AREAS (REFER TO FLOOR PLAN AND ROOM SCHEDULE) THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE PREPARED IN ACCORDANCE TO MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF NEW FLOOR.

WHERE PAINTING OF EXISTING WALLS IS INDICATED ON THE ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY EXISTING WALL COVERING, PATCHED & PREPARED TO ACCEPT NEW MATERIAL, UNLESS OTHERWISE NOTED.

0	ISSUED FOR TENDER	16.11.20
No.	REVISION/DESCRIPTION	BY DATE

SEAL

Nov. 29, 2016

DRAWN: [initials] DATE: 2016.11.15

CHECKED: [initials] DESIGNED: [initials] APPROVED: [initials]

USER APPROVAL

THE CITY OF WINNIPEG
PLANNING, PROPERTY AND
DEVELOPMENT DEPARTMENT
MUNICIPAL ACCOMMODATIONS DIVISION
3-65 GARRY STREET, R3C 4K4

PROJECT
REPLACEMENT OF
DOMESTIC HOT WATER
SYSTEM AT PAN AM POOL
25 POSEIDON BAY

SHEET TITLE
ELECTRICAL
BOILER ROOM VESTIBULE PLAN -
NEW

SCALE AS SHOWN	PROJECT No: 16-0107-026	SHEET No: E05
-------------------	----------------------------	------------------

