



ABBR:

NIC NOT IN CONTRACT
RD ROOF DRAIN

LEGEND:

|| (OS) OVERFLOW SCUPPER

KEYNOTES:

- ◇ 1 28" WIDE MIN.
- ◇ 7 40" WIDE MIN.
- ◇ 2 26" WIDE MIN.
- ◇ 8 50" WIDE MIN.
- ◇ 3 46" WIDE MIN.
- ◇ 9 18" WIDE MIN.
- ◇ 4 36" WIDE MIN.
- ◇ 10 48" WIDE MIN.
- ◇ 5 20" WIDE MIN.
- ◇ 6 28" WIDE MIN.

NOTE: 4' CUT-BACK AT TIE-IN TO EXISTING BUR SHALL ENSURE VB CONTINUITY UNDER NEW WALL CONSTRUCTION & 'SPUDDING' BACK EXISTING AGGREGATE TO ENSURE A WATER-TIGHT TIE-IN. THE EXISTING BUR INSULATION DOES NOT NEED TO BE REMOVED IN THE FULL 4' ZONE AS LONG AS NEW VB TRANSITION IS PROVIDED FOR FUTURE ROOFING. (REF. SOP32, SOP40)

POS. DRAIN BACKSLOPE
 MIN. 4' - 0" WIDE

B21&B21a slope to positive drainage. Min. 2%



**QCA BUILDING
 ENVELOPE LTD.**

PROJECT NAME:	PROVISION OF ROOF REPLACEMENT
CLIENT:	358-2016
eFile:	358-2016-Addendum_2-Drawing_A-4-R1
SCALE:	1/96" = 1'-0"
SHEET NO:	A4