



THE CITY OF WINNIPEG
 PLANNING, PROPERTY AND DEVELOPMENT DEPARTMENT
 MUNICIPAL ACCOMMODATIONS DIVISION

REPLACEMENT OF BOILERS AND POOL WATER HEAT EXCHANGERS AT PAN AM POOL

BID OPPORTUNITY 468-2016

25 POSEIDON BAY
 WINNIPEG, MANITOBA

STRUCTURAL	
DRAWING No.	DRAWING TITLE
468-2016_DRAWING_P1_S01	BOILER ROOM PLAN DEMOLITION / NEW CONCRETE PAD
468-2016_DRAWING_P1_S02	ROOF PART PLAN PLAN & SECTION

MECHANICAL	
DRAWING No.	DRAWING TITLE
468-2016_DRAWING_P1_M01	BOILER ROOM PLAN DEMOLITION
468-2016_DRAWING_P1_M02	SECOND FLOOR PLAN DEMOLITION
468-2016_DRAWING_P1_M03	BOILER ROOM PLAN NEW
468-2016_DRAWING_P1_M04	SECOND FLOOR PLAN NEW
468-2016_DRAWING_P1_M05	MECHANICAL ROOM PLAN DEMOLITION AND NEW
468-2016_DRAWING_P1_M06	SECTIONS AND DETAILS 1
468-2016_DRAWING_P1_M07	SECTIONS AND DETAILS 2
468-2016_DRAWING_P1_M08	PIPING SCHEMATIC
468-2016_DRAWING_P1_M09	CONTROLS SCHEMATIC

ELECTRICAL	
DRAWING No.	DRAWING TITLE
468-2016_DRAWING_P1_E01	SINGLE LINE DIAGRAM BASEMENT DEMOLITION AND NEW
468-2016_DRAWING_P1_E02	BOILER ROOM DEMOLITION
468-2016_DRAWING_P1_E03	ELECTRICAL ROOM DEMOLITION
468-2016_DRAWING_P1_E04	BOILER ROOM NEW
468-2016_DRAWING_P1_E05	ELECTRICAL ROOM NEW
468-2016_DRAWING_P1_E06	DETAILS
468-2016_DRAWING_P1_E07	WIRING SCHEMATIC AND DETAILS
468-2016_DRAWING_P1_E08	MECHANICAL ROOM PLAN DEMOLITION AND NEW

NOTES:

- THESE DRAWINGS SHALL NOT BE SCALED.
- THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.
- THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.
- ALL OPENINGS THROUGH THE FIRE SEPARATIONS AS A RESULT OF THE WORK OF THIS CONTRACT ARE TO BE FIRE STOPPED AND SEALED WITH UL/C APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE AND SMOKE-TIGHT BARRIER. EXISTING OPENINGS THROUGH FIRE SEPARATIONS THAT ARE NOT CURRENTLY FIRE STOPPED TO BE DEALT WITH UNDER SEPARATE CONTRACT.
- ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.
- WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN EXISTING AREAS (REFER TO FLOOR PLAN AND ROOM SCHEDULE) THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED, UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE PREPARED IN ACCORDANCE TO MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF NEW FLOOR.
- WHERE PAINTING OF EXISTING WALLS IS INDICATED ON THE ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY EXISTING WALL COVERING, PATCHED & PREPARED TO ACCEPT NEW MATERIAL, UNLESS OTHERWISE NOTED.

No.	REVISION/DESCRIPTION	BY	DATE
0	ISSUED FOR TENDER		16.05.20

SEAL

DRAWN	ML	CHECKED	DESIGNED	MAP	APPROVED
DATE	2016.04.14	USER	APPROVAL		

THE CITY OF WINNIPEG
 PLANNING, PROPERTY AND DEVELOPMENT DEPARTMENT
 MUNICIPAL ACCOMMODATIONS DIVISION
 3-65 GARRY STREET, R3C 4K4

PROJECT
 REPLACEMENT OF BOILERS AND
 POOL WATER HEAT EXCHANGERS AT
 PAN AM POOL
 25 POSEIDON BAY

SHEET TITLE
 TITLE SHEET

SCALE	PROJECT No:	SHEET No:
AS SHOWN	16-0107-008	P1_G00

