



SCOPE OF WORK	REFERENCE SHEETS
(1) DEMOLISH EXISTING SIDEWALK AND SIDEWALK RETAINING WALL. CONSTRUCT PROPOSED STRUCTURAL PATH AND PATH RETAINING WALL.	20 TO 34
(2) DEMOLISH EXISTING SIDEWALK. CONSTRUCT PROPOSED UNREINFORCED PATH.	13 TO 16
(3) DEMOLISH EXISTING TRAFFIC BARRIER AND MEDIAN SLAB. CONSTRUCT PROPOSED REINFORCED MEDIAN SLAB AND TRAFFIC BARRIER.	39 TO 42
(4) REMOVE AND SALVAGE EXISTING CRASH PROTECTION FOR TRAFFIC BARRIER. PROTECT EXISTING BASE. RE-INSTALL EXISTING CRASH PROTECTION ON EXISTING BASE.	39
(5) REPAIR EXISTING CONCRETE 230 PAVEMENT.	10 TO 12
(6) DEMOLISH FACE AND TOP OF EXISTING UNDERPASS RETAINING WALLS. RESURFACE THE EXISTING UNDERPASS RETAINING WALLS.	20 TO 34
(7) DEMOLISH EXISTING RETAINING WALLS PINNED TO EXISTING ROAD SLAB. INSTALL NEW RETAINING WALLS PINNED TO ROAD SLAB.	20 TO 34
(8) REMOVE AND SALVAGE EXISTING ALL GUARDRAILS. RE-INSTALL EXISTING GUARDRAILS ON REFACED UNDERPASS RETAINING WALLS.	20 TO 34 & 43
(9) DEMOLISH 1500 WIDE EXISTING ROAD SLAB, CURB AND SUB-BASE TO EXPOSE FACE OF RETAINING WALLS. INSTALL 230 ROAD SLAB, CURB AND SUB-BASE.	20 TO 34
(10) PROVIDE PATH AND RETAINING WALLS FOR FUTURE PATH CONNECTION.	FUTURE
(11) DEMOLISH EXISTING SLOPE PAVING AND SALVAGE DRAINAGE GRILLES. CONSTRUCT NEW SLOPE PAVING, RE-INSTALL GRILLES AND RE-STABLISH DRAINAGE.	35 TO 38
(12) EXISTING SIDEWALK TO REMAIN.	

LOCATION APPROVED UNDERGROUND STRUCTURES	
SUPV. U/G STRUCTURES COMMITTEE	DATE
NOTE: LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.	

B.M. ELEV.	
DESIGNED BY	S.Y.
CHECKED BY	B.J.W.
DRAWN BY	V.F.
APPROVED BY	K.S.A.
HOR. SCALE:	AS NOTED
VERTICAL:	RELEASED FOR CONSTRUCTION:
NO. REVISIONS	DATE BY
1	ISSUED FOR ADDENDUM No. 1 16.07.14 D.J.M.
0	ISSUED FOR TENDER 16.07.04 K.A.
1	2016.02.19

**THE CITY OF WINNIPEG**  
PUBLIC WORKS DEPARTMENT  
ENGINEERING DIVISION

**2016 REGIONAL STREET PROGRAM**

ARCHIBALD STREET  
UNDERPASS REHABILITATION  
SCOPE OF WORK

SHEET 17 OF 62

CAD FILE DRAWING NUMBER  
06880s-101-884.dwg

CITY DRAWING NUMBER  
U205-16-17

ENGINEER'S SEAL

CONSULTANT DRAWING NO.  
S-101

**APCGM**  
Certificate of Authorization  
Stantec Consulting Ltd.  
No. 1301

**METRIC**  
WHOLE NUMBERS INDICATE MILLIMETRES  
DECIMALIZED NUMBERS INDICATE METRES  
UNLESS INDICATED OTHERWISE

VA 1571.ecad.ctb, 1/19/2016, 0:00:00, dwg, 2016.02.19, 1:59 PM, S.Y., 2016.02.19, C:\Users\S.Y.\AppData\Local\Temp\1571.ecad.ctb