



582-2016 ADDENDUM #1

LIGHTING UPGRADE – ERIC COY ARENA – 535 OAKDALE DRIVE

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: JULY 12, 2016
BY: KATHY ROBERTS
TELEPHONE NO. 204 470-7380

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 582-2016_Bid_Submission with 582-2016_Addendum_1_Bid_Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B-R1: Items 2, 14, 19 – Change in approximate quantity.

PART D – SUPPLEMENTAL CONDITIONS

- Add: D2.2(a) DISCONNECT, REMOVE AND DISPOSE OF existing pendant, chain-hung, surface and recessed fixtures, and exit fixtures as indicated on Form B:Prices and on Appendix 1 – Lighting Schedule. Work to include removal of fixture in recessed ceiling trenches, and supply and installation of junction box in trench to terminate wiring.
- Delete: D2.2(c)
- Add: D2.2(g) In Skate Sharpening room: Re-wire two existing plug-in light fixtures to be hard wired.
- Add: D2.2(h) Disconnect, remove and dispose of existing wall-mounted ballasts and splitter boxes associated with existing mercury fixtures over ice surface. Supply and install a junction box in each location to terminate wiring (total of 4 locations).
- Add: D2.2(i) Relocate 2 ceiling-mounted exit fixtures approx. 2 feet back towards their respective doors.
- Add: D2.2(j) Add one additional exit fixture at south exit door in Ice Shed, and provide conduit and/or cabling and wire as needed.
- Add: D2.6 Height of Fixtures Over Ice Surface: For each row of 5 fixtures, the approximate distances from the concrete to bottom of pendant arm are: 21'-6", 26'-0", 29'-3", 26'-0" and 22'-8".
- Revise: D13.4 to read: The City intends to award this Contract by July 21, 2016.
- Revise: D14.1(a) to read: **Critical Stage #1 – All Work in Ice Shed** – All Work in the Ice Shed shall be completed by August 14. As of end of day on August 14, all new fixtures shall be fully operational, all Work in the area shall be complete, and all tools, materials, equipment and garbage must be removed from the area.

Revise: D17.1(a) to read: Critical Stage #1 – All Work in the Ice Shed – one thousand dollars (\$1,000);

Page numbering on some forms may be changed as a result.

PART E – SPECIFICATIONS

Revise: E2.2 to read: There are known Asbestos Containing Materials (ACM) in the Work Area (see Appendix 2 – Asbestos Inventory). The following Work directly impact the ACM, and shall be performed by the City:

- (a) Removal of any items mounted to the concrete block walls in the Ice Shed;
- (b) Installation of any items to be attached to the concrete block walls in the Ice Shed.

APPENDICES

Replace: 582-2016_Appendix_1 with 582-2016_Addendum_1_Appendix_1-R1