Crescent Drive Park 4 Season Recreation Building Section 22 05 00 781 Crescent Dr. Mechanical Specification MCW/AGE #10399 Page 1 of 11

1. GENERAL REQUIREMENTS 21 00 05

- 1. Comply with all requirements of Contract Administrator's specification.
- This section applies to and is part of all sections of Division 22, 23, and 25. Every section of these specifications applies equally to all sections.
- Total Bid Price to include price to include all necessary equipment, parts, labour and plant to complete the Work shown on the drawings and described in the specifications and to ensure complete and operational mechanical systems.
- Drawings are diagrammatic and approximately to scale. Do not scale them. For exact dimensions refer to
- Drawings and specifications establish scope of work only and are not detailed installation instructions. Follow manufacturer's recommendations and adhere to all applicable Codes, Standards, Regulations and Bylaws, hereafter referred to as Codes.
- Connect to equipment specified in other sections, installed by other Contractors or the City.
- The Contract Administrator shall have the final say in matters of interpretation.
- Use only new materials under this contract unless otherwise noted. New materials shall be free of Asbestos Containing Materials (ACM).
- Apply for and pay for all required permits, licenses, inspections and fees. Indicate building and mechanical permit numbers on all progress draws. Where no permit was applied for indicate same on progress draw.
- 10. In the event of conflict between contract documents and Codes, the more stringent requirement shall be adhered to at no additional cost.
- 11. All work shall be executed with good workmanship, and be guaranteed for one year from substantial
- Only skilled and qualified licensed tradesmen shall perform the work. Tradesmen to provide proof of registered status as requested.
- Install mechanical systems in a workmanlike manner, neat in appearance and to function properly to the
- Supply access doors, provide rated doors to match fire rating, at all service points for mechanical equipment. Indicate on "as-built drawings" the location of all access doors.
- The Mechanical Subcontractor is responsible to carefully examine conditions at the intended place of Work. Verify all services, connection points, and all access openings to permit installation of new
- Mechanical Subcontractor shall submit shop drawings for review by the Contract Administrator prior to commencing Work. Shop drawings shall be specific to the equipment and materials for this project. Changes to location and arrangement shall be reviewed prior to installation. Review of shop drawings by the Contract Administrator is for the sole purpose of ascertaining conformance to design intent. The Mechanical Subcontractor retains responsibility for all aspects of installation, performance and coordination.

Crescent Drive Park 4 Season Recreation Building Section 22 05 00 Mechanical Specification 781 Crescent Dr. MCW/AGE #10399 Page 2 of 11

17. Shop Drawing Procedures are as follows:

General:

- 1. Submittal routing shall be established at the beginning of each project.
- 2. Generally, submittals shall be forwarded as follows: Sub-Trade to Contractor/Contractor to Contract Administrator.
- 3. A transmittal listing each item of equipment shall accompany each submission. 4. Contractor and Mechanical or Electrical Subcontractor must review, approve and stamp submittals prior to sending to Contract Administrator for review. Submittals
- without Contractor stamps will not be reviewed. 5. Equipment must be labeled appropriately. Each item of equipment must bear the
- identifier used on the drawings, i.e. EF-1, RTU-3, etc. 6. Data sheets must clearly indicate model and options being utilized. All information that
- does not apply must be crossed off.
- 7. Allow for Contract Administrator to take ten (10) working days to respond to all
- 8. Where products have applied for and received equal approvals, proof of this shall be
- submitted with shop drawings. Electronic Submissions (.pdf only):
 - 1. Send electronic shop drawing submittals to wpg.shopdrawings@mcw.com only,
- please do not copy staff members directly.
- Hard Copy Submissions: 1. A minimum of four (4) hard copies must be provided: MCW will retain one (1) copy, provide additional copies when requested.
- Mechanical Subcontractor shall maintain accurate "as-built" drawings on site and shall present for review at each Site review. Submit these record drawings in AutoCAD 2010 or newer format for review at the completion of the project. Note that changes to floor plans must be included. (A minimum of \$1,000.00 per drawing shall be held-back until all drawings are submitted and deemed complete.) The Contract Administrator will not perform final inspections nor certify for occupancy until the "as-built" drawings have been received, reviewed and accepted. After acceptance of "as-built" drawings by the Contract Administrator, provide one (1) complete set on CD-ROM and three (3) sets of prints.
- Contract Administrator can complete the as-built drawings from contractor's red-lined markups for a fee of \$250.00 per drawing, with a project minimum of \$1,000.00.
- Engineering Site Reviews: Contractor's work shall be periodically reviewed by the Contract Administrator for determining general quality of installation. Guidance will be offered as to interpretation of contract documents and to assist in performing the mechanical installation. Inspections, reviews and directives issued in no way relieve the Contractor, his agents, employees or subtrades from contractual obligations, conformance to codes or safe and recognized practices.
- Operating and Maintenance Manuals: At the completion of work submit three (3) hard covered loose leaf binders showing all major components divided by trade sections. Manuals shall be complete with all instructions for operation, maintenance and replacement parts as required. Include performance curves, detailed drawings, part lists, supplier information and any other pertinent data. Include copies of reviewed shop drawings, Contract Administrator contact information, Contractor and Sub-contractor information. Include copies of valve tag lists, all inspection certificates, and balancing reports. The Contract Administrator will not perform final inspections nor certify for occupancy until the O&M Manuals are received, reviewed and approved.
 - 1. Provide manufacturers start-up reports and letters of certification that the following equipment and systems are started, commissioned and working correctly:
 - Controls
 - 2. Air moving equipment
 - 3. Heat recovery ventilators

Crescent Drive Park 4 Season Recreation Building 781 Crescent Dr. MCW/AGE #10399

4. Plumbing fixtures, mixing valves and brass.

Water Treatment

Provide one (1) set of special tools required to service equipment as recommended by manufacturer. Provide a receipt signed by the City's representative for each tool in each copy of the O&M Manual.

Section 22 05 00

Page 3 of 11

Mechanical Specification

- 23. Provide one (1) set of spare filters for each filter bank.
- Prior to requesting any Substantial Performance site review, all aspects of the mechanical systems shall be complete and operational. Testing and balancing shall be complete along with valve and equipment identification, equipment startups.
- 25. Each of the Contractors shall instruct the City's Operating Staff on the operation, maintenance, and adjustment of equipment and/or system that they have installed or set. Provide sign off sheets for training indicating who was trained and number of hours of training.
- 26. Use of Equipment before occupancy by the City:
 - 1. The Contractor may operate equipment for testing and balancing only. The use of equipment for any other purpose must be approved by the City in writing prior to use.
 - Approval must indicate who is paying for utilities used. Any equipment that is placed in use for any reason prior to the beginning of the guarantee period shall be cleaned and provide with whatever maintenance and repair is required so that its condition is equal to that of new equipment, or it shall be replaced, at no cost to the
- 27. Prior to final inspection or certification provide the following:
 - Fire damper certification Copies of manufacturer's startup or certification reports
 - TAB reports.
 - Training sign off sheets.
 - Receipts or transmittals indicating the City has received all special tools and spare sets of
- Contractor is to review and approve all requests for information (RFI's) from subcontractors and Contractor is to review and approve all mechanical RFI's prior to submittal to ensure information is not already included in contract documents or cannot be reasonably inferred from contract documents.
- Contractor is to review and approve all mechanical change pricing and credits prior to submitting to Contract Administrator, approval to state that the Contractor believes the pricing is fair and reasonable.
- Mechanical change pricing will only be reviewed if it includes a complete breakdown of items of material, labour hours, labour rates and markups. This review period will start when the information indicated above is received.
- Mechanical progress claims will only be reviewed if they provide a complete breakdown by trade and sub trade and list all major equipment complete with costs.
- 2. DEFINITIONS 21 00 07
- 1. The terms, "supply", "install", and "provide" shall mean to supply install, coordinate, and connect to ensure a fully functional mechanical system, tested and complete in every way, unless otherwise noted.
- "Drawings" and "Specifications" are complementary to each other. What is called for by one shall be binding to both. "Contract Documents" refers to both drawings and specifications

Crescent Drive Park 4 Season Recreation Building 781 Crescent Dr. MCW/AGE #10399

Section 22 05 00 Mechanical Specification Page 4 of 11

3. ACCEPTABLE MANUFACTURERS 22 00 10

Standard of Material & Equipment: Where a Manufacturer's name is mentioned, it is for the purpose of setting a standard of quality.

satisfaction of the Contract Administrator.

performance, capacity, appearance and serviceability. Manufacturers shown below are pre-approved if their products are equal in performance to the specified ones, and the products can be used in the preparation of the Bid. Where no approved manufacturer's are provided, provide the exact make specified. Requests for approval must be submitted to the Contract Administrator not less than two full working days prior to the issuance of the last addendum and must be approved in writing by the engineer in an addendum, no exceptions. Approval does not absolve the supplier and Contractor of the obligation to meet <u>all</u> clauses of this specification. Where approved products have different power requirements, controls, weights, dimensions, or features, it is the responsibility of the bidder to include all costs associated with this in their bid.

Description: Plumbing and Drainage Approved List

Acceptable Manufacturers <u>Equipment</u> Hangers and Supports Crane, Grinnell, Myatt **Drainage Specialties** Ancon, Smith, Zurn, Mifab, Watts Shock Absorbers Ancon, Smith, Zurn, PPP, Watts Gauges and Thermometers (swivel) Dresser, Trerice, Weiss, Dwyer Wall Hydrants Ancon, Zurn, Smith, Mifab, Watts Plumbing Fixtures

Kohler, American Standard, Toto, Crane, Sloan Kohler, Delta Commercial, Chicago Faucets, Zurn, Plumbing Brass Moen, Toto, Sloan

Sloan, Delta Commercial, Crane, Kohler, Toto Flush Valves

Thermostatic Mixing Valves Powers, Leonard

Mop Sinks American Standard, Fiat, Stern Williams **Toilet Seats**

Domestic Hot Water Heaters RHEEM, State, A.O. Smith, Bradford White

Olsonite, Beneke, Centoco

Ventilation Approved List

Acceptable Manufacturers <u>Equipment</u> Damper Hardware, Fan Connectors Duro-Dyne, Elgin Fire Dampers NCA, Ruskin, Nailor Industries

Section 22 05 00 Crescent Drive Park 4 Season Recreation Building 781 Crescent Dr. Mechanical Specification MCW/AGE #10399 Page 5 of 11

Acceptable Manufacturers **Equipment** Static Pressure Monitors Dwyer, Trerice A.A.F., Farr, Cambridge, Flanders Inline Centrifugal Fans Greenheck, Penn, Loren Cook, Delhi Diffusers, Registers and Grilles Titus, Price, Nailor Industries, Tuttle and Bailey Backdraft Dampers Tamco, Ruskin, Price, Westvent, Nailor Industries Owens Corning, J-M, Knauf, Ultralite Acoustic Duct Insulation Flexible Ductwork Thermoflex, Wire-mould, Flex Master **Electric Duct Heaters** Thermolec, PM Wright

Controls Approved List

Heat Recovery Ventilators

Acceptable Manufacturers **Equipment** Ruskin, Ventex, Tamco, Greenheck, Westvent **Control Dampers** Damper Motors Honeywell, Belimo, TAC I/A, Johnson Controls

Lifebreath, VenMar, Renewaire, Vanee

PIPING and FITTINGS 22 00 20

- Provide isolation valves at all fixtures, appliances and equipment
- Provide check stops at all mixing valves.

of dielectric unions or brass valves.

- Allow for thermal expansion on all piping systems conveying hot or cold vapour or liquid.
- Provide point of use thermostatic mixing valves set to 43°C (110°F) for lavatories where indicated.
- Tag all major zone and shut off valves with 38mm (1½") diameter brass tags. Index and list valves, insert list in each O&M Manual also frame and mount copy of list in a conspicuous area of the mechanical
- Identify all equipment with black lamacoid tags 100mm x 25mm (4"x1") with white lettering. Mechanically affix tags to equipment. Equipment names and number to match those listed on contract documents.
- Identify all piping with stenciled lettering and directional arrows at intervals no greater than 6m (20') and at every change in direction. Labeling and identification to either the City's standard or the CSA standard. Confirm system with the City prior to Bid.

Wherever pipes of dis-similar metals are joined the piping systems shall be protected and isolated by use

Provide and install union or flange connections at all equipment and devices to allow for ease of service or future replacement.

Crescent Drive Park 4 Season Recreation Building 781 Crescent Dr. MCW/AGE #10399

Section 22 05 00 Mechanical Specification Page 6 of 11

Cast iron and copper. PVC DWV as permitted by the

Type L copper with wrought copper fittings and lead

the 2010 NPC. PEX as permitted by the 2010 NPC.

free solder; CPVC Dr11 Pipe and fittings as permitted by

10.

Sanitary Drainage - Above

Domestic Hot & Cold Water:

Building Water Services:

Sanitary Drainage - Buried:

Soft copper Type K, PVC or HDPE to approval of authorities having jurisdiction PVC DWV as permitted by the 2010 NPC. PVC Sewer Pipe as permitted by the 2010 NPC.

11.

Isolate all serviceable equipment, using ball and butterfly valves where possible.

- All valves shall have a minimum certified rating of 150 psi.
- All drain valves shall be complete with cap and chain. Install ¼ turn ball valves prior to all pressure gauge devices.
- PVC ball valves, double backing with union ends, solvent weld, pressure rated at 230 psi (1580kPa) at 79°F (23°C).

12. Hangers and Supports:

- All hangers shall be of same material as piping system, or shall be isolated from the pipe. Provide adjustable clevis hangers equal to pipe size and of same material as piping system. Provide oversized hangers on all cold water piping conveying liquid less than 21°C (70°F).
- Use only factory made inserts, coach screw rods, c-clamps, beam clamps and expansion shields rated for the intended load.
- "Caddy" clip or tension clip rod supports are not allowed on this project. Duct hangers shall be rod or strap 2 gauges heavier than duct.
- Provide and install sleeves of suitable material where piping and duct systems pass through any and all separations.
- and place so that ease of reading is ensured. Pressure and temperature ranges shall be suitable for the

receptacle. Confirm locations with Contract Administrator prior to installation.

systems are not acceptable on this project.

substantial completion and include in O&M Manuals.

- 15. Primer paint all miscellaneous metal supports channels and angle iron prior to installation. Pipe all water discharge from relief valves and equipment drains to nearest floor drain or suitable
- Install all valves, strainers, equipment, specialties, filters and the like to permit ease of operation and full

Supply and install thermostats and gauges at all major pieces of equipment and where indicated on the

drawings. (Note PSN-B Snubbers required at all gauges.) Mount all gauges and thermostats vertically

- Acceptable joining systems include mechanical joints (sanitary) soldering, silver soldering, threaded joints, welding, grooved Victaulic (black) and grooved copper Victaulic. NOTE: Tee drilling and Press-fit
- 19. Test all systems to 1½ times working pressure for a minimum of two hours. All tests shall be recorded and independently witnessed. Submit recorded data for Contract Administrator's review prior to
- Metal to PVC thread connections shall be stainless steel reinforced SCH 80, PVC female adaptors.

City of Winnipeg Crescent Drive Park


Revision Notes No. Date 0 2016/02/29 Issued for Construction Re-Issued for Construction 1 2016/09/08

Consulting Professional Engineers 210-1821 Wellington Avenue

Winnipeg, Manitoba, R3H 0G4 Phone - (204) 779-7900 Fax - (204) 779-1119 E-Mail: mcw_wpg@mcw.com

Certificate of Authorization MCW/AGE Consulting Professional Engineers No. 589 Expiry: April 30, 2016

IIS IS A PRINT OF A DOCUMENT THAT HAS BEEN ELECTRONICALLY AUTHENTICATED WIT TECHNOLOGY AUTHORIZED BY THE APEGM. THE ORIGINAL IS IN ELECTRONIC FORM.



This drawing must not be scaled. The contractors shall verify all dimensions and other data on site prior to commencement of work. Discrepancies, errors, and omissions are to be reported to the Architect prior to

roceeding with the Work. Drawings and specifications as instruments of service are the property of the Architect; the copyright in the same being reserved to him. No reproduction or revision to these drawings may be made without the permission of the Architect and when made, must bear his name. All prints to

be returned to the Architect upon request.

Crescent Drive Park Pavilion

MECHANICAL SPECIFICATION

Drawn By Reviewed By CD

Sept 2016

As Noted

Project No.