DRAWING INDEX

SHEET NUMBER	CITY OF WINNIPEG DRAWING NUMBER	DRAWING TITLE
1	D-14403	DRAWING INDEX, DESIGN NOTES, LEGEND, & ABBREVIATIONS
2	D-14404	FIFTH AVENUE - ST MARYS ROAD TO 133 E OF ST MARYS ROAD
3	D-14405	FIFTH AVENUE - 133 E OF ST MARYS ROAD TO 3 E OF DES MEURONS STREET
4	D-14406	FIFTH AVENUE - 3 E OF DES MEURONS STREET TO 150 E OF DES MEURONS STREET
5	D-14407	FIFTH AVENUE - 150 E OF DES MEURONS STREET TO YOUVILLE STREET
6	D-14408	PEPPERLOAF CRESCENT - RANNOCK AVENUE TO ROBINDALE ROAD
7	D-14409	PEPPERLOAF CRESCENT - DUNELM LANE TO 142 N OF DUNELM LANE
8	D-14410	PEPPERLOAF CRESCENT - 142 N OF DUNELM LANE TO BOWHILL LANE

ABBREVIATIONS

WWS	WASTE WATER SEWER
CS	COMBINED SEWER
LDS	LAND DRAINAGE SEWER
℄	PROPERTY LINE
℄	CENTER LINE
G.I.S.	GEOGRAPHIC INFORMATION SYSTEM
B.M.	BENCH MARK
TH	TEST HOLE
ELEV	ELEVATION
INV	INVERT
MIN	MINIMUM
MAX	MAXIMUM
SL	STREET LIGHTING
TS	TRAFFIC SIGNALS
ABAND	ABANDONED
BLDG	BUILDING
HSE	HOUSE
CRN	CORNER
OPP	OPPOSITE
C/S OR S/C	CURB STOP
MTS	MANITOBA TELEPHONE SYSTEM
R.O.W.	RIGHT-OF-WAY
WM	WATERMAIN
CULV	CULVERT
MH	MANHOLE
CB	CATCH BASIN
CI	CURB INLET
VERT.	VERTICAL
HORZ.	HORIZONTAL
I.B.	IRON BAR
FIBRE	FIBRE OPTIC
TYP	TYPICAL
X-ING	CROSSING
HYD	HYDRANT
EXIST	EXISTING
N	NORTH
E	EAST
S	SOUTH
W	WEST
W/	WITH
C/W	CONSTRUCTED WITH
CONC	CONCRETE
AC	ASBESTOS CEMENT
VC OR CLAY	VITRIFIED CLAY
CI	CAST IRON
DI	DUCTILE IRON
PVC	POLYVINYL CHLORIDE
HDPE	HIGH DENSITY POLYETHYLENE
PCCP	PRESTRESSED CONCRETE CYLINDER PIPE

LEGEND

PLAN VIEW

DESCRIPTION	EXISTING	PROPOSED
WATER PIPE		
FIRE HYDRANT		
VALVE		
CURB STOP		
REDUCER		
COUPLING OR SLIDDER		
CROSS		
BEND - 11.25°, 22.5°, 45°, 90°		
TEE		
VERTICAL BEND		
ANODE		
REPAIR MARKER		
PLUG		
SEWER PIPE		
MANHOLE		
CATCH BASIN		
CURB INLET		
JUNCTION		
℄ DITCH		
CULVERT		
SURVEY BAR		
SURVEY MONUMENT		
TREE - DECIDUOUS		
TREE - CONIFEROUS		
HYDRO		
HYDRO POLE		
LAMP STANDARD		
HYDRO POLE W/STREET LIGHTING		
POLE		
GUY ANCHOR		
M.T.S. POLE		
PEDESTAL OR BOX		
CABINET		
M.T.S., SHAW, OR VIDEON		
TRAFFIC SIGNALS		
TRAFFIC LIGHT STANDARD		
GAS		
STEAM		
FIBRE OPTIC		
FENCE		
EDGE OF PAVEMENT OR GUTTER		
EDGE UNPAVED OR GRAVEL ROAD		
℄		
PROJECTED ℄		
LOT LINE		
SIDEWALK - PATHWAY		
EASEMENT		
EDGE OF BUILDING		
MAILBOX	M	
PARKING METER	P	
TEST HOLE		
TREE LINE OR BUSH		

PROFILE

DESCRIPTION	EXISTING	PROPOSED
WATER PIPE		
HYDRANT TOP		
VALVE		
TEE OR CROSS		
COUPLING OR BEND		
REDUCER		
END OF PIPE		
SEWER PIPE		
UNPAVED GROUND SURFACE		
PAVED GROUND SURFACE - ℄ PIPE		
GUTTER (NORTH AND WEST)		
GUTTER (SOUTH AND EAST)		
℄ DITCH (NORTH AND WEST)		
℄ DITCH (SOUTH AND EAST)		
STRUCTURE		
MANHOLE OR CATCH BASIN		

HATCH PATTERNS

EXISTING	PROPOSED	DESCRIPTION
		EARTH OR GROUND ABOVE PIPE
		SAND OR OTHER FINE MATERIAL
		CONCRETE
		WASHED STONE OR GRANULAR MATERIAL
		INTERLOCKING STONE
		METAL
		GRAVEL OR STONE

CONSTRUCTION NOTES

1. EXPOSE EXISTING WATERMAIN & CONFIRM INVERTS PRIOR TO CONSTRUCTION.
2. LOCATION OF ALL SERVICES TO BE CONFIRMED IN THE FIELD.
3. INSTALL WATERMAIN BY TRENCHLESS METHODS.
4. TRENCHES AND EXCAVATIONS WITHIN 1 METRE OF A PAVED AREA INCLUDING SIDEWALKS SHALL BE CLASS 3 BACKFILL.
5. ALL MATERIALS SHALL CONFORM TO THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.
6. MINIMUM COVER TO TOP OF WATERMAIN SHALL BE 2.4 m.
7. REPLACE ALL EXISTING LEAD SERVICES FROM PROPOSED WATERMAIN TO ℄.
8. NOTIFY ALL AFFECTED RESIDENTS AND BUSINESSES 24 HOURS IN ADVANCE OF ANY WATER SHUTDOWNS OR DISRUPTION OF SERVICE.

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE _____ DATE _____

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M.
ELEV.

NO.	REVISIONS	DATE	BY

DESIGNED BY	ML	CHECKED BY	SC
DRAWN BY	RS	APPROVED BY	KZ
SCALE: HORIZONTAL	1:250	RELEASED FOR CONSTRUCTION	KAS ZUREK
SCALE: VERTICAL	1:50		
DATE	2016 08 09	DATE	2016 07 29

PLOT DATE: 2016 08 09

ENGINEER'S SEAL
ORIGINAL SIGNED BY S.R.J. COURNOYER 16-07-29

CONSULTANT DRAWING NUMBER
-

BID OPPORTUNITY: 697-2016
CONTRACT NUMBER: 12

FILE PATH: R:\DRAWINGS\WATER\RENEWAL\2016 RENEWALS\Extra work\
FILE NAME: CONTRACT 12 - INDEX.dwg

Winnipeg

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

2016 SUPPLEMENTAL WATER MAIN RENEWALS
CONTRACT 12

INDEX PAGE

SHEET 1 OF 8

CITY DRAWING NUMBER
D-14403