



1 NEW BASEMENT POWER PLAN
3/16" = 1'-0"

- NOTE:
- EXISTING WIRING TO BE CONCEALED BEHIND WALL/CEILING.
 - REPLACE ALL EXISTING RECEPTACLE TO TAMPER RESISTANCE, DECORA TYPE.
 - PROVIDE NEW 16A, 120V LINE VOLTAGE THERMOSTAT C/W CLEAR, VENTED, LOCKABLE COVER.
 - REFER TO ARCHITECTURAL DRAWINGS FOR DOOR ACTUATOR LOCATION.
 - WIRE AND CONNECT DOOR ACTUATOR AND ASSOCIATED PUSH BUTTONS. PROVIDE ALL REQUIRED CONDUIT, JUNCTION BOXES, WIRING, ETC. COORDINATE ALL WORK WITH DOOR HARDWARE SUPPLIER. CONFIRM FINAL LOCATION OF BUTTONS WITH ARCHITECTURAL PRIOR TO ROUGH-IN.



APEGM
Certificate of Authorization
HDK Consulting Incorporated
No. 5539 Date: 04/30/2017



Winnipeg
THE CITY OF WINNIPEG PLANNING, PROPERTY AND DEVELOPMENT DEPARTMENT
MUNICIPAL ACCOMMODATIONS DIVISION
4TH FLOOR - 185 KING STREET
R3B 1J1

Project:
St. Vital Library
Project Number: 16054
Bid Opportunity Number: 788-2016
Drawing Title:
NEW BASEMENT POWER PLAN

#	Issue/Revision	Date
1	ISSUED FOR CONSTRUCTION	SEPT 09, 2016
2	ADDENDUM #1	OCT 31, 2016

Sheet No: E-10

This drawing is property of the Architect and cannot be reproduced or used without the consent of the Architect. The contractor is responsible for checking and verifying all levels and dimensions and shall report all discrepancies to the Architect and obtain clarification prior to commencing work.