



1 MAIN FLOOR PLUMBING DEMOLITION LAYOUT
 3/16" = 1'-0"

DRAWING KEYNOTES:

1. EXISTING 2" VENT STACK TO REMAIN.
2. EXISTING WATER CLOSET AND LAVATORY TO BE REMOVED. CAP-OFF WATER SUPPLIES, DRAINS AND VENTS BACK TO MAINS IN CRAWLSPACE AND REMOVE ASSOCIATED PIPES IN BASEMENT AND IN THIS LEVEL. MAKE A GOOD PATCH ON FLOOR AND WALL AS REQUIRED.
3. EXISTING WATER CLOSET AND LAVATORY TO BE REMOVED. CAP-OFF WATER SUPPLIES, DRAINS AND VENTS BACK TO MAINS IN CRAWLSPACE. REMOVE ASSOCIATED PIPES IN BASEMENT AND WALL AS REQUIRED.
4. EXISTING JANITOR SINK TO BE REMOVED. CAP-OFF EXISTING WATER SUPPLIES, DRAIN AND VENTS BACK TO MAINS IN CRAWLSPACE. REMOVE ASSOCIATED PIPE IN BASEMENT AND IN THIS LEVEL. MAKE A GOOD PATCH ON FLOOR AND WALL AS REQUIRED.
5. EXISTING SINK TO BE REMOVED. CAP-OFF EXISTING WATER SUPPLIES, DRAIN AND VENTS BACK TO MAINS IN CRAWLSPACE. REMOVE ASSOCIATED PIPE IN BASEMENT AND IN THIS LEVEL. MAKE A GOOD PATCH ON FLOOR AND WALL AS REQUIRED.
6. REMOVE EXISTING DRINKING FOUNTAIN. CAP ALL CONNECTIONS.

GENERAL NOTES:

1. DO NOT SCALE THIS DRAWING. CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO INSTALLATION AND REPORT ANY DISCREPANCY TO THE CONTRACT ADMINISTRATOR.
2. THE DRAWING ONLY SHOWS A GENERAL SCHEMATIC OF NEW SYSTEMS. ROUTING OF PIPING AND UNITS LOCATIONS SHALL SUIT SITE CONDITIONS AND MAY HAVE TO BE CHANGED TO AVOID CONFLICTS WITH STRUCTURE, DUCTS AND PIPES. WHEN CONFLICT CANNOT BE AVOIDED, THE DUCTWORK SHALL BE MODIFIED AS REQUIRED.
3. CONTRACTOR SHALL INCLUDE FOR AND PROVIDE ALL COORDINATION BETWEEN TRADES AND CONSULTANT ON AND OFF SITE AS REQUIRED FOR INSTALLATION OF MECHANICAL AND ELECTRICAL SYSTEMS, WHERE MINOR REROUTING OF DUCT OR SERVICES IS REQUIRED DUE TO ONSITE CONDITIONS. IT SHALL BE PERFORMED AT NO ADDITIONAL COST.
4. CRAWLS SPACE IS A CONFINED AREA. CONTRACTOR TO CONFIRM ALL EXISTING PLUMBING PIPING IN CRAWL SPACE AND MAKE CONNECTIONS AS REQUIRED.
5. COORDINATE ALL PIPING ROUTING WITH ARCHITECTURAL ELEMENTS. ALLOW FOR CUTTING AND PATCHING WHERE EXISTING WALLS, CEILINGS AND ARCHITECTURAL FEATURES ARE REQUIRED TO BE OPENED FOR PIPING.



Project:
 St. Vital Library
 6 Fermor Ave., Winnipeg, Manitoba
 Project Number: 16004
 Bidding Opportunity Number: 716-2016

Drawing Title:
 MAIN FLOOR PLUMBING DEMOLITION LAYOUT

Issue/Revision Date
 1 ISSUED FOR CONSTRUCTION SEPT 09, 2016

Sheet No: M-2

This drawing is property of the Architect and cannot be reproduced or used without the consent of the Architect. The contractor is responsible for checking and verifying all levels and dimensions and shall report all discrepancies to the Architect and obtain clarification prior to commencing work.