DRAWING INDEX

SHEET NUMBER	CITY OF WINNIPEG DRAWING NUMBER	DRAWING TITLE
1	D-14600	COVER PAGE
2	D-14601	DRAWING INDEX, DESIGN NOTES, LEGEND, & ABBREVIATIONS
3	D-14602	ABBOTSFORD CRESENT (W-LEG) - GREENWOOD AVENUE TO ABBOTSFORD CRESCENT (N. LEG)
4	D-14603	ABBOTSFORD CRESENT (N. LEG) - ABBOTSFORD CRESCENT (W. LEG) TO 150 E OF ABBOTSFORD CRESCENT (W. LEG)
5	D-14604	ABBOTSFORD CRESENT (N. LEG) - 150 E OF ABBOTSFORD CRESCENT (W. LEG) TO IOWA STREET
6	D-14605	IOWA STREET - ABBOTSFORD CRESCENT (N. LEG) TO GREENWOOD AVENUE
7	D-14606	ALPINE AVENUE - 58 E OF SEAGRIM ROAD TO 175 E OF SEAGRIM ROAD
8	D-14607	ALPINE AVENUE - 175 E OF SEAGRIM ROAD TO 198 E OF SEAGRIM ROAD
9	D-14608	EDGEWATER DRIVE - 74 W OF SWEETWATER BAY (W. LEG) TO SWEETWATER BAY (E. LEG)
10	D-14609	PARKVILLE BAY (W. LEG) - PARKVILLE DRIVE TO PARKVILE BAY (S. LEG)
11	D-14610	PARKVILLE BAY (S. LEG) - PARKVILLE BAY (W. LEG) TO 150 E OF PARKVILLE BAY (W. LEG)
12	D-14611	PARKVILLE BAY (S. LEG) - 150 E OF PARKVILLE BAY (W. LEG) TO PARKVILLE BAY (E. LEG)
13	D-14612	PARKVILLE BAY (E. LEG) - PARKVILLE BAY (N. LEG) TO PARKVILLE DRIVE
14	D-14613	PEMBINA HIGHWAY - 241 N OF NEWDALE AVENUE TO 87 N OF NEWDALE AVENUE
15	D-14614	PEMBINA HIGHWAY - 87 N OF NEWDALE AVENUE TO NEWDALE AVENUE
16	D-14705	SOUTH PARK DRIVE - BACKLANE W OF PEMBINA HIGHWAY TO 175 E OF BACKLANE
17	D-14615	VERMILLION ROAD - BEAVERHILL BOULEVARD TO 141 E OF BEAVERHILL BOULEVARD
18	D-14616	VERMILLION ROAD - 141 E OF BEAVERHILL BOULEVARD TO GROVER HILLS LANE

ABBREVIATIONS

WWS	WASTE WATER SEWER
CS	COMBINED SEWER
LDS	LAND DRAINAGE SEWER
℄	PROPERTY LINE
℄	CENTER LINE
G.I.S.	GEOGRAPHIC INFORMATION SYSTEM
B.M.	BENCH MARK
TH	TEST HOLE
ELEV	ELEVATION
INV	INVERT
MIN	MINIMUM
MAX	MAXIMUM
SL	STREET LIGHTING
TS	TRAFFIC SIGNALS
ABAND	ABANDONED
BLDG	BUILDING
HSE	HOUSE
CRN	CORNER
OPP	OPPOSITE
C/S OR S/C	CURB STOP
MTS	MANITOBA TELEPHONE SYSTEM
R.O.W.	RIGHT-OF-WAY
WM	WATERMAIN
CULV	CULVERT
MH	MANHOLE
CB	CATCH BASIN
CI	CURB INLET
VERT.	VERTICAL
HORZ.	HORIZONTAL
I.B.	IRON BAR
FIBRE	FIBRE OPTIC
TYP	TYPICAL
X-ING	CROSSING
HYD	HYDRANT
EXIST	EXISTING
N	NORTH
E	EAST
S	SOUTH
W	WEST
W/	WITH
C/W	CONSTRUCTED WITH
CONC	CONCRETE
AC	ASBESTOS CEMENT
VC OR CLAY	VITRIFIED CLAY
CI	CAST IRON
DI	DUCTILE IRON
PVC	POLYVINYL CHLORIDE
HDPE	HIGH DENSITY POLYETHYLENE
PCCP	PRESTRESSED CONCRETE CYLINDER PIPE

LEGEND

PLAN VIEW

DESCRIPTION	EXISTING	PROPOSED
WATER PIPE		
FIRE HYDRANT		
VALVE		
CURB STOP		
REDUCER		
COUPLING OR SLIDDER		
CROSS		
BEND - 11.25°, 22.5°, 45°, 90°		
TEE		
VERTICAL BEND		
ANODE		
REPAIR MARKER		
PLUG		
SEWER PIPE		
MANHOLE		
CATCH BASIN		
CURB INLET		
JUNCTION		
℄ DITCH		
CULVERT		
SURVEY BAR		
SURVEY MONUMENT		
TREE - DECIDUOUS		
TREE - CONIFEROUS		
HYDRO		
HYDRO POLE		
LAMP STANDARD		
HYDRO POLE W/STREET LIGHTING		
POLE		
GUY ANCHOR		
M.T.S. POLE		
PEDESTAL OR BOX		
CABINET		
M.T.S., SHAW, OR VIDEON		
TRAFFIC SIGNALS		
TRAFFIC LIGHT STANDARD		
GAS		
STEAM		
FIBRE OPTIC		
FENCE		
EDGE OF PAVEMENT OR GUTTER		
EDGE UNPAVED OR GRAVEL ROAD		
℄		
PROJECTED ℄		
LOT LINE		
SIDEWALK - PATHWAY		
EASEMENT		
EDGE OF BUILDING		
MAILBOX		
PARKING METER		
TEST HOLE		
TREE LINE OR BUSH		

PROFILE

DESCRIPTION	EXISTING	PROPOSED
WATER PIPE		
HYDRANT TOP		
VALVE		
TEE OR CROSS		
COUPLING OR BEND		
REDUCER		
END OF PIPE		
SEWER PIPE		
UNPAVED GROUND SURFACE		
PAVED GROUND SURFACE - ℄ PIPE		
GUTTER (NORTH AND WEST)		
GUTTER (SOUTH AND EAST)		
℄ DITCH (NORTH AND WEST)		
℄ DITCH (SOUTH AND EAST)		
STRUCTURE		
MANHOLE OR CATCH BASIN		

HATCH PATTERNS

EXISTING	PROPOSED	DESCRIPTION
		EARTH OR GROUND ABOVE PIPE
		SAND OR OTHER FINE MATERIAL
		CONCRETE
		WASHED STONE OR GRANULAR MATERIAL
		INTERLOCKING STONE
		METAL
		GRAVEL OR STONE

CONSTRUCTION NOTES

1. EXPOSE EXISTING WATERMAIN & CONFIRM INVERTS PRIOR TO CONSTRUCTION.
2. LOCATION OF ALL SERVICES TO BE CONFIRMED IN THE FIELD.
3. INSTALL WATERMAIN BY TRENCHLESS METHODS.
4. TRENCHES AND EXCAVATIONS WITHIN 1 METRE OF A PAVED AREA INCLUDING SIDEWALKS SHALL BE CLASS 3 BACKFILL.
5. ALL MATERIALS SHALL CONFORM TO THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.
6. MINIMUM COVER TO TOP OF WATERMAIN SHALL BE 2.4 m.
7. REPLACE ALL EXISTING LEAD SERVICES FROM PROPOSED WATERMAIN TO ℄.
8. NOTIFY ALL AFFECTED RESIDENTS AND BUSINESSES 24 HOURS IN ADVANCE OF ANY WATER SHUTDOWNS OR DISRUPTION OF SERVICE.

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE _____ DATE _____

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

NO.	REVISIONS	DATE	BY
	B.M. ELEV.		

DESIGNED BY	MJK	CHECKED BY	SC
DRAWN BY	RS	APPROVED BY	KZ
SCALE: HORIZONTAL	1:250	RELEASED FOR CONSTRUCTION	
VERTICAL	1:50	KAS ZUREK	
DATE	2017 05 10	DATE	2017 05 09

PLOT DATE: 2017 05 10

ENGINEER'S SEAL
ORIGINAL SIGNED BY S.J.R. COURNOYER 17/05/09

CONSULTANT DRAWING NUMBER
-

BID OPPORTUNITY: 157-2017
CONTRACT NUMBER: 2

Winnipeg

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

2017 WATER MAIN RENEWALS
CONTRACT 2

INDEX PAGE

SHEET 2 OF 18

CITY DRAWING NUMBER
D-14601

FILE PATH: R:\DRAWINGS\WATER\RENEWAL\2017 RENEWALS\CONTRACT 2\Construction\
FILE NAME: INDEX.dwg