

Part 1 General

1.1 INSTALLATION AND REMOVAL

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.2 HOARDING

- .1 The Contractor must barricade off the area under construction to prevent the general public from improper access to the construction area. Suitable barricades and protection systems include:
 - .1 Erect temporary site enclosures using 38 x 89 mm construction grade lumber framing at 600 mm centres and 1200 x 2400 x 13 mm exterior grade fir plywood to CSA O121. Enclosures to be minimum 2400 mm high.
 - .2 Repair surface coatings and/or finishes which are damaged by temporary hoardings and barricades.
 - .3 Provide adequate signage, fencing, etc. to inform the public of the work being undertaken.
 - .4 Apply plywood panels vertically, flush and butt jointed.
 - .5 Erect and maintain pedestrian walkways including roof and side covers, complete with signs and electrical lighting as required by law.

1.3 DUST TIGHT SCREENS

- .1 Provide dust tight screens to localize dust generating activities, and for protection of workers, finished areas of Work and public.
- .2 Maintain and relocate protection until such work is complete.

1.4 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.5 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

1.6 PROTECTION OF BUILDING FINISHES

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Be responsible for damage incurred due to lack of or improper protection.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION