



PROPOSED MANHOLE SCHEDULE		
REFERENCE	NORTHING	EASTING
MH 038	5529083.161	644209.339
MH 039	5529086.664	644314.280
MH 040	5529090.761	644437.037
MH 041	5528988.593	644440.698
MH 042	5528923.635	644443.026
MH 043	5528991.456	644521.496
MH 044	5528999.109	644538.700
MH 045	5529002.960	644647.862
MH 046	5529005.499	644719.817
MH 047	5529008.690	644810.261

EXISTING MANHOLE SCHEDULE			
REFERENCE	NORTHING	EASTING	ASSET REFERENCE
MH 036	5529079.825	644109.394	S-MH40008633
MH E20	5529087.561	644430.954	S-MH40008709
MH E21	5529001.200	644434.242	S-MH40008711
MH E22	5528910.391	644437.027	S-MH40008259
MH E23	5529008.421	644643.041	S-MH40008726
MH E24	5529010.696	644723.458	S-MH40008735
MH E25	5529013.525	644804.985	S-MH40008737



B.M. ELEV. CONSTRUCTION COMPLETION DATE: YYYY MM DD				ENGINEER'S SEAL 			
		DESIGNED BY: MAF	CHECKED BY: MD	APPROVED BY: <i>[Signature]</i> RELEASED FOR CONSTRUCTION: <i>[Signature]</i>		TRANSCONA SEWER RELIEF WORKS CONTRACT NO. 3	
		DRAWN BY: JBC	APPROVED BY: <i>[Signature]</i>			OVERALL PLAN AND MANHOLE SCHEDULE SHEET 1 OF 2	
		SCALE: HORIZONTAL N.T.S. VERTICAL -	DATE: 10/17/17	CONSULTANT DRAWING NUMBER: C-103		SHEET 3 OF 19 CITY DRAWING NUMBER: LD-8079	
0 ISSUED FOR TENDER 10/17 JBC NO. REVISIONS DATE BY		PLOT DATE: 2017 10 12		BID OPPORTUNITY: 25-2017		FILE PATH: C:\pwworkdir\den001\jortez1\40876766\ C-103.dwg	