



TYPICAL PARAPET CONSTRUCTION:
 8 CEMENT BOARD x 400 WIDE VERT. BATTON STRIPS
 19 x 64 CEMENT FIBRE VERTICAL FURRING
 6 CEMENT BOARD SHEATHING
 100 J-BARS AT TOP & BOTTOM OF FASCIA
 13 PLYWOOD SHEATHING
 92 STEEL STUDS AT 400 O.C.
 13 MINERAL FIBRE BATT INSUL.
 13 PLYWOOD SHEATHING
 2 PLY MOD. BITUMEN ROOF MEMBRANE

TYPICAL FLAT ROOF CONSTRUCTION:
 2 PLY MOD. BITUMEN MEMBRANE (SELF ADHESIVE BASE WITH TORCH ON CAP SHEET)
 100 POLY ISO RIGID INSUL. TOP LAYER
 125 SLOPED RIGID INSUL. BASE LAYER (SLOPED DOWN TO 1:3)
 SELF ADHESIVE V.B. MEMBRANE
 38 STEEL DECK - SEE STRUCT.
 OWS JOISTS - SEE STRUCT.

TYPICAL METAL ROOF CONSTRUCTION:
 22 GA. STANDING SEAM PRE-FINISHED METAL ROOF PANELS CW CONCEALED CLIPS & FASTENERS
 WEATHER RESISTANT BARRIER
 16 CONST. GRADE T&G PLYWOOD
 ENGINEERED 100 GALV. Z-BARS (EACH WAY) AT 1200 O.C. BOTTOM AND 610 O.C. TOP
 2 LAYERS - 100 SEMI-RIGID MINERAL FIBRE INSUL.
 VAPOUR BARRIER MEMBRANE
 38 STEEL ROOF DECK (SEE STRUCT.)

NOTE:
 CITY OF WINNIPEG NOT PERMITTED TO PUT WINDOW COVERINGS ON WINDOWS OR COMBUSTIBLE MATERIALS TO WITHIN 50mm OF GLAZING

No.	DATE	REVISION / ISSUANCE
4	YY.MM.DD	-
3	YY.MM.DD	-
2	YY.MM.DD	-
1	17.08.24	- ISSUED FOR ADDENDUM #1
0	17.06.30	- ISSUED FOR CONSTRUCTION

x | architecture inc.
 130 Fort Street, Suite 103 Winnipeg, Manitoba R3C 1C7 204 318 2010

KILDONAN PARK MAINTENANCE BUILDING

WALL SECTIONS

Project No. 1559
 Date JUNE 30, 2017
A5.1