



NOTES:
 THESE DRAWINGS SHALL NOT BE SCALED.
 THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.
 THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.
 ALL OPENINGS THROUGH FIRE ASSEMBLIES ARE TO BE FIRE STOPPED AND SEALED WITH ULC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE A SMOKE-TIGHT BARRIER.
 ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.

COLUMN SCHEDULE		
MARK	SIZE	BASE PLATE '
C-1	HSS 200x200x9.53	BP-1
C-2	HSS 150x150x13	BP-2
C-2A	HSS 150x150x13	BP-1
C-2B	HSS 150x150x13	BP-3
C-2C	HSS 150x150x13	BP-1 GALVANIZED
C-2D	HSS 150x150x13	SEE DETAIL 13/S3.1 FOR BASE PLATE
C-3	2 - HSS 200x150x9 GALVANIZED SEE DET. 1/S3.2	BP-4 GALVANIZED

SEE SHEET S3.2 FOR BASE PLATE DETAIL

MASONRY WALL SCHEDULE		
MARK	SIZE	REINFORCING
MW-1	200 CONCRETE BLOCK	15M VERTICALS @ 600 O/C
MW-2	400 CONCRETE BLOCK (DOUBLE WYTHE OF 200)	20M VERTICALS @ 200 O/C

REFER TO ARCHITECTURAL DRAWINGS & SPECIFICATIONS FOR MORE INFO
 PROVIDE DOWELS FROM GRADE BEAM TO MATCH WALL REINFORCING WHERE APPLICABLE

No.	REVISION/DESCRIPTION	BY	DATE
0	ISSUED FOR CONSTRUCTION	JAW	MAR 20 2017

SEAL

DRAWN: JAW
 CHECKED: BON
 DESIGNED: BON
 APPROVED: BON
 DATE: 2016.08.25
 USER APPROVAL

THE CITY OF WINNIPEG
 PLANNING, PROPERTY AND DEVELOPMENT DEPARTMENT
 MUNICIPAL ACCOMMODATIONS DIVISION
 3-65 GARRY STREET, R3C 4K4

PROJECT
 BRADY ROAD LANDFILL
 ADMINISTRATION BUILDING DEVELOPMENT FOR BRADY LANDFILL
 1777 BRADY ROAD

SHEET TITLE
 ROOF FRAMING PLAN AND STEEL ELEVATIONS