



**1 MATERIALS & PLANTING PLAN**  
04 SCALE: 1:250

QTY	BOTANICAL / COMMON NAME	SIZE / REMARKS
<b>Deciduous Trees</b>		
32	<i>Acer negundo</i> / Manitoba Maple	Single-stem 65mm cal. 12 major branches in well formed head 1.8m above grade B & B, wire basket. Double stake.
11	<i>Ulmus americana</i> / American Elm	Single-stem 65mm cal. 12 major branches in well formed head 1.8m above grade B & B, wire basket. Double stake.
4	<i>Tilia americana</i> / Basswood	Single-stem 65mm cal. 12 major branches in well formed head 1.8m above grade B & B, wire basket. Double stake.
3	<i>Salix amygdaloides</i> / Peachleaf Willow	Single-stem 65mm cal. 12 major branches in well formed head 1.8m above grade, B & B, wire basket. Double stake.
1	<i>Populus Deltoides</i> / Cottonwood	Single-stem 65mm cal. 12 major branches in well formed head 1.8m above grade, B & B, wire basket. Double stake.
<b>Deciduous Shrubs</b>		
96	<i>Caragana pygmaea</i> / Pygmy Caragana	400-500mm dia. well formed shrub with even growth. Container stock (2 gal pot min.)
<b>Perennials / Vines</b>		
66	<i>Calamagrostis x acutiflora</i> 'Karl Foerster' / Karl Foerster Reed Grass	2 yr. plants from division. No. 1 grade, well developed, vigorous rhizomes (not root bound) (3 gal pot min.)
70	<i>Parthenocissus quinquefolia</i> / Virginia Creeper	2 yr. plants from division. No. 1 grade, well branched, with not less than 3 runner, 18" and up and vigorous, well developed root system. Stake. (6" dia. pot min.)

- GENERAL NOTES**
- ALL UTILITIES ARE SHOWN AS INFORMATION ONLY. CONTRACTOR TO CONFIRM LOCATION OF ALL UTILITIES ON SITE PRIOR TO CONSTRUCTION.
  - CONTRACTOR SHALL PROVIDE QUALIFIED CREW TO LAY OUT LANDSCAPING ELEMENTS. THE CREW SHALL BE EQUIPPED WITH ALL THE NECESSARY EQUIPMENT TO PROVIDE HORIZONTAL AND VERTICAL LAYOUT IN ACCORDANCE WITH THE DRAWINGS AND SPECIFICATIONS.
  - CONTRACTOR TO STAKE OUT LOCATION OF ALL WORKS FOR REVIEW BY CONTRACT ADMINISTRATOR PRIOR TO ANY REMOVALS OR CONSTRUCTION.
  - DURING CONSTRUCTION CONTRACTOR TO PROTECT TO CITY OF WINNIPEG STANDARDS ALL EXISTING BUILDINGS & FEATURES, ABOVE & BELOW GROUND UTILITIES, PAVING, CURBS, SIDEWALKS, FENCING, BOLLARDS AND PLANTING MATERIAL, TO REMAIN. AREAS DAMAGED DURING CONSTRUCTION TO BE REPAIRED IN ACCORDANCE WITH CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS AT NO COST TO THE CITY.
  - ALL WORK TO BE DONE IN ACCORDANCE WITH CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS UNLESS OTHERWISE INDICATED.
  - DECIDUOUS TREES TO BE FIELD LOCATED W/CONTRACT ADMINISTRATOR.

**MATERIALS LEGEND:**

	MOWING BOUNDARY		CIP CONC. SIDEWALK - SEE CIVIL
	APPROX. EXTENT OF TREE PROTECTION ZONE / FENCING		UNIT PAVER INDICATOR STRIP IN CONC. BLOCKOUT
	PROTECT & MAINTAIN EXISTING TREE		LIMESTONE BLOCK RETAINING WALL
	ASPHALT PATH - SEE CIVIL		TOPSOIL (FOR NO-MOW SEEDING BY OTHERS)
	UNIT PAVERS IN CONC. BLOCKOUT - BELVEDERE		SODDING PER CW 3510 & SD-243

Oct 10, 2017 10:54 AM  
 \\ps1\htfc\file\_server\2017\17-042 Tache Promenade\4.2 Construction Drawings\ACAD\17-042\_LAYOUT.dwg -tab:04\_05\_06 Materials & Planting

<b>LOCATIONS APPROVED UNDERGROUND STRUCTURES</b> SIGNED BY: _____ DATE: _____ SUPV U/G STRUCTURES		G.B.M. ELEV.	 200-111 St. Mary's Avenue East Winnipeg, MB R2B 0P5 PH: (204) 541-1907		ENGINEER'S SEAL  CONSULTANT ACAD DWG. NO.	 <b>THE CITY OF WINNIPEG</b> PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION <b>TACHE PROMENADE</b> <b>MATERIALS &amp; PLANTING PLAN</b>	CITY DRAWING NUMBER <b>B250-17-62</b> SHEET 62 OF 70 DRAWING No. REV <b>04 0</b>																			
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING		<table border="1"> <tr> <th>NO.</th> <th>REVISIONS</th> <th>DATE</th> <th>BY</th> </tr> <tr> <td>0</td> <td>ISSUED FOR TENDER</td> <td>17/10/13</td> <td>JH</td> </tr> </table>	NO.	REVISIONS	DATE	BY	0	ISSUED FOR TENDER	17/10/13	JH	<table border="1"> <tr> <td>DESIGNED BY</td> <td>GM</td> <td>CHECKED BY</td> <td>GM</td> </tr> <tr> <td>DRAWN BY</td> <td>JH</td> <td>APPROVED BY</td> <td>GM</td> </tr> <tr> <td>REL. FOR CONSTRUCTION</td> <td colspan="3"></td> </tr> </table>	DESIGNED BY	GM	CHECKED BY	GM	DRAWN BY	JH	APPROVED BY	GM	REL. FOR CONSTRUCTION				HOR. SCALE: AS NOTED VERTICAL SCALE: AS NOTED	DATE: 17/10/13	
NO.	REVISIONS	DATE	BY																							
0	ISSUED FOR TENDER	17/10/13	JH																							
DESIGNED BY	GM	CHECKED BY	GM																							
DRAWN BY	JH	APPROVED BY	GM																							
REL. FOR CONSTRUCTION																										

BID OPPORTUNITY No. 754-2017