

I	LOCATION OF UNDERGROUND STRUCTURES A
	SHOWN ARE BASED ON THE BEST INFORMATIC
	AVAILABLE. BUT NO GUARANTEE IS GIVE
	THAT ALL EXISTING UTILITIES ARE SHOWN C
_	THAT THE GIVEN LOCATIONS ARE EXAC
	CONFIRMATION OF EXISTENCE AND EXAC
	LOCATION OF ALL SERVICES MUST B
	OBTAINED FROM THE INDIVIDUAL UTILITIE
	BEFORE PROCEEDING WITH CONSTRUCTION

CONSTRUCTION NOTES

- 1. LEGAL PLAN AND UNDERGROUND INFORMATION FROM CITY OF WINNIPEG LBIS. CONTRACTOR TO VERIFY ALL UNDERGROUNDS IN THE FIELD.
- 2. ISOLATE MISCELLANEOUS ITEMS IN NEW CONCRETE WORKS AS PER SD-228C.
- 3. CONTRACTOR TO TAKE PRECAUTIONARY STEPS TO AVOID DAMAGE FROM CONSTRUCTION ACTIVITIES TO TREES WITHIN THE LIMIT OF CONSTRUCTION.
- 4. CONTRACTOR TO TAKE PRECAUTIONARY STEPS TO CONTROL EROSION BY USING STRAW WATTLES, AS REQUIRED.
- 5. LOCATION OF ALL EXISTING SERVICES TO BE CONFIRMED IN THE FIELD BY CONTRACTOR.
- 6. CONTRACTOR SHALL CONFIRM EXISTING LEAD INVERT ELEVATIONS PRIOR TO INSTALLATION.
- 7. ADJUST MH AND CB RIMS TO NEW GRADES. 8. REFER TO LAND DRAINAGE DRAWINGS FOR ADDITIONAL UNDERGROUND INFORMATION REGARDING MANHOLES, CATCH BASINS, CULVERT ELEVATIONS, AND OUTLET DETAILS.
- 9. REFER TO LANDSCAPE DRAWINGS FOR DETAILS ON ISLANDS, AND ADDITIONAL SURFACE WORK DETAILS.
- 10. OPEN CUT TRENCH THROUGH PROPOSED PRIMARY DIKE TO BE BACKFILLED UNDER GUIDANCE OF A GEOTECHNICAL ENGINEER.

METRIC

WHOLE NUMBERS INDICATE MILLIMETRES DECIMALIZED NUMBERS INDICATE METRES

WARNING

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:

- 1. NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.
- 2. TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS SEE PROVINCIAL REGULATION 210/72 FOR DETAILS.
- 3. OBTAIN EXCAVATION PERMITS PRIOR TO CONSTRUCTION.

Certificate of Authorization **Dillon Consulting Limited (MB)** No. 1789 Date: 18/02/09

ALCOPT.	Winnipeg THE CITY OF W	
SINCINEER	FERMOR AVENUE BRIDGE OVER SEINE RIVER BRIDGE REHABILITATION, PEDESTRIAN-CYCLIST UNDERPASS STRUCTURE	CITY DRAWING NUMBER P-3489-2017-CT-050 SHEET OF
	AND ROADWORKS FROM ST. ANNE'S ROAD TO ARCHIBALD STREET	050 067
T NUMBER	PEDESTRIAN UNDERPASS - STA.	CONSULTANT DRAWING NUMBER
	0+115 TO STA. 0+240 (PLAN-PROFILE)	CT-050