
Part 1 General

1.1 INSTALLATION AND REMOVAL

- .1 Provide construction facilities in order to execute Work expeditiously.
- .2 Remove from Site all such Work after use.

1.2 SCAFFOLDING

- .1 Provide and maintain scaffolding, ramps, ladders, and platforms.

1.3 SITE STORAGE/LOADING

- .1 Confine Work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products. Store materials in areas designated by Contract Administrator.
- .2 Do not load or permit to load any part of Work with a weight or force that will endanger the Work.
- .3 Restrict equipment, Work, Workers and storage of construction materials, tools, equipment, etc. to designated areas and established routes to and from Work areas. Confirm designated areas and routes with Contract Administrator.

1.4 CONSTRUCTION PARKING

- .1 Parking will be permitted on Site. Contractor to submit parking and Site use plan to Contract Administrator for approval.

1.5 EQUIPMENT, TOOL AND MATERIALS STORAGE

- .1 Provide and maintain, in a clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
- .2 Locate materials not required to be stored in weatherproof sheds on Site in a manner to cause least interference with Work activities.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION