

Part 1 General

1.1 PROJECT CLEANLINESS

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris.
- .2 Remove waste materials from site at regularly scheduled times or dispose of as directed by Contract Administrator. Do not burn waste materials on site.
- .3 Make arrangements with and obtain permits from Authorities Having Jurisdiction for disposal of waste and debris.
- .4 Provide on-site containers for collection of recyclable materials, waste materials and debris.
 - .1 Separate wood fibre waste materials, paper product waste materials, recyclable plastics and metal cut-offs into separate recycling collection bins.
 - .2 Locate containers in areas designated by Contract Administrator.
- .5 Remove waste material and debris from site at end of each working day.
- .6 Dispose of waste materials and debris off site.
- .7 Clean interior areas prior to start of finish work, and maintain areas free of dust and other contaminants during finishing operations.
- .8 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .9 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.
- .10 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.
- .11 Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly painted surfaces nor contaminate building systems.

1.2 FINAL CLEANING

- .1 When Work is Substantially Performed, remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2 Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.
- .3 Prior to final review, remove surplus products, tools, construction machinery and equipment.
- .4 Remove waste products and debris other than that caused by Client.
- .5 Remove waste materials from site at regularly scheduled times or dispose of as directed by Contract Administrator. Do not burn waste materials on site.

- .6 Make arrangements with and obtain permits from Authorities Having Jurisdiction for disposal of waste and debris.
- .7 Clean and polish glass, mirrors, hardware, wall tile, stainless steel, chrome, porcelain enamel, baked enamel, plastic laminate, and mechanical and electrical fixtures. Replace broken, scratched or disfigured glass.
- .8 Remove stains, spots, marks and dirt from decorative work, electrical and mechanical fixtures, furniture fitments, walls, and floors.
- .9 Clean lighting reflectors, lenses, and other lighting surfaces.
- .10 Vacuum clean and dust building interiors, behind grilles, louvers and screens.
- .11 Inspect finishes, fitments and equipment and ensure specified workmanship and operation.
- .12 Broom clean and wash exterior walks, steps and surfaces; rake clean other surfaces of grounds.
- .13 Remove dirt and other disfiguration from exterior surfaces.
- .14 Sweep and wash clean paved areas.
- .15 Clean equipment and fixtures to a sanitary condition; clean or replace filters of mechanical equipment.
- .16 Remove debris and surplus materials from crawl areas and other accessible concealed spaces.

END OF SECTION