



1042-2018 ADDENDUM 1

2019 OUTFALL RENEWAL AND REHABILITATION

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: November 29, 2018
BY: Ray Offman
TELEPHONE NO. 204 896-1209

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

Revise: E1.3 to read: The following are applicable to the Work:

<u>Drawing No.</u>	<u>Drawing Name/Title</u>
LD-8857	Cover Sheet
LD-8858	Index Page
LD-8859-R1	Red River Boulevard Outfall
LD-8860	Henderson Highway Outfall
LD-8861-R1	Gateway Road Outfall
LD-8862	St Charles Street Outfall
LD-8863-R1	Valley View Drive Outfall (Abandonment)
LD-8864	Valley View Drive Storm Sewer
LD-8865-R1	Valley View Drive Outfall (New)
LD-8866-R1	Jae Eadie Park Outfall
LD-8867	North Drive Outfall
LD-8868	Hindley Avenue Outfall
LD-8869	Bishop Grandin Outfall
LD-8870-R1	Pembina Highway Outfall
LD-8871	Miscellaneous Details – Sheet 1 of 2
LD-8872	Miscellaneous Details – Sheet 2 of 2

Revise: E11.1.1 to read: This Specification shall cover all aspects of the Site Development and Restoration Work, including but not limited to mobilization and demobilization, erection, maintenance and removal of safety fencing, swamp mats as required for access, traffic control and signage, sediment control Works, snow clearing, flow control, **temporary cofferdams as required regardless of if they are specified on the drawings or not**, protection and pruning as required of existing trees, removal of fallen trees and debris, removal and reinstallation of site furniture, office facilities, general access development, access maintenance and removal, and Site Restoration.

Revise: E15.2.1 to read: The rockfill material for use as riprap shall consist of a clean free draining, sound, dense, durable rock. The Contractor shall supply quarried limestone for all sites, **with the exception of Pembina Highway Outfall where 100 mm to 300 mm field stone shall be supplied.**

- Add: E15.7.3 The supply and placement of field stone shall be measured on a weight basis and paid for at the Contract Unit Price for "Riverstone Rockfill Riprap". The weight to be paid for shall be the total number of metric tonnes of field stone supplied and placed in accordance with this Specification, as measured by a certified weigh scale and accepted by the Contract Administrator.
- Revise: E16.2.13(b) to read: Coupling Systems for the pipe are to be Armtex Polymer Coated Trenchcoat H500 Huggler Band Couplers complete with O-ring Elastomeric Gaskets, or approved equivalent in accordance with B7.
- Delete: E16.3.10
- Add: E31.2.4: The Contractor shall have a qualified technician refurbish the existing flap gate. Refurbishment shall include sandblasting and painting. Proposed refurbishment service method shall be submitted and approved by the Contract Administrator prior to the Work.
- Revise: E31.3.2 to read: All costs associated with the removal and re-installation of existing flap gate, which includes refurbishment and all installation works, will be considered incidental to the Work.
- Revise: E32.2.1 to read: The Contractor shall submit shop drawings for all hand rail materials prior to construction.
- Revise: E32.2.2 to read: The Contractor shall remove and install the hand rail as specified on the Drawings.
- Revise: E32.3.1 to read: The removal, supply, and installation of the hand rail shall be measured on a length basis and paid for at the Contract Unit Price per lineal meter for "Removal and Installation of Hand Rail". The length to be paid for shall be the total number of meters removed, supplied, and installed in accordance with this Specification, accepted and measured by the Contract Administrator. Payment of hand rail shall be in accordance with the following payment schedule:
- (a) Forty percent (40%) of the Contract Unit Price per lineal meter for "Removal and Installation of Hand Rail" shall be paid following removal.
 - (b) Sixty percent (60%) of the Contract Unit Price per lineal meter for "Removal and Installation of Hand Rail" shall be paid following supply and final installation.

DRAWINGS

- Replace: 1042-2018_Drawing_LD8859 with 1042-2018_Addendum_1-Drawing_LD8859-R1
- 1042-2018_Drawing_LD8861 with 1042-2018_Addendum_1-Drawing_LD8861-R1
- 1042-2018_Drawing_LD8863 with 1042-2018_Addendum_1-Drawing_LD8863-R1
- 1042-2018_Drawing_LD8865 with 1042-2018_Addendum_1-Drawing_LD8865-R1
- 1042-2018_Drawing_LD8866 with 1042-2018_Addendum_1-Drawing_LD8866-R1
- 1042-2018_Drawing_LD8870 with 1042-2018_Addendum_1-Drawing_LD8870-R1