



314-2018 ADDENDUM #1

KILDONAN PARK GOLF COURSE – DRAINAGE RENOVATIONS

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: May 9, 2018
BY: Kathy Roberts
TELEPHONE NO. 204 470-7380

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 314-2018_Bid_Submission with 314-2018_Addendum_1_Bid_Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Revise Item No. 10 description

PART E – SPECIFICATIONS

Revise: E1.3 to read: The following are applicable to the Work:

<u>Specification No.</u>	<u>Specification Title</u>
01001	Table of Contents
01560	General Requirements
02210	Environmental Protection
02260	Site Grading
02512	Topsoil & Finish Grading
02710	Cart Paths
02938	Subgrade Drainage
02952	Sodding
02954	Tee Construction
03330	Bunker Construction
	Retaining Wall

<u>Drawing No.</u>	<u>Drawing Name/Title</u>
SA1	Site Access for 2018 Projects – Kildonan Park Golf Course
L1-R1	Construction Layout Plan – Tee Nos. 2, 11, 15
L2	Construction Details
L3	Construction Details

DRAWINGS

Replace: 314-2018_Drawing_L1 with 314-2018_Addendum_1_Drawing_L1-R1

NMS SPECIFICATIONS

Section 02210 – Site Grading

Revise: 2.1.1 to read: Fill: Utilize native material from excavation, grading or designated off-site borrow sources approved by the Contract Administrator for use intended. Material to be unfrozen and free from: rocks larger than 50 mm (2"), cinders, ashes, sods, refuse, or other deleterious materials. Refer to Drawing L1-R1 for location. Noted below are estimated fill material requirement, to be hauled to each location from central golf course stockpile shown on drawing SA1.

No. 2 Tee	80 cubic meters
No. 15 Tee	30 cubic meters
No. 11 Tee / 10 Green	120 cubic meters

Revise: 3.1.1 to read: Rough grade to grades and contours indicated by the Contract Administrator, allowing for positive surface drainage at all times, and intended surface treatment as indicated on the tee construction detail on Drawing L2.

Section 02954 – Bunker Construction

Revise: 3.3.1 to read: Place sod along bunker edges immediately after topsoil installation in order to prevent erosion of edges and contamination of bunker floor and drain lines. Refer to construction detail on Drawing L3. Water as required.