



- NOTES:**
- REFER TO DRAWING S05 FOR GENERAL NOTES AND SCHEDULES.
 - BASE SLAB TO BE SLAB S-1, TOP OF SLAB EL. 229.570 UNLESS NOTED OTHERWISE.
 - REMOVE ALL TEMPORARY WORKS UPON COMPLETION OF WORK.
 - COORDINATE AND SCHEDULE ALL WORK WITH THE CONTRACT ADMINISTRATOR.
 - COORDINATE INSTALLATION OF UV EQUIPMENT. SUPPLY AND INSTALL 16-M16x150 LONG WEDGE ANCHORS.
 - SUPPLY AND INSTALL CONCRETE BENCHING FOR UV EQUIPMENT. COORDINATE WITH UV EQUIPMENT MANUFACTURER.
 - SEE DRAWING S05 FOR SUGGESTED SEQUENCE OF CONSTRUCTION.
 - EXCAVATE TO REMOVE SOFT SOIL AT THE BOTTOM OF EXISTING EXCAVATION TO SOUND CLAY. FILL WITH LEAN MIX CONCRETE TO U/S OF CONCRETE COLLAR AND NEW CONCRETE BEAM CB4.

FOUNDATION FRAMING PLAN
SCALE: 1:50

THESE RECORD DRAWINGS HAVE BEEN PREPARED, IN PART, ON THE BASIS OF INFORMATION COMPILED AND FURNISHED BY OTHERS. AS A RESULT, THE ENGINEER WILL NOT BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS WHICH HAVE BEEN INCORPORATED INTO THIS DOCUMENT.

REID CROWTHER & PARTNERS LIMITED
WINNIPEG
RECORD DRAWING
DATE: 99/09/24

| | | | | | |
|---------------------|---------------|-------------|----------|-------------------------------|--|
| B.M. ELEV. | | | | | |
| DESIGNED BY | MEB/NHK | CHECKED BY | DGN/DLH | | |
| DRAWN BY | C.T. | APPROVED BY | AL | | |
| 1 RECORD DRAWING | 99/09/24 R.D. | HOR. SCALE: | AS NOTED | RELEASED FOR CONSTRUCTION BY: | |
| 0 ISSUED FOR TENDER | 98/07/27 C.T. | VERTICAL: | | | |
| NO. REVISIONS | DATE | BY | DATE | DATE | |
| | | | 98/04/11 | | |

| | | |
|-------------------------------------|--------------------------------------------------|-----------------------------------------------------------|
| Consulting Engineering Worldwide | ENGINEER'S SEAL | THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT |
| | ORIGINAL SIGNED BY D.G. NICHOLLS 7/22/1998 | |
| CONSULTANT DRAWING NO. 61786.01 S02 | | FOUNDATION PLAN SHEET OF REV-1 |