

- MECHANICAL KEYNOTES**
- ① DISCONNECT AND REMOVE EXISTING FLOOR DRAIN IN POOL DECK COMPLETE W/ STRAINER AND BODY. PROTECT AND COVER OPEN PIPING DURING CONSTRUCTION.
 - ② DISCONNECT AND REMOVE OVERFLOW CHANNEL DRAIN COMPLETE W/ STRAINER AND BODY. REMOVE SECTION OF DRAIN PIPE BACK TO FIRST ELBOW BELOW FLOOR.
 - ③ POOL MAIN DRAIN TO REMAIN. PROTECT DURING CONSTRUCTION. TYPICAL. TIE WATERPROOFING INTO DRAIN BODIES.
 - ④ POOL WATER RETURNS TO REMAIN, PROTECT DURING CONSTRUCTION. TIE WATERPROOFING INTO DRAIN BODIES.
 - ⑤ INSTALL NEW FLOOR DRAIN (FD-1) COMPLETE W/ STRAINER TO ACCOMMODATE NEW DECK TILE. CONNECT TO EXISTING PIPING BELOW FLOOR REFER TO SPECIFICATION COORDINATE W/ ARCHITECTURAL AND CONTRACT ADMINISTRATOR.
 - ⑥ INSTALL NEW DRAIN OVERFLOW CHANNEL (FD-2) COMPLETE W/ NEW PIPING BACK TO EXISTING.
 - ⑦ POOL SKIMMER COVERS TO BE REMOVED AND REPLACED WITH MATCHING.

- LEGEND**
- DENOTES APPROXIMATE EXTENT OF SOFFIT CONCRETE REPAIRS. (UNIT PRICE)
 - FD FLOOR DRAINS (FD-1) TO BE REPLACED - SEE DETAIL 5/S4.1
 - OFD OVER FLOW DRAINS (FD-2) TO BE REPLACED - SEE DETAIL 6/S4.1
 - SK SKIMMER COVERS TO BE REMOVED AND REPLACED
 - RD RETURN DRAINS TO REMAIN

- NOTES:**
1. COMPLETE CONCRETE REPAIRS TO POOL DECK, TANKS, AND PILES.
 2. CONCRETE REPAIR AREAS WILL BE IDENTIFIED ON SITE BY THE CONTRACT ADMINISTRATOR, IN THE PRESENCE OF AND WITH THE ASSISTANCE OF THE CONTRACTOR.
 3. THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMATION OF SHORING REQUIREMENTS WITH THE CONTRACT ADMINISTRATOR PRIOR TO COMMENCEMENT OF DEMOLITION AND THROUGHOUT REPAIR PROCESS.

The General Contractor shall check & verify all dimensions and report any errors or omissions to the designers.

No.	Date	Issue/Revision	By
0	2019-08-07	ISSUED FOR TENDER	DJM

NOTE:
PRELIMINARY
DRAWING
DO NOT USE FOR
CONSTRUCTION



300-275 Carlton Street
Winnipeg, Manitoba R3C 5R6
T 204-943-7501
F 204-943-7507



Crosier Kilgour & Partners Ltd.
CONSULTING STRUCTURAL ENGINEERS


Project
BONIVITAL POOL
POOL DECK AND TANKS RESTORATION
TENDER NO. : 286-2019
1215 ARCHIBALD STREET
WINNIPEG, MANITOBA

Sheet Title
MAIN FLOOR STRUCTURAL FRAMING PLAN

File	2018-1471	Date	2019-08-07
------	-----------	------	------------

Design	DJM	Drawn	MAH
--------	-----	-------	-----

Revision	0	Sheet No.	S2.2
----------	---	-----------	------



MAIN FLOOR STRUCTURAL FRAMING PLAN
1/8" = 1'-0"