


KEYNOTES			
1	NEW BONDED MORTAR BED (DECK, TANK WALLS, TANK BOTTOM) THICKNESS VARIES. MECHANICALLY PROFILE & PREPARE CONCRETE SUBSTRATE TO ICRI-CSP-3 TO 5 PROFILE FOR DECK AND ICRI-CSP-7 FOR TANK WALLS AND FLOOR. SUBSTRATE TO BE SSD AT TIME OF MORTAR BED INSTALLATION.		
2	FOR BOLTED DOWN SPECIALITY ITEMS, SITE CONFIRM EXISTING ANCHORS DIAMETER AND PROVIDE NEW HILTI HIT-RE 500 V3 W/ HILTI-HIS-RN 316 SS INTERNALLY THREADED INSERT AT MATCHING LOCATIONS. ALL ANCHOR LOCATIONS TO BE REVIEWED W/ THE CONTRACT ADMINISTRATOR		

LEGEND	
FD	FLOOR DRAINS ON POOL DECK (EL 99'-11 1/2" TYP) SITE CONFIRM EXISTING DRAIN ELEVATIONS PRIOR TO DEMOLITION. RECORD EXISTING CONDITIONS AND SUBMIT TO CONTRACT ADMINISTRATOR
OFD	OVER FLOW DRAINS
RD	RETURN DRAINS
SK	SKIMMER COVER TO BE REPLACED. SEE ARCH

- NOTES:**
- COMPLETE CONCRETE REPAIRS TO POOL DECK, TANKS, AND FILES.
  - CONCRETE REPAIR AREAS WILL BE IDENTIFIED ON SITE BY THE CONTRACT ADMINISTRATOR, IN THE PRESENCE OF AND WITH THE ASSISTANCE OF THE CONTRACTOR.
  - THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMATION OF SHORING REQUIREMENTS WITH THE CONTRACT ADMINISTRATOR PRIOR TO COMMENCEMENT OF DEMOLITION AND THROUGHOUT REPAIR PROCESS.

NOTE:  
PRELIMINARY  
DRAWING  
DO NOT USE FOR  
CONSTRUCTION

 **MAIN FLOOR PLAN**  
1/8" = 1'-0"



Project  
**BONIVITAL POOL**  
POOL DECK AND TANKS RESTORATION  
TENDER NO. : 286-2019  
1215 ARCHIBALD STREET  
WINNIPEG, MANITOBA

Sheet Title  
**MAIN FLOOR PLAN**

File	2018-1471	Date	2019-08-07
Design	DJM	Drawn	MAH
Revision	0	Sheet No.	S2.3