



GENERAL NOTES

- A. ELECTRICAL SUBCONTRACTOR TO VERIFY ALL EXISTING CIRCUITING ON SITE PRIOR TO DISCONNECTION OF LOADS.
- B. FOR ALL EXISTING ELECTRICAL DEVICES, EQUIPMENT, ETC. THAT ARE TO BE REMOVED, REMOVE EXISTING CONDUIT, WIRING, CONTROL PANEL, MOTOR STARTER, ETC. BACK TO SOURCE UNLESS OTHERWISE NOTED. TURN BREAKER OFF, MARK AS SPARE, UPDATE PANEL DIRECTORY AND LABELING. FOR CONDUITS EMBEDDED IN FLOOR SLAB, REMOVE WIRING, CUT CONDUIT AT FLOOR LEVEL AND SEAL CONDUIT.
- C. EXISTING EQUIPMENT TO BE OFFERED TO THE CITY UPON REMOVAL. DISPOSE OF EQUIPMENT UPON THE CITY'S REQUEST.
- D. COORDINATE WITH THE CITY PRIOR TO SHUT-DOWN OR REMOVAL OF EQUIPMENT.
- E. ALL ABANDONED EQUIPMENT AND SERVICES WITHIN AREA OF WORK SHALL BE REMOVED.
- F. THIS BUILDING MAY CONTAIN ASBESTOS. REFER TO FRONT END SPECIFICATIONS FOR FURTHER INFORMATION.
- G. FIRE STOP ALL PENETRATIONS LEFT BY DEMOLITION OF CABLE/CONDUITS.
- H. THIS BUILDING MAY CONTAIN ASBESTOS. REFER TO FRONT END SPECIFICATIONS FOR FURTHER INFORMATION.

DEMOLITION KEY NOTES

- 1. DISCONNECT EXISTING INFRA RED HEATER TO BE DEMOLISHED BY MECHANICAL. REMOVE CONDUIT, WIRE, ETC. BACK TO SOURCE. PRIOR TO REMOVAL INSPECT AND PERFORM INSULATION RESISTANCE (MEGGER) TEST ON EXISTING WIRING. IF WIRING PASSES TESTING AND INSPECTION, PROVIDE CASH CREDIT FOR WIRE REMOVAL AND NEW WIRING (REFER TO E2.1, KEY NOTE 1). CREDIT TO BE ACCEPTED AT THE DISCRETION OF THE CITY.
- 2. DISCONNECT EXISTING INFRA RED HEATER TO BE DEMOLISHED BY MECHANICAL. REMOVE WIRING, CONDUIT, ETC. BACK TO SOURCE.
- 3. EXISTING ROLL UP DOOR TO BE REMOVED BY MECHANICAL. DISCONNECT DOOR MOTOR AND ASSOCIATED EQUIPMENT (CONTROLLER, TRAFFIC LIGHT, SENSORS, WANDS, ETC). REFER TO MECHANICAL DRAWING M1.1 FOR DETAILS. REMOVE WIRE, CONDUIT, ETC. BACK TO SOURCE.
- 4. EXISTING EXTERIOR ELECTRIC SNOW MELT RADIANT FLOOR LOOP CONTROLLER TO REMAIN.



5			
4			
3			
2			
1			
0	ISSUED FOR CONSTRUCTION	VEK	16/04/19
NO.	Description	BY	DD/MM/YY

ENGINEERS GEOSCIENTISTS
MANITOBA
 Certificate of Authorization
SMS Engineering Ltd.
 No. 166

770 Bradford Street
 Winnipeg, Canada
 T 204 775 0291
 SMSeng.com

Winnipeg Transit

Project Title
**CITY OF WINNIPEG FORT ROUGE
 TRANSIT BASE - RAPID ROLL DOORS
 AND RADIANT HEATERS REPLACEMENT**

WINNIPEG MANITOBA
 Drawing Title
**MAIN FLOOR PLAN - SERVICE
 BAY - DEMOLITION -
 ELECTRICAL**

Drawn By RD	Checked By RD	Approved By VEK
Scale AS SHOWN	Date APRIL 2019	Project No. 19-028-01
Revision Number 0	Drawing Number E1.1	Sheet Order 1 OF 4

1 MAIN FLOOR PLAN SERVICE BAY - DEMOLITION - ELECTRICAL
 SCALE: 1/8" = 1'-0"