

380-2019 ADDENDUM 1

552 PLINGUET STREET REFUELLING STATION PAVEMENT AND EQUIPMENT REHABILITATION

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: May 10, 2019 BY: Thomas Findlay TELEPHONE NO. 204 928-8438

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A - BID SUBMISSION

Replace: 380-2019 Bid Submission with 380-2019 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Add Item A.6 ii).

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, June 4th, 2019.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D14.4 to read: The City intends to award this Contract by June 18th, 2019.

PART E - SPECIFICATIONS

Add: E4.6.3 Existing drainage material removed from Tank Nest Area may be reused as backfill material within the limits of the existing liner. The Contractor shall be responsible for safe storage of the contaminated material. Revise: E9.4.1 to read: Salvaged Drainage Material or Drainage Material to be placed using end dump methods off of existing concrete, ensure material is not dumped directly over underground storage tanks. Spread material by hand and complete compaction using a small vibrator plate compactor to the satisfaction of the Contract Administrator. E9.5 MEASUREMENT AND PAYMENT Add: Supply and Placing Drainage Material and Placing Salvaged Drainage Material shall be measured on a volume basis and paid for at the contract unit price per cubic meter for "Supply and Placing Drainage Material" or "Placing Salvaged Drainage Material". The volume to be paid for will be the total number of cubic meters of Drainage Material placed in accordance with this specification, accepted and measured by the Contract Administrator.