

PETUNIA ST

PEONY AVENUE

109.5 OF 300 CS TO BE LINED  
S-MA00001881



REPLACE RISER 0.0-0.8  
(TO BE DONE BY OTHERS)

S-MH00001615  
RIM 231.46  
INV N 227.79  
INV E 228.01  
INV S 227.72  
INV W 227.74

S-MH00001606  
RIM 231.00  
INV E 228.57  
INV W 228.57

REPLACE RISER 0.0-0.8

SEWER JUNCTION INFORMATION FROM SEWER VIDEO INSPECTION SEWER ID S-MA00001881		
DISTANCE FROM MH ID S-MH00001606		
DISTANCE	DIAMETER	CLOCK
2.0	150	2
6.4	150	11
6.7	150	2
8.3	150	10
18.4	150	10
20.7	150	3
23.1	150	9
24.8	150	10
35.6	150	2
38.1	150	10
51.8	150	2
54.2	150	10
66.6	150	2
69.1	150	2
81.4	150	2
83.9	150	3
97.4	150	10
99.9	150	2
100.1	150	10
101.2	150	10

WARNING


IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:

- 1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.
- 2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.

SEE PROVINCIAL REGULATION 210/72 FOR DETAILS

FOR INDEX SEE  
11988

METRIC  
WHOLE NUMBERS INDICATE MILLIMETRES  
DECIMALIZED NUMBERS INDICATE METRES



LOCATION APPROVED  
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE \_\_\_\_\_ DATE \_\_\_\_\_

NOTE:

LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M. ELEV.			
NO.	REVISIONS	DATE	BY

DESIGNED BY	SC	CHECKED BY	SC
DRAWN BY	AJ	APPROVED BY	KZ
SCALE:	1:750	RELEASED FOR CONSTRUCTION	K.ZUREK
HORIZONTAL		DATE	
VERTICAL	DATE	2019 01 24	DATE

ENGINEER'S SEAL  
ORIGINAL  
SIGNED BY  
S.R.J.  
COURNOYER  
19/01/22  
CONSULTANT DRAWING NUMBER  
-



THE CITY OF WINNIPEG  
WATER AND WASTE DEPARTMENT  
ENGINEERING DIVISION

2018 SEWER MAIN RENEWALS  
BY CIPP LINING  
PEONY AVENUE  
1ST MH E OF PETUNIA STREET TO  
MH AT PETUNIA STREET

SHEET 42 OF 52  
CITY DRAWING NUMBER  
12027

PLOT DATE: 2019 01 24

BID OPPORTUNITY: 58-2019  
CONTRACT NUMBER: 4

FILE PATH: R:\DRAWINGS\SEWER\2018 RENEWALS\RENEWALS & ASSOCIATED WORKS\CONTRACT 4\CONSTRUCTION DWGS\  
FILE NAME: PEONY AVENUE 1ST MH E OF PETUNIA.dwg