Corporate Finance Department

Materials Management Division

Winnipeg

699-2019 ADDENDUM No. 1

**ROOFTOP HEAT RECOVERY VENTILATIOR
REPLACEMENT BONIVITAL POOL – 1215
ARCHIBALD STREET**

ISSUED: September 12, 2019
BY: P. Silva, P.Eng.
TELEPHONE NO.   204 896-1209

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20160708

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions
in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this
Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.**

PART B - BIDDING PROCEDURES

Revise B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, September 20, 2019.

PART E - SPECIFICATIONS

Section 23 05 93   **TESTING, ADJUSTING AND BALANCING FOR HVAC:**

Delete: 1.2.1.1.2   Balancing all supply and return air grilles associated with existing air handling unit F-1.

Revise 1.2.2 to read: TAB of all supply and return air grilles associated with existing air handling units F-1 and F-2.

Revise 1.2.3 to read: TAB of exhaust fan EF-3 and associated grilles.

Add: 1.2.4   Coordinate Work with all applicable sections including section 23 09 33 Electric and Electronic
Control for HVAC

Section 26 05 33   **HEAT TRACE:**

Revise 2.4 to read: Provide a heat trace temperature control system with the following functionality:
.1   Controller to turn heat trace off when the ambient exterior temperature is above 5
degrees Celsius.
.2   Controller to integrate a thermocouple and PID controls to maintain the temperature of
the condensate line at 15 degrees Celsius.

DRAWINGS

Replace: 699-2019_Drawing_S01-R0 with 699-2019_Addendum_1_Drawing_S01-R1

Replace: 699-2019_Drawing_S02-R0 with 699-2019_Addendum_1_Drawing_S02-R1

Replace: 699-2019_Drawing_M01-R0 with 699-2019_Addendum_1_Drawing_M01-R1

Replace: 699-2019_Drawing_M02-R0 with 699-2019_Addendum_1_Drawing_M02-R1

Replace: 699-2019_Drawing_M03-R0 with 699-2019_Addendum_1_Drawing_M03-R1

Add: 699-2019_Addendum_1_Drawing_M07-R0