

CONSTRUCTION NOTES:

1. LOCATION OF ALL EXISTING SEWER AND WATER LINES TO BE CONFIRMED IN THE FIELD.
2. SEWER AND WATER SERVICES SHOWN ON DRAWINGS ARE APPROXIMATE ONLY.
3. INSTALL NEW SEWER AND CATCHBASIN LEADS BY TRENCHLESS METHODS, UNLESS NOTED OTHERWISE.
4. CERTAIN CATCHBASINS REQUIRE EXTRA RISERS FOR FUTURE STREET RECONSTRUCTION. SEE INDIVIDUAL CATCHBASIN NOTES FOR INFORMATION.

GENERAL NOTES:

COLLEGIATE STREET

1. CHAINAGE IS ALONG WEST LIMIT OF COLLEGIATE STREET.
2. STATION 1+00 = NORTH LIMIT OF ASSINIBOINE AVENUE AND WEST LIMIT OF COLLEGIATE STREET.
3. SEE SPECIFICATIONS FOR DETAILED TEST HOLE INFORMATION.

ROSEBERRY STREET

1. CHAINAGE IS ALONG WEST LIMIT OF ROSEBERRY STREET.
2. STATION 1+00 = NORTH LIMIT OF ASSINIBOINE AVENUE AND WEST LIMIT OF ROSEBERRY STREET.
3. SEE SPECIFICATIONS FOR DETAILED TEST HOLE INFORMATION.





BID OPPORTUNITY No. 840-2019



KEY PLAN

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
Tetra Tech Canada Inc.
No. 6499

EXISTING	LEGEND-PLAN	PROPOSED	EXISTING	LEGEND-PLAN	PROPOSED	EXISTING	LEGEND-PLAN	PROPOSED
150 WM	WATERMAIN	150 WM		BEND			ANCHOR	
400 FM	FEEDERMAIN	400 FM		TEE			TREE	
300 LDS	LAND DRAINAGE SEWER	300 LDS		CURB STOP		15.240	LEGAL DIMENSION	
250 WWS	WASTEWATER SEWER	250 WWS		PLUG			SURVEY BAR	
300 CS	COMBINED SEWER	300 CS		MANHOLE			GAS	
200 FCM	FORCEMAIN	200 FCM		CATCHBASIN			HYDRO	
	JUNCTIONS			CURB INLET			MTS	
	HYDRANT		66	ADDRESS			CURB	
	VALVE			HYDRO POLE			SIDEWALK	
	REDUCER			LIGHT STANDARD			SHAFT LOCATION	

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE — DATE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE. BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M. CITY OF WINNIPEG 38-069
ELEV. 233.792m

NO.	REVISIONS	DATE	BY
00	ISSUED FOR TENDER	19.09.26	TRC

TETRA TECH

DESIGNED BY	ML	CHECKED BY	KJM, TRC
DRAWN BY	GMD	APPROVED BY	GS
HOR. SCALE:	1 250	RELEASED FOR CONSTRUCTION	
VERTICAL:	1 : 50		
DATE	2019-09-26	DATE	

PROVINCE OF MANITOBA
T.R. CHRISTIANSEN
Member
34138
REGISTERED PROFESSIONAL ENGINEER

CONSULTANT DRAWING NO.
1000120300-DWG-C0204

Winnipeg

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT

FERRY ROAD AND RIVERBEND
COMBINED SEWER RELIEF WORKS
CONTRACT 7A
COLLEGIATE STREET
ASSINIBOINE AVENUE TO 30m NORTH
ROSEBERRY STREET
ASSINIBOINE AVENUE TO 30m NORTH

CITY DRAWING NUMBER
LD-9537
SHEET 7 OF 12
C0707

X:\A-G\CITY OF WINNIPEG - WATER & WASTE DEPARTMENT - 00121000012 03.00 - FERRY ROAD\CONTRACT 7\CAD\PRODUCTION DRAWINGS\7\AC0707 1000120300-DWG-C0204 COLLEGIATE_ROSEBERRY.DWG 2019-09-26 9:43 AM