

PLAN

SCALE: 1:250

0 5 10 15m

CURVE TABLE				
CURVE	RADIUS	LENGTH	DELTA	TANGENT
C50	4.500	6.536	83°13'24"	3.997
C51	4.500	6.536	83°13'24"	3.997
C52	4.500	6.536	83°13'24"	3.997
C53	7.500	8.105	61°54'52"	4.499
C54	7.500	8.034	61°22'40"	4.451
C55	4.000	2.670	38°14'17"	1.387
C56	4.500	6.536	83°13'24"	3.997
C57	4.500	6.536	83°13'24"	3.997
C58	4.500	6.536	83°13'24"	3.997
C59	4.500	6.536	83°13'24"	3.997
C60	4.500	6.536	83°13'24"	3.997
C61	4.500	6.536	83°13'24"	3.997
C62	4.500	6.536	83°13'24"	3.997
C63	4.500	6.536	83°13'24"	3.997
C64	4.500	6.536	83°13'24"	3.997
C65	4.500	6.536	83°13'24"	3.997
C66	4.500	6.536	83°13'24"	3.997
C67	4.500	6.536	83°13'24"	3.997
C68	4.500	6.536	83°13'24"	3.997



PLAN

SCALE: 1:250

0 5 10 15m

WALL STREET - CONTROL LINE GEOMETRY										
NUMBER	LENGTH	RADIUS	DELTA	TANGENT	START STATION	NORTHING	EASTING	END STATION	NORTHING	EASTING
L200	2566.800				-0+234.397	8501.642	10205.173	2+332.403	11067.579	10271.724

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
MORRISON HERSHFIELD
No. 1736

TENDER No. 538-2020

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPR. U/G STRUCTURES COMMITTEE — DATE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

BM 37-59 ELEV 233.277 m — NE Cor. Erin St. & Richard Ave., Tblt. in W. Conc. foundation No. 1525 Erin St., 1 m N. & 0.7 m below brick of S.W. Cor. of Bldg.

No.	REVISIONS	YY/MM/DD	BY
B	ISSUED FOR TENDER	20/11/16	RPB
A	ISSUED FOR CLIENT REVIEW	20/08/05	RPB

MORRISON HERSHFIELD

DESIGNED BY	WRJ	CHECKED BY	RPB
DRAWN BY	DML	APPROVED BY	BWB
HOR SCALE / VERT SCALE	1:250	RELEASED FOR CONSTRUCTION	
DATE	20/08/05	DATE	

PROFESSIONAL'S SEAL
PRELIMINARY DRAWING
NOT TO BE USED FOR CONSTRUCTION

CONSULTANT FILE NAME
1903792-Wall-HG-04.dwg

Winnipeg

THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

2021-2022 REGIONAL STREET RENEWAL PROGRAM
WALL STREET RECONSTRUCTION
ST MATTHEWS AVE TO NOTRE DAME AVE

WALL STREET
HORIZONTAL GEOMETRY
STA 1+230 TO STA 1+490

CITY DRAWING NUMBER: P-3530-05
SHEET 5 OF 26
DRAWING NUMBER: 05

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

ISO A1 - 594mm x 841mm

P:\2019\190379200-2019-2023 Erin-Wall-Sargent Street\09_CAD\07 Sheets\Wall Street\1903792-Wall-HG-04.dwg Last Saved: 11/5/2020 12:54 PM by DLane Plotted: 11/17/2020 9:42 AM by Dave Lane